



US 20190229802A1

(19) **United States**

(12) **Patent Application Publication**
Panther et al.

(10) **Pub. No.: US 2019/0229802 A1**
(43) **Pub. Date: Jul. 25, 2019**

(54) **ADAPTIVE DATA TRANSFER USING
BLUETOOTH**

H04W 4/02 (2006.01)

A61B 5/00 (2006.01)

(71) Applicant: **Fitbit, Inc.**, San Francisco, CA (US)

H04B 5/00 (2006.01)

(72) Inventors: **Heiko Gernot Albert Panther**,
Oakland, CA (US); **James Park**,
Berkeley, CA (US)

H04B 5/02 (2006.01)

A61B 5/11 (2006.01)

(21) Appl. No.: **16/258,452**

(22) Filed: **Jan. 25, 2019**

(52) **U.S. Cl.**
CPC *H04B 7/26* (2013.01); *A61B 5/02416*
(2013.01); *A61B 5/02427* (2013.01); *A61B*
5/02433 (2013.01); *A61B 5/02438* (2013.01);
H04L 67/12 (2013.01); *A61B 5/4812*
(2013.01); *A61B 5/0002* (2013.01); *H04B*
5/0031 (2013.01); *H04B 5/02* (2013.01);
A61B 5/1123 (2013.01); *H04W 4/027*
(2013.01)

Related U.S. Application Data

(60) Continuation of application No. 15/465,411, filed on Mar. 21, 2017, now Pat. No. 10,218,433, which is a division of application No. 14/290,902, filed on May 29, 2014, now Pat. No. 9,641,239, which is a continuation-in-part of application No. 13/924,784, filed on Jun. 24, 2013, now Pat. No. 8,954,135.


(60) Provisional application No. 61/948,468, filed on Mar. 5, 2014, provisional application No. 61/752,826, filed on Jan. 15, 2013, provisional application No. 61/662,961, filed on Jun. 22, 2012, provisional application No. 61/830,600, filed on Jun. 3, 2013.

Publication Classification

(51) **Int. Cl.**
H04B 7/26 (2006.01)
A61B 5/024 (2006.01)

(57) **ABSTRACT**

Biometric monitoring devices, including various technologies that may be implemented in such devices, are discussed herein. Additionally, techniques, systems, and apparatuses are discussed herein for utilizing two different Bluetooth communications interfaces, one that provides Bluetooth classic (base rate/enhanced data rate) communications functionality and one that provides Bluetooth low-energy communications functionality, in a common device. The techniques, systems, and apparatuses may elect to use a particular Bluetooth interface based on various criteria.






Figure 1




Figure 2A




Figure 2B




Figure 2C




Figure 3A




Figure 3B




Figure 3C




Figure 4A




Figure 4B

Protrusion Detail




Figure 4C




Figure 5




Figure 6A




Figure 6B




Figure 7




Figure 8




Figure 9







Figure 10






Figure 11D




Figure 11E




Figure 11F




Figure 11G




Figure 12A




Figure 12B




Figure 12C




Figure 13A




Figure 13B




Figure 14A (Prior Art)




Figure 14B




Figure 14C




Figure 14D




Figure 15A




Figure 15B




Figure 15C




Figure 15D




Figure 16A




Figure 16B




Figure 16C




Figure 16D




Figure 16E




Figure 16F




Figure 16G




Figure 16H




Figure 16I




Figure 16J




Figure 17




Figure 18




Figure 19




Figure 20




Figure 21




Figure 22




Figure 23




Figure 24




Figure 25




Figure 26




Figure 27




Figure 28




Figure 29

ADAPTIVE DATA TRANSFER USING BLUETOOTH

CROSS REFERENCE TO RELATED APPLICATIONS

[0001] This application is a continuation application of U.S. patent application Ser. No. 15/465,411, titled "ADAPTIVE DATA TRANSFER USING BLUETOOTH" and filed on Mar. 21, 2017 (Attorney Docket No. FTBTP002X1BD1US), which is a divisional of U.S. patent application Ser. No. 14/290,902, titled "ADAPTIVE DATA TRANSFER USING BLUETOOTH" and filed on May 29, 2014 (Attorney Docket No. FTBTP002X1BUS), which is a continuation-in-part of U.S. patent application Ser. No. 13/924,784, titled "PORTABLE BIOMETRIC MONITORING DEVICES AND METHODS OF OPERATING SAME" and filed on Jun. 24, 2013 (Attorney Docket No. FTBTP002US), which claims benefit of priority under 35 U.S.C. § 119(e) to U.S. Provisional Patent Application Nos. 61/662,961, titled "WIRELESS PERSONAL BIOMETRICS MONITOR" and filed on Jun. 22, 2012 (Attorney Docket No. FTBTP002PUS) and 61/752,826, titled "PORTABLE MONITORING DEVICES AND METHODS OF OPERATING SAME" and filed on Jan. 15, 2013 (Attorney Docket No. FTBTP002P2US); this application also claims benefit of priority under 35 U.S.C. § 119(e) to U.S. Provisional Patent Application Nos. 61/830,600, titled "PORTABLE MONITORING DEVICES AND METHODS OF OPERATING SAME" and filed on Jun. 3, 2013 (Attorney Docket No. FTBTP002X1PUS), and 61/948,468, titled "ADAPTIVE DATA TRANSFER USING BLUETOOTH" and filed on Mar. 5, 2014 (Attorney Docket No. FTBTP002X1BPUS), all of which are hereby incorporated by reference herein in their entireties.

BACKGROUND

[0002] Recent consumer interest in personal health has led to a variety of personal health monitoring devices being offered on the market. Such devices, until recently, tended to be complicated to use and were typically designed for use with one activity, e.g., bicycle trip computers.

[0003] Recent advances in sensor, electronics, and power source miniaturization have allowed the size of personal health monitoring devices, also referred to herein as "biometric tracking" or "biometric monitoring" devices, to be offered in extremely small sizes that were previously impractical. For example, the Fitbit Ultra is a biometric monitoring device that is approximately 2" long, 0.75" wide, and 0.5" deep; it has a pixelated display, battery, sensors, wireless communications capability, power source, and interface button, as well as an integrated clip for attaching the device to a pocket or other portion of clothing, packaged within this small volume.

[0004] Discussed herein are various embodiments of biometric monitoring devices and technologies that may be used therein (and in other devices, in some instances, not necessarily providing biometric tracking functionality).

SUMMARY

[0005] Details of one or more implementations of the subject matter described in this specification are set forth in the accompanying drawings and the description below. Other features, aspects, and advantages will become appar-

ent from the description, the drawings, and the claims. Note that the relative dimensions of the following figures may not be drawn to scale unless specifically indicated as being scaled drawings.

[0006] In some implementations, an apparatus is provided that includes a first Bluetooth communications interface configured to provide communications via the Bluetooth Base Rate/Enhanced Data Rate (BR/EDR) protocol and a second Bluetooth communications interface configured to provide Bluetooth communications via the Bluetooth Low-Energy (BLE) protocol. The apparatus may also include a controller including at least one processor and a memory. The at least one processor, the memory, the first Bluetooth communications interface, and the second Bluetooth communications interface may be communicatively connected and the memory may store instructions for controlling the at least one processor to: a) establish a first Bluetooth communications connection with a remote device external to the apparatus via the first Bluetooth communications interface, b) establish a second Bluetooth communications connection with the remote device via the second Bluetooth communications interface, c) determine whether to utilize the first Bluetooth communications connection or the second Bluetooth communications connection to transmit first data between the apparatus and the remote device according, at least in part, to information selected from the group consisting of: information obtained from one or more sensors in the apparatus, information obtained in association with the first Bluetooth communications connection, information obtained in association with the second Bluetooth communications connection, and information describing the first data, and d) utilize the first Bluetooth communications connection or the second Bluetooth communications connection as determined in (c) to transmit the first data between the apparatus and the remote device.

[0007] In some such implementations of the apparatus, the memory may store further instructions for controlling the at least one processor to deactivate the first Bluetooth communications connection when the first Bluetooth communications connection is not used to transmit data between the apparatus and the remote device and while the second Bluetooth communications connection is still established between the apparatus and the remote device.

[0008] In some implementations of the apparatus, the information describing the first data may indicate that the first data is an application or part of an application that is to be installed on the apparatus, and the memory may store further instructions for controlling the at least one processor to utilize the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is an application or part of an application that is to be installed on the apparatus.

[0009] In some implementations of the apparatus, the information describing the first data may indicate that the first data is data collected by one or more sensors of the apparatus and the memory may store further instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is data collected by the one or more sensors on the apparatus.

[0010] In some implementations of the apparatus, the one or more sensors of the apparatus may include a battery charge level sensor and the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information obtained from the one or more sensors in the apparatus includes battery charge level data from the battery charge level sensor that indicates that a charge level of a battery in the apparatus is below a first threshold.

[0011] In some implementations of the apparatus, the one or more sensors in the apparatus may include at least one motion sensor and the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors includes information indicating that the apparatus is substantially stationary with respect to a global frame of reference.

[0012] In some implementations of the apparatus, the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors indicates that the apparatus is monitoring a sleep state of a wearer of the apparatus.

[0013] In some implementations of the apparatus, the information describing the first data may indicate that the first data is to be sent from the apparatus to the remote device and the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is to be sent from the apparatus to the remote device.

[0014] In some implementations of the apparatus, the information describing the first data may indicate that the first data is to be received by the apparatus from the remote device and the instructions for (c) may include instructions for controlling the at least one processor to utilize the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is to be received by the apparatus from the remote device.

[0015] In some implementations of the apparatus, the information obtained in association with the first Bluetooth communications connection and/or the information obtained in association with the second Bluetooth communications connection may include information describing the remote device and the instructions for (c) may include instructions for controlling the at least one processor to utilize either the first Bluetooth communications connection or the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device depending, at least in part, on the information describing the remote device.

[0016] In some implementations of the apparatus, the information describing the remote device may indicate that the remote device is a cell phone or a smart phone and the

instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the remote device indicates that the remote device is a cell phone or a smart phone.

[0017] In some implementations of the apparatus, the one or more sensors in the apparatus may include a Bluetooth receiver and the information from the one or more sensors may include information from the Bluetooth receiver indicating that a vehicle-mounted Bluetooth device is within Bluetooth communications range of the apparatus and has a signal strength that meets or exceeds a predefined threshold.

[0018] In some implementations of the apparatus, the information obtained in association with the second Bluetooth communications connection may include information indicating that the second Bluetooth communications connection has not been interrupted for a first time period greater than a first threshold time period and the instructions for (c) may include instructions for controlling the at least one processor to utilize the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the first time period is less than the first threshold time period.

[0019] In some implementations, a method may be provided. The method may include: a) establishing a first Bluetooth communications connection between an apparatus and a remote device external to the apparatus via the first Bluetooth communications interface; b) establishing a second Bluetooth communications connection between the apparatus and the remote device via the second Bluetooth communications interface; c) determining whether to utilize the first Bluetooth communications connection or the second Bluetooth communications connection to transmit first data between the apparatus and the remote device according, at least in part, to information selected from the group consisting of: information obtained from one or more sensors in the apparatus, information obtained in association with the first Bluetooth communications connection, information obtained in association with the second Bluetooth communications connection, and information describing the first data; and d) utilizing the first Bluetooth communications connection or the second Bluetooth communications connection as determined in (c) to transmit the first data between the apparatus and the remote device.

[0020] Some implementations of the method may further include deactivating the first Bluetooth communications connection when the first Bluetooth communications connection is not used to transmit data between the apparatus and the remote device and while maintaining the second Bluetooth communications connection between the apparatus and the remote device.

[0021] In some implementations of the method, the information describing the first data may indicate that the first data is an application or part of an application that is to be installed on the apparatus, and the method may further include utilizing the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is an application or part of an application that is to be installed on the apparatus.

[0022] In some implementations of the method, the information describing the first data may indicate that the first

data is data collected by one or more sensors of the apparatus, and the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is data collected by the one or more sensors on the apparatus.

[0023] In some implementations of the method, the one or more sensors of the apparatus may include a battery charge level sensor and the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information obtained from the one or more sensors in the apparatus includes battery charge level data from the battery charge level sensor that indicates that a charge level of a battery in the apparatus is below a first threshold.

[0024] In some implementations of the method, the one or more sensors in the apparatus may include at least one motion sensor the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors includes information indicating that the apparatus is substantially stationary with respect to a global frame of reference.

[0025] In some implementations of the method, the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors indicates that the apparatus is monitoring a sleep state of a wearer of the apparatus.

[0026] In some implementations of the method, the information describing the first data may indicate that the first data is to be sent from the apparatus to the remote device and the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is to be sent from the apparatus to the remote device.

[0027] In some implementations of the method, the information describing the first data may indicate that the first data is to be received by the apparatus from the remote device and the method may further include utilizing the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is to be received by the apparatus from the remote device.

[0028] In some implementations of the method, the information obtained in association with the first Bluetooth communications connection and/or the information obtained in association with the second Bluetooth communications connection may include information describing the remote device and the method may further include utilizing either the first Bluetooth communications connection or the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device depending, at least in part, on the information describing the remote device.

[0029] In some such implementations of the method, the information describing the remote device may indicate that

the remote device is a cell phone or a smart phone and the method may further include utilizing the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the remote device indicates that the remote device is a cell phone or a smart phone.

[0030] In some implementations of the method, the one or more sensors in the apparatus may include a Bluetooth receiver and the information from the one or more sensors may include information from the Bluetooth receiver indicating that a vehicle-mounted Bluetooth device is within Bluetooth communications range of the apparatus and has a signal strength that meets or exceeds a predefined threshold.

[0031] In some implementations of the method, the information obtained in association with the second Bluetooth communications connection may include information indicating that the second Bluetooth communications connection has not been interrupted for a first time period greater than a first threshold time period and the method may further include utilizing the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the first time period is less than the first threshold time period.

[0032] In some implementations, a non-transitory, machine-readable storage medium may be provided. The non-transitory, machine-readable storage medium may store computer-executable instructions for controlling at least one processor communicatively connected with a first Bluetooth communications interface and a second Bluetooth communications interface in an apparatus. The first Bluetooth communications interface may be configured to provide communications via the Bluetooth Base Rate/Enhanced Data Rate (BR/EDR) protocol and the second Bluetooth communications interface may be configured to provide Bluetooth communications via the Bluetooth Low-Energy (BLE) protocol. The instructions may include instructions to: a) establish a first Bluetooth communications connection with a remote device external to the apparatus via the first Bluetooth communications interface, b) establish a second Bluetooth communications connection with the remote device via the second Bluetooth communications interface, c) determine whether to utilize the first Bluetooth communications connection or the second Bluetooth communications connection to transmit first data between the apparatus and the remote device according, at least in part, to information selected from the group consisting of: information obtained from one or more sensors in the apparatus, information obtained in association with the first Bluetooth communications connection, information obtained in association with the second Bluetooth communications connection, and information describing the first data, and d) utilize the first Bluetooth communications connection or the second Bluetooth communications connection as determined in (c) to transmit the first data between the apparatus and the remote device.

[0033] In some such implementations, the storage medium may store further instructions for controlling the at least one processor to deactivate the first Bluetooth communications connection when the first Bluetooth communications connection is not used to transmit data between the apparatus and the remote device and while the second Bluetooth communications connection is still established between the apparatus and the remote device.

[0034] In some implementations of the storage medium, the information describing the first data may indicate that the first data is an application or part of an application that is to be installed on the apparatus, and the storage medium may store further instructions for controlling the at least one processor to utilize the first Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is an application or part of an application that is to be installed on the apparatus.

[0035] In some implementations of the storage medium, the information describing the first data may indicate that the first data is data collected by one or more sensors of the apparatus and the storage medium may store further instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information describing the first data indicates that the first data is data collected by the one or more sensors on the apparatus.

[0036] In some implementations of the storage medium, the one or more sensors of the apparatus may include a battery charge level sensor and the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information obtained from the one or more sensors in the apparatus includes battery charge level data from the battery charge level sensor that indicates that a charge level of a battery in the apparatus is below a first threshold.

[0037] In some implementations of the storage medium, the one or more sensors in the apparatus may include at least one motion sensor and the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors includes information indicating that the apparatus is substantially stationary with respect to a global frame of reference.

[0038] In some implementations of the storage medium, the instructions for (c) may include instructions for controlling the at least one processor to utilize the second Bluetooth communications connection to transmit the first data between the apparatus and the remote device when, at least in part, the information from the one or more sensors indicates that the apparatus is monitoring a sleep state of a wearer of the apparatus.

[0039] These and other implementations are described in further detail with reference to the Figures and the detailed description below.

BRIEF DESCRIPTION OF DRAWINGS

[0040] The various implementations disclosed herein are illustrated by way of example, and not by way of limitation, in the figures of the accompanying drawings, in which like reference numerals may refer to similar elements.

[0041] FIG. 1 illustrates an example portable monitoring device which enables user interaction via a user interface.

[0042] FIG. 2A illustrates an example portable monitoring device which may be secured to the user through the use of a band.

[0043] FIG. 2B provides a view of the example portable monitoring device of FIG. 2A which shows the skin-facing portion of the device.

[0044] FIG. 2C provides a cross-sectional view of the portable monitoring device of FIG. 2A.

[0045] FIG. 3A provides a cross sectional view of a sensor protrusion of an example portable monitoring device.

[0046] FIG. 3B depicts a cross sectional view of a sensor protrusion of an example portable monitoring device; this protrusion is similar to that presented in FIG. 3A with the exception that the light sources and photodetector are placed on a flat and/or rigid PCB.

[0047] FIG. 3C provides another cross-sectional view of an example PPG sensor implementation.

[0048] FIG. 4A illustrates an example of one potential PPG light source and photodetector geometry.

[0049] FIGS. 4B and 4C illustrate examples of a PPG sensor having a photodetector and two LED light sources.

[0050] FIG. 5 illustrates an example of an optimized PPG detector that has a protrusion with curved sides so as not to discomfort the user.

[0051] FIG. 6A illustrates an example of a portable monitoring device having a band; optical sensors and light emitters may be placed on the band.

[0052] FIG. 6B illustrates an example of a portable biometric monitoring device having a display and wristband. Additionally, optical PPG (e.g., heart rate) detection sensors and/or emitters may be located on the side of the biometric monitoring device. In one embodiment, these may be located in side-mounted buttons.

[0053] FIG. 7 depicts a user pressing the side of a portable biometric monitoring device to take a heart rate measurement from a side-mounted optical heart rate detection sensor. The display of the biometric monitoring device may show whether or not the heart rate has been detected and/or display the user's heart rate.

[0054] FIG. 8 illustrates functionality of an example biometric monitoring device smart alarm feature.

[0055] FIG. 9 illustrates an example of a portable biometric monitoring device that changes how it detects a user's heart rate based on how much movement the biometric monitoring device is experiencing.

[0056] FIG. 10 illustrates an example of a portable biometric monitoring device that has a bicycle application on it that may display bicycle speed and/or pedaling cadence, among other metrics.

[0057] FIG. 11A illustrates an example block diagram of a PPG sensor which has a light source, light detector, ADC, processor, DAC/GPIOs, and light source intensity and on/off control.

[0058] FIG. 11B illustrates an example block diagram of a PPG sensor that is similar to that of FIG. 11A which additionally uses a sample-and-hold circuit as well as analog signal conditioning.

[0059] FIG. 11C illustrates an example block diagram of a PPG sensor that is similar to that of FIG. 11A which additionally uses a sample-and-hold circuit.

[0060] FIG. 11D illustrates an example block diagram of a PPG sensor having multiple switchable light sources and detectors, light source intensity/on and off control, and signal conditioning circuitry.

[0061] FIG. 11E illustrates an example block diagram of a PPG sensor which uses synchronous detection. To perform this type of PPG detection, it has a demodulator.

[0062] FIG. 11F illustrates an example block diagram of a PPG sensor which, in addition to the features of the sensor illustrated in FIG. 11A, has a differential amplifier.

[0063] FIG. 11G illustrates an example block diagram of a PPG sensor which has the features of the PPG sensors shown in FIGS. 11A-KKF.

[0064] FIG. 12A illustrates an example of a portable biometric monitoring device having a heart rate or PPG sensor, motion sensor, display, vibromotor, and communication circuitry which is connected to a processor.

[0065] FIG. 12B illustrates an example of a portable biometric monitoring device having a heart rate or PPG sensor, motion sensor, display, vibromotor, location sensor, altitude sensor, skin conductance/wet sensor and communication circuitry which is connected to a processor.

[0066] FIG. 12C illustrates an example of a portable biometric monitoring device having physiological sensors, environmental sensors, and location sensors connected to a processor.

[0067] FIG. 13A illustrates an example of the use of a motion signal and an optical PPG signal to measure a heart rate.

[0068] FIG. 13B illustrates another example of the use of a motion signal and an optical PPG signal to measure heart rate.

[0069] FIG. 14A illustrates an example of a sensor which has an analog connection to a sensor processor.

[0070] FIG. 14B illustrates an example of a sensor which has an analog connection to a sensor processor which, in turn, has a digital connection to an application processor.

[0071] FIG. 14C illustrates an example of a sensor device which has one or multiple sensors connected to an application processor.

[0072] FIG. 14D illustrates an example of a sensor device which has one or multiple sensors connected to sensor processors which, in turn, are connected to an application processor.

[0073] FIG. 15A illustrates an example of a swim detection algorithm using a sequential algorithm flow.

[0074] FIG. 15B illustrates an example of a swim detection algorithm which uses a parallel algorithm flow.

[0075] FIG. 15C illustrates an example of a swim detection algorithm which uses a hybrid of sequential and parallel algorithm flow.

[0076] FIG. 15D illustrates an example of a swim detection algorithm which uses a hybrid of sequential and parallel algorithm flow.

[0077] FIG. 16A illustrates an example schematic of a sample-and-hold circuit and differential/instrumentation amplifier which may be used in PPG sensing.

[0078] FIG. 16B illustrates an example schematic of a circuit for a PPG sensor using a controlled current source to offset “bias” current prior to a transimpedance amplifier

[0079] FIG. 16C illustrates an example schematic of a circuit for a PPG sensor using a sample-and-hold circuit for current feedback applied to photodiode (prior to a transimpedance amplifier).

[0080] FIG. 16D illustrates an example schematic of a circuit for a PPG sensor using a differential/instrumentation amplifier with ambient light cancellation functionality.

[0081] FIG. 16E illustrates an example schematic of a circuit for a PPG sensor using a photodiode offset current generated dynamically by a DAC.

[0082] FIG. 16F illustrates an example schematic of a circuit for a PPG sensor using a photodiode offset current generated dynamically by a controlled voltage source.

[0083] FIG. 16G illustrates an example schematic of a circuit for a PPG sensor including ambient light removal functionality using a “switched capacitor” method.

[0084] FIG. 16H illustrates an example schematic of a circuit for a PPG sensor that uses a photodiode offset current generated by a constant current source (this may also be done using a constant voltage source and a resistor).

[0085] FIG. 16I illustrates an example schematic of a circuit for a PPG sensor that includes ambient light removal functionality and differencing between consecutive samples.

[0086] FIG. 16J illustrates an example schematic of a circuit for ambient light removal and differencing between consecutive samples.

[0087] FIG. 17 depicts a simplified block schematic of a device with both Bluetooth base rate/enhanced data rate and Bluetooth low-energy capability.

[0088] FIG. 18 depicts a flow diagram of one example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device.

[0089] FIG. 19 depicts a flow diagram of another example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device.

[0090] FIG. 20 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the data to be transmitted is application data.

[0091] FIG. 21 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the data to be transmitted is data collected from one or more sensors of the common device.

[0092] FIG. 22 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on the battery charge level of the common device.

[0093] FIG. 23 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the device is stationary or in motion.

[0094] FIG. 24 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether a user of the device appears to be asleep.

[0095] FIG. 25 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether data is being sent from the common device to a remote device.

[0096] FIG. 26 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on what type of remote device is in communication with the common device.

[0097] FIG. 27 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether a vehicle-mounted Bluetooth device is in range.

[0098] FIG. 28 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate

or Bluetooth low-energy capability in a common device based on the length of time since one or more of the Bluetooth connections was most recently lost.

[0099] FIG. 29 depicts a flow diagram of an example technique involving using several criteria to determine whether Bluetooth base rate/enhanced data rate capability or Bluetooth low-energy capability in a common device should be used to transmit data.

DETAILED DESCRIPTION

[0100] This disclosure is directed at biometric monitoring devices (which may also be referred to herein and in any references incorporated by reference as “biometric tracking devices,” “personal health monitoring devices,” “portable monitoring devices,” “portable biometric monitoring devices,” “biometric monitoring devices,” or the like), which may be generally described as wearable devices, typically of a small size, that are designed to be worn relatively continuously by a person. When worn, such biometric monitoring devices gather data regarding activities performed by the wearer or the wearer’s physiological state. Such data may include data representative of the ambient environment around the wearer or the wearer’s interaction with the environment, e.g., motion data regarding the wearer’s movements, ambient light, ambient noise, air quality, etc., as well as physiological data obtained by measuring various physiological characteristics of the wearer, e.g., heart rate, perspiration levels, etc.

[0101] Biometric monitoring devices, as mentioned above, are typically small in size so as to be unobtrusive for the wearer. Fitbit offers several varieties of biometric monitoring devices that are all quite small and very light, e.g., the Fitbit Flex is a wristband with an insertable biometric monitoring device that is about 0.5" wide by 1.3" long by 0.25" thick. Biometric monitoring devices are typically designed to be able to be worn without discomfort for long periods of time and to not interfere with normal daily activity.

[0102] In some cases, a biometric monitoring device may leverage other devices external to the biometric monitoring device, e.g., an external heart rate monitor in the form of an EKG sensor on a chest strap may be used to obtain heart rate data or a GPS receiver in a smartphone may be used to obtain position data. In such cases, the biometric monitoring device may communicate with these external devices using wired or wireless communications connections. The concepts disclosed and discussed herein may be applied to both stand-alone biometric monitoring devices as well as biometric monitoring devices that leverage sensors or functionality provided in external devices, e.g., external sensors, sensors or functionality provided by smartphones, etc.

[0103] In general, the concepts discussed herein may be implemented in stand-alone biometric monitoring devices as well as, when appropriate, biometric monitoring devices that leverage external devices.

[0104] It is to be understood that while the concepts and discussion included herein are presented in the context of biometric monitoring devices, these concepts may also be applied in other contexts as well if the appropriate hardware is available. For example, many modern smartphones include motion sensors, such as accelerometers, that are normally included in biometric monitoring devices, and the concepts discussed herein may, if appropriate hardware is available in a device, be implemented in that device. In

effect, this may be viewed as turning the smartphone into some form of biometric monitoring device (although one that is larger than a typical biometric monitoring device and that may not be worn in the same manner). Such implementations are also to be understood to be within the scope of this disclosure.

[0105] The functionality discussed herein may be provided using a number of different approaches. For example, in some implementations a processor may be controlled by computer-executable instructions stored in memory so as to provide functionality such as is described herein. In other implementations, such functionality may be provided in the form of an electrical circuit. In yet other implementations, such functionality may be provided by a processor or processors controlled by computer-executable instructions stored in a memory coupled with one or more specially-designed electrical circuits. Various examples of hardware that may be used to implement the concepts outlined herein include, but are not limited to, application specific integrated circuits (ASICs), field-programmable gate arrays (FPGAs), and general-purpose microprocessors coupled with memory that stores executable instructions for controlling the general-purpose microprocessors.

[0106] Standalone biometric monitoring devices may be provided in a number of form factors and may be designed to be worn in a variety of ways. In some implementations, a biometric monitoring device may be designed to be insertable into a wearable case or into multiple, different wearable cases, e.g., a wristband case, a belt-clip case, a pendant case, a case configured to be attached to a piece of exercise equipment such as a bicycle, etc. Such implementations are described in more detail in, for example, U.S. patent application Ser. No. 14/029,764, filed Sep. 17, 2013, which is hereby incorporated by reference for such purpose. In other implementations, a biometric monitoring device may be designed to be worn in only one manner, e.g., a biometric monitoring device that is integrated into a wristband in a non-removable manner may be intended to be worn only on a person’s wrist (or perhaps ankle).

[0107] Portable biometric monitoring devices according to embodiments and implementations described herein may have shapes and sizes adapted for coupling to (e.g., secured to, worn, borne by, etc.) the body or clothing of a user. An example of a portable biometric monitoring device is shown in FIG. 1; the example portable monitoring device may have a user interface, processor, biometric sensor(s), memory, environmental sensor(s) and/or a wireless transceiver which may communicate with a client and/or server. An example of a wrist-worn portable biometric monitoring device is shown in FIGS. 2A through 2C. This device may have a display, button(s), electronics package, and/or an attachment band. The attachment band may be secured to the user through the use of hooks and loops (e.g., Velcro), a clasp, and/or a band having memory of its shape, e.g., through the use of a spring metal band. In FIG. 2B, a sensor protrusion and recess for mating a charger and/or data transmission cable can be seen. In FIG. 2C, a cross-section through the electronics package is shown. Of note are the sensor protrusion, main PCB board, and display.

[0108] Portable biometric monitoring devices may collect one or more types of physiological and/or environmental data from embedded sensors and/or external devices and communicate or relay such information to other devices, including devices capable of serving as an Internet-access-

sible data sources, thus permitting the collected data to be viewed, for example, using a web browser or network-based application. For example, while the user is wearing a biometric monitoring device, the biometric monitoring device may calculate and store the user's step count using one or more biometric sensors. The biometric monitoring device may then transmit data representative of the user's step count to an account on a web service (e.g., www.fitbit.com), computer, mobile phone, or health station where the data may be stored, processed, and visualized by the user. Indeed, the biometric monitoring device may measure or calculate a plurality of other physiological metrics in addition to, or in place of, the user's step count. These include, but are not limited to, energy expenditure, e.g., calorie burn, floors climbed and/or descended, heart rate, heart rate variability, heart rate recovery, location and/or heading, e.g., through GPS, GLONASS, or a similar system, elevation, ambulatory speed and/or distance traveled, swimming lap count, swimming stroke type and count detected, bicycle distance and/or speed, blood pressure, blood glucose, skin conduction, skin and/or body temperature, muscle state measured via electromyography, brain activity as measured by electroencephalography, weight, body fat, caloric intake, nutritional intake from food, medication intake, sleep periods, e.g., clock time, sleep phases, sleep quality and/or duration, pH levels, hydration levels, respiration rate, and other physiological metrics. The biometric monitoring device may also measure or calculate metrics related to the environment around the user such as barometric pressure, weather conditions (e.g., temperature, humidity, pollen count, air quality, rain/snow conditions, wind speed), light exposure (e.g., ambient light, UV light exposure, time and/or duration spent in darkness), noise exposure, radiation exposure, and magnetic field. Furthermore, the biometric monitoring device or the system collating the data streams from the biometric monitoring device may calculate metrics derived from such data. For example, the device or system may calculate the user's stress and/or relaxation levels through a combination

of heart rate variability, skin conduction, noise pollution, and sleep quality. In another example, the device or system may determine the efficacy of a medical intervention, e.g., medication, through the combination of medication intake, sleep data, and/or activity data. In yet another example, the biometric monitoring device or system may determine the efficacy of an allergy medication through the combination of pollen data, medication intake, sleep and/or activity data. These examples are provided for illustration only and are not intended to be limiting or exhaustive. Further embodiments and implementations of sensor devices may be found in U.S. patent application Ser. No. 13/156,304, titled "Portable Biometric Monitoring Devices and Methods of Operating Same" filed Jun. 8, 2011 and U.S. Patent Application 61/680,230, titled "Fitbit Tracker" filed Aug. 6, 2012, which are both hereby incorporated herein by reference in their entireties.

Physiological Sensors

[0109] Biometric monitoring devices as discussed herein may use one, some or all of the following sensors to acquire physiological data, including, but not limited to, the physiological data outlined in the table below. All combinations and permutations of physiological sensors and/or physiological data are intended to fall within the scope of this disclosure. Biometric monitoring devices may include but are not limited to types of one, some, or all of the sensors specified below for the acquisition of corresponding physiological data; indeed, other type(s) of sensors may also or alternatively be employed to acquire the corresponding physiological data, and such other types of sensors are also intended to fall within the scope of the present disclosure. Additionally, the biometric monitoring device may derive the physiological data from the corresponding sensor output data, but is not limited to the number or types of physiological data that it could derive from said sensor.

Physiological Sensors	Physiological data acquired
Optical Reflectometer	Heart Rate, Heart Rate Variability
Example Sensors:	SpO ₂ (Saturation of Peripheral Oxygen)
Light emitter and receiver	Respiration
Multi or single LED and photo diode arrangement	Stress
Wavelength tuned for specific physiological signals	Blood pressure
Synchronous detection/amplitude modulation	Arterial Stiffness
	Blood glucose levels
	Blood volume
	Heart rate recovery
	Cardiac health
Motion Detector	Activity level detection
Example Sensors:	Sitting/standing detection
Inertial sensors, Gyroscopic sensors, and/or Accelerometers	Fall detection
GPS	
Skin Temperature	Stress
EMG (eletromyographic sensor)	Muscle tension
EKG or ECG (electrocardiographic sensor)	Heart Rate
Example Sensors:	Heart Rate Variability
Single-lead ECG or EKG	Heart Rate Recovery
Dual-lead ECG or EKG	Stress
	Cardiac health
Magnetometer	Activity level based on rotation
Laser Doppler	
Power Meter	
Ultrasonic Sensor	Blood flow
Audio Sensor	Heart Rate
	Heart Rate Variability

-continued

Physiological Sensors	Physiological data acquired
	Heart Rate Recovery
	Laugh detection
	Respiration
	Respiration type, e.g., snoring, breathing, breathing problems (such as sleep apnea)
	User's voice
Strain gauge	Heart Rate
Example:	Heart Rate Variability
In a wrist band	Stress
Wet/Immersion Sensor	Stress
Example Sensor:	Swimming detection
Galvanic skin response	Shower detection

[0110] In one example embodiment, the biometric monitoring device may include an optical sensor to detect, sense, sample and/or generate data that may be used to determine information representative of, for example, stress (or level thereof), blood pressure, and/or heart rate of a user. (See, for example, FIGS. 2A through 3C and 11A through KKG). In such embodiments, the biometric monitoring device may include an optical sensor having one or more light sources (LED, laser, etc.) to emit or output light into the user's body, as well as light detectors (photodiodes, phototransistors, etc.) to sample, measure and/or detect a response or reflection of such light from the user's body and provide data used to determine data that is representative of stress (or level thereof), blood pressure, and/or heart rate of a user (e.g., such as by using photoplethysmography).

[0111] In one example embodiment, a user's heart rate measurement may be triggered by criteria determined by one or more sensors (or processing circuitry connected to them). For instance, when data from a motion sensor(s) indicates a period of stillness or of little motion, the biometric monitoring device may trigger, acquire, and/or obtain a heart rate measurement or data. (See, for example, FIGS. 9, 12A, and 12B).

[0112] FIG. 12A illustrates an example of a portable biometric monitoring device having a heart rate or PPG sensor, motion sensor, display, vibromotor, and communication circuitry which is connected to a processor.

[0113] FIG. 12B illustrates an example of a portable biometric monitoring device having a heart rate or PPG sensor, motion sensor, display, vibromotor, location sensor, altitude sensor, skin conductance/wet sensor and communication circuitry which is connected to a processor.

[0114] In one embodiment, when the motion sensor(s) indicate user activity or motion (for example, motion that is not suitable or optimum to trigger, acquire, and/or obtain desired heart rate measurement or data (for example, data used to determine a user's resting heart rate)), the biometric monitoring device and/or the sensor(s) employed to acquire and/or obtain a desired heart rate measurement or data may be placed in, or remain in, a low power state. Since heart rate measurements taken during motion may be less reliable and may be corrupted by motion artifacts, it may be desirable to decrease the frequency with which heart rate data samples are collected (thus decreasing power usage) when the biometric monitoring device is in motion.

[0115] In another embodiment, a biometric monitoring device may employ data (for example, from one or more motion sensors) indicative of user activity or motion to adjust or modify characteristics of triggering, acquiring,

and/or obtaining desired heart rate measurements or data (for example, to improve robustness to motion artifact). For instance, if the biometric monitoring device receives data indicative of user activity or motion, the biometric monitoring device may adjust or modify the sampling rate and/or resolution mode of sensors used to acquire heart rate data (for example, where the amount of user motion exceeds a certain threshold, the biometric monitoring device may increase the sampling rate and/or increase the sampling resolution mode of sensors employed to acquire heart rate measurement or data.) Moreover, the biometric monitoring device may adjust or modify the sampling rate and/or resolution mode of the motion sensor(s) during such periods of user activity or motion (for example, periods where the amount of user motion exceeds a certain threshold). In this way, when the biometric monitoring device determines or detects such user activity or motion, the biometric monitoring device may place the motion sensor(s) into a higher sampling rate and/or higher sampling resolution mode to, for example, enable more accurate adaptive filtering of the heart rate signal. (See, for example, FIG. 9).

[0116] FIG. 9 illustrates an example of a portable biometric monitoring device that changes how it detects a user's heart rate based on how much movement the biometric monitoring device is experiencing. In the case where there is motion detected (e.g., through the use of an accelerometer), the user may be considered by the biometric monitoring device to be "active" and high-sampling-rate heart rate detection may occur to reduce motion artifacts in the heart rate measurement. This data may be saved and/or displayed. In the case that the user is determined by the biometric monitoring device to not be moving (or to be relatively sedentary), low-sampling-rate heart rate detection (which does not consume as much power) may be adequate to measure a heart rate and may thus be used.

[0117] Notably, where a biometric monitoring device employs optical techniques to acquire heart rate measurements or data, e.g., by using photoplethysmography, a motion signal may be employed to determine or establish a particular approach or technique to data acquisition or measurement by the heart rate sensor (e.g., synchronous detection rather than a non-amplitude-modulated approach) and/or analysis thereof. (See, for example, FIG. 11E). In this way, the data which is indicative of the amount of user motion or activity may cause the biometric monitoring device to establish or adjust the type or technique of data acquisition or measurement used by an optical heart rate sensor or sensors.

[0118] For example, in one embodiment, a biometric monitoring device (or heart-rate measurement technique as disclosed herein may adjust and/or reduce the sampling rate of optical heart rate sampling when motion detector circuitry detects or determines that the biometric monitoring device wearer's motion is below a threshold (for example, if the biometric monitoring device determines the user is sedentary or asleep). (See, for example, FIG. 9). In this way, the biometric monitoring device may control its power consumption. For example, the biometric monitoring device may reduce power consumption by reducing the sensor sampling rate—for instance, the biometric monitoring device may sample the heart rate (via the heart rate sensor) once every 10 minutes, or 10 seconds out of every 1 minute. Notably, the biometric monitoring device may, in addition thereto or in lieu thereof, control power consumption via controlling data processing circuitry analysis and/or data analysis techniques in accordance with motion detection. As such, the motion of the user may impact the heart rate data acquisition parameters and/or data analysis or processing thereof.

Motion Artifact Suppression in Heart Rate Sensors

[0119] As discussed above, the raw heart rate signal measured by a PPG sensor may be improved by using one or more algorithms to remove motion artifacts. Movement of the user (for determining motion artifacts) may be measured using sensors including, but not limited to, accelerometers, gyroscopes, proximity detectors, magnetometers, etc. The goal of such algorithms is to remove components of the PPG signal attributable to movement (movement artifacts) using the movement signal captured from the other sensors as a guide. In one embodiment the movement artifacts in the PPG signal may be removed using an adaptive filter based on a hybrid Kalman filter and a least mean square filter or a recursive least squares filter. The heart rate may then be extracted from the cleaned/filtered signal using a peak counting algorithm or a power spectral density estimation algorithm. Alternatively, a Kalman filter or particle filter may be used to remove such movement artifacts.

[0120] Another approach that may be used to calculate the heart rate frequency is to create a model of the heart rate signal as $Y=Y_{dc}+\sum a_k \cos k\theta+b_k \sin k\theta$, where k is the order of harmonic components, and θ is a model parameter for heart rate. This model may then be fit to the signal using either an extended Kalman filter or a particle filter. This model exploits the fact that the signal is not sinusoidal so contains power both at the fundamental harmonic as well as multiple additional harmonics.

[0121] Alternately, the signal may be modeled as $Y=Y_{dc}+\sum a_k \sin(k*w_{motion}t+\theta)+\sum b_k \sin(k*w_{HR}t+\phi)$, where w_{motion} is estimated directly from the accelerometer signal (or another motion sensor signal).

Ambient Light and Skin Color

[0122] Ambient light and skin color may make it difficult to extract a user's heart rate from a PPG signal. The effect of ambient light may be reduced by subtracting a value of the received detected light signal when the PPG light source is off from the value of the received detected light signal when the PPG light source is on (assuming that both signals are obtained in close temporal proximity to each other).

[0123] The effect of skin color may be reduced by changing the intensity of the PPG light source, the wavelength of the light emitted from the light source, and/or by using the ratio or difference of received signal corresponding to two different wavelengths. Skin color may be determined by using user input (e.g. the user entering their skin color), an image of the person's face, etc., and may then subsequently be used to calibrate the algorithm, light source brightness, light source wavelength, and the receiver gain. The effect of skin color (and tightness with which the user is wearing the device) on the raw PPG signal may also be measured by sending in a signal of known amplitude to the light source(s) and then measuring the received signal from the photodetector(s). Such a signal may be sent for a prolonged period of time (so as to capture data through multiple expected heart beats) and then averaged to produce a steady-state data set that is not heart-rate dependent. This amplitude may then be compared to a set of values stored in a table to determine algorithm calibration, transmitter amplitude and the receiver gain.

Heart Rate Estimate Improvement Using Heuristics

[0124] After getting an initial estimate of the heart rate (e.g. by peak counting of a power spectral density estimation), it may be useful to apply bounds on the allowable rates for heart rate. These bounds may be optimized on a per-user basis since each user will have a unique heart rate profile. For example, the sedentary rate of each user may be estimated when they are stationary and this may be used as a lower bound when the user is walking. Similarly, half the frequency of walking as calculated from the pedometer may serve as a good lower bound for the expected heart rate.

[0125] The heart rate algorithm may be tailored for each user and may learn the heart rate profile of the user and adapt to the user's behaviors and/or characteristics so as to perform better with time. For example, the algorithm may set bounds on the heart rate expected during a particular physical activity or rate of walking based on historical data from that user. This may help provide better results when the heart rate data is corrupted by noise and/or motion artifacts.

HR Quality Metric

[0126] In another example embodiment, a signal quality metric of the heart rate/PPG signal may be used to provide a quantification of the accuracy/precision of the signal being generated. Depending on the values of this metric, the algorithm that determines what the user's heart rate (or other PPG-derived metric such as respiration) is may take certain actions, including asking the user to tighten the watch band, ignoring certain portions of collected heart-rate data (e.g. sections of data that have a low quality metric), and weighting certain portions of the heart-rate data (e.g., data with a higher quality metric may be weighted more heavily when the heart rate is being calculated).

[0127] In one embodiment, the signal quality metric may be derived as follows: make a scatter plot where the x-axis is time, and the y-axis is the frequency of a peak in the PPG signal at that given instant in time. An issue to be overcome using this strategy is that there may be multiple and/or zero peaks at a given instant in time. A best fit line captures the linear relationship in this scatter plot. A high quality signal should have a set of peaks that fit well to a line (in a short time span), whereas a bad signal will have a set of peaks that

are not well described by a line. Therefore, the quality of the fit to the line provides a good metric for the quality of the PPG signal itself.

Sedentary, Sleep, and Active Classified Metrics

[0128] In yet another example embodiment, the biometric monitoring device may employ sensors to calculate heart rate variability when the device determines the user to be sedentary or asleep. Here, the biometric monitoring device may operate the sensors in a higher-rate sampling mode (relative to non-sedentary periods or periods of user activity that exceed a predetermined threshold) to calculate heart rate variability. The biometric monitoring device (or an external device) may employ heart rate variability as an indicator of cardiac health or stress.

[0129] Indeed, in some embodiments, the biometric monitoring device may measure and/or determine the user's stress level and/or cardiac health when the user is sedentary and/or asleep (for example, as detected and/or determined by the biometric monitoring device). Some embodiments of a biometric monitoring device of the present disclosure may determine the user's stress level, health state (e.g., risk, onset, or progression of fever or cold), and/or cardiac health using sensor data that is indicative of the heart rate variability, galvanic skin response, skin temperature, body temperature, and/or heart rate. In this way, processing circuitry of the biometric monitoring device may determine and/or track the user's "baseline" stress levels over time and/or cardiac "health" over time. In another embodiment, the device may measure a physiologic parameter of the user during one or more periods where the user is motionless (or the user's motion is below a predetermined threshold), such as when the user is sitting, lying down, asleep, or in a sleep stage (e.g., deep sleep). Such data may also be employed by the biometric monitoring device as a "baseline" for stress-related parameters, health-related parameters (e.g., risk or onset of fever or cold), cardiac health, heart rate variability, galvanic skin response, skin temperature, body temperature and/or heart rate.

Sleep Monitoring

[0130] In some embodiments, the biometric monitoring device may automatically detect or determine when the user is attempting to go to sleep, is entering sleep, is asleep, and/or is awoken from a period of sleep. In such embodiments, the biometric monitoring device may employ physiological sensors to acquire data and the data processing circuitry of the biometric monitoring device may correlate a combination of heart rate, heart rate variability, respiration rate, galvanic skin response, motion, skin temperature, and/or body temperature data collected from sensors of the biometric monitoring device to detect or determine if the user is attempting to go to sleep, is entering sleep, is asleep, and/or is awoken from a period of sleep. In response, the biometric monitoring device may, for example, acquire physiological data (of the types, and in the manners, as described herein) and/or determine physiological conditions of the user (of the types, and in the manners, as described herein). For example, a decrease or cessation of user motion combined with a reduction in user heart rate and/or a change in heart rate variability may indicate that the user has fallen asleep. Subsequent changes in heart rate variability and galvanic skin response may then be used by the biometric

monitoring device to determine transitions of the user's sleep state between two or more stages of sleep (for example, into lighter and/or deeper stages of sleep). Motion by the user and/or an elevated heart rate and/or a change in heart rate variability may be used by the biometric monitoring device to determine that the user has awoken.

[0131] Real-time, windowed, or batch processing to maybe used to determine the transitions between wake, sleep, and sleep stages. For instance, a decrease in heart rate may be measured in a time window where the heart rate is elevated at the start of the window and reduced in the middle (and/or end) of the window. The awake and sleep stages may be classified by a hidden Markov model using changes in motion signal (e.g., decreasing motion intensity), heart rate, heart rate variability, skin temperature, galvanic skin response, and/or ambient light levels. The transition points may be determined through a changepoint algorithm (e.g., Bayesian changepoint analysis). The transition between awake and sleep may be determined by observing periods where the user's heart rate decreases over a predetermined time duration by at least a certain threshold but within a predetermined margin of the user's resting heart rate (that is observed as, for example, the minimum heart rate of the user while sleeping). Similarly, the transition between sleep and awake may be determined by observing an increase in the user's heart rate above a predetermined threshold of the user's resting heart rate.

[0132] In some embodiments, the biometric monitoring device may be one component of a system for monitoring sleep, where the system includes a secondary device configured to communicate with the biometric monitoring device and adapted to be placed near the sleeper (e.g., an alarm clock). The secondary device may, in some implementations, have a shape and mechanical and/or magnetic interface to accept the biometric monitoring device for safe keeping, communication, and/or charging. However, the secondary device may also be generic to the biometric monitoring device, e.g., a smartphone that is not specifically designed to physically interface with the biometric monitoring device. The communication between the biometric monitoring device and the secondary device may be provided through wired communication interfaces or through wireless communication interfaces and protocols such as Bluetooth (including, for example, Bluetooth 4.0 and Bluetooth Low Energy protocols), RFID, NFC, or WLAN. The secondary device may include sensors to assist in sleep monitoring or environmental monitoring such as, for example, sensors that measure ambient light, noise and/or sound (e.g., to detect snoring), temperature, humidity, and air quality (pollen, dust, CO₂, etc.). In one embodiment, the secondary device may communicate with an external service such as www.fitbit.com or a server (e.g., a personal computer). Communication with the secondary device may be achieved through wired (e.g., Ethernet, USB) or wireless (e.g., WLAN, Bluetooth, RFID, NFC, cellular) circuitry and protocols to transfer data to and/or from the secondary device. The secondary device may also act as a relay to transfer data to and/or from the biometric monitoring device to and/or from an external service such as www.fitbit.com or other service (e.g., data such as news, social network updates, email, calendar notifications) or server (e.g., personal computer, mobile phone, tablet). Calculation of the

user's sleep data may be performed on one or both devices or an external service (e.g., a cloud server) using data from one or both devices.

[0133] The secondary device may be equipped with a display to display data obtained by the secondary device or data transferred to it by the biometric monitoring device, the external service, or a combination of data from the biometric monitoring device, the secondary device, and/or the external service. For example, the secondary device may display data indicative of the user's heart rate, total steps for the day, activity and/or sleep goal achievement, the day's weather (measured by the secondary device or reported for a location by an external service), etc. In another example, the secondary device may display data related to the ranking of the user relative to other users, such as total weekly step count. In yet another embodiment, the biometric monitoring device may be equipped with a display to display data obtained by the biometric monitoring device, the secondary device, the external service, or a combination of the three sources. In embodiments where the first device is equipped with a wakeup alarm (e.g., vibramotor, speaker), the secondary device may act as a backup alarm (e.g., using an audio speaker). The secondary device may also have an interface (e.g., display and buttons or touch screen) to create, delete, modify, or enable alarms on the first and/or the secondary device.

Sensor-Based Standby Mode

[0134] In another embodiment, the biometric monitoring device may automatically detect or determine whether it is or is not attached to, disposed on, and/or being worn by a user. In response to detecting or determining that the biometric monitoring device is not attached to, disposed on, and/or being worn by a user, the biometric monitoring device (or selected portions thereof) may implement or be placed in a low power mode of operation—for example, the optical heart rate sensor and/or circuitry may be placed in a lower power or sleep mode. For example, in one embodiment, the biometric monitoring device may include one or more light detectors (photodiodes, phototransistors, etc.). If, at a given light intensity setting (for example, with respect to the light emitted by a light source that is part of the biometric monitoring device), one or more light detectors provides a low return signal, the biometric monitoring device may interpret the data as indicative of the device not being worn. Upon such a determination, the device may reduce its power consumption—for example, by “disabling” or adjusting the operating conditions of the stress and/or heart rate detection sensors and/or circuitry in addition to other device circuitry or displays (for example, by reducing the duty cycle of or disabling the light source(s) and/or detector(s), turning off the device display, and/or disabling or attenuating associated circuitry or portions thereof). In addition, the biometric monitoring device may periodically determine (e.g., once per second) if the operating conditions of the stress and/or heart rate detection sensors and/or associated circuitry should be restored to a normal operating condition (for example, light source(s), detector(s) and/or associated circuitry should return to a normal operating mode for heart rate detection). In another embodiment, the biometric monitoring device may restore the operating conditions of the stress and/or heart rate detection sensors and/or associated circuitry upon detection of a triggerable event—for example, upon detecting motion of the device

(for example, based on data from one or more motion sensor(s)) and/or detecting a user input via the user interface (for example, a tap, bump or swipe interaction with the biometric monitoring device). In some related embodiments, the biometric monitoring device may, for power saving purposes, reduce its default rate of heart rate measurement collection to, for instance, one measurement per minute while the user is not highly active and the user may have the option of putting the device into a mode of operation to generate measurements on demand or at a faster rate (e.g., once per second), for instance, by pushing a button.

Optical Sensor(s)

[0135] In one embodiment, the optical sensors (sources and/or detectors) may be disposed on an interior or skin-side of the biometric monitoring device (i.e., a side of the biometric monitoring device that contacts, touches, and/or faces the skin of the user (hereinafter “skin-side”). (See, for example, FIGS. 2A through 3C). In another embodiment, the optical sensors may be disposed on one or more sides of the device, including the skin-side and one or more sides of the device that face or are exposed to the ambient environment (environmental side). (See, for example, FIGS. 6A through 7).

[0136] FIG. 6A illustrates an example of a portable monitoring device having a band; optical sensors and light emitters may be placed on the band.

[0137] FIG. 6B illustrates an example of a portable biometric monitoring device having a display and wristband. Additionally, optical PPG (e.g., heart rate) detection sensors and/or emitters may be located on the side of the biometric monitoring device. In one embodiment, these may be located in side-mounted buttons.

[0138] FIG. 7 depicts a user pressing the side of a portable biometric monitoring device to take a heart rate measurement from a side-mounted optical heart rate detection sensor. The display of the biometric monitoring device may show whether or not the heart rate has been detected and/or display the user's heart rate.

[0139] Notably, the data from such optical sensors may be representative of physiological data and/or environmental data. Indeed, in one embodiment, the optical sensors provide, acquire and/or detect information from multiple sides of the biometric monitoring device whether or not the sensors are disposed on one or more of the multiple sides. For example, the optical sensors may obtain data related to the ambient light conditions of the environment.

[0140] Where optical sensors are disposed or arranged on the skin-side of the biometric monitoring device, in operation, a light source in the biometric monitoring device may emit light upon the skin of the user and, in response, a light detector in the biometric monitoring device may sample, acquire, and/or detect corresponding reflected and/or emitted light from the skin (and from inside the body). The one or more light sources and light detectors may be arranged in an array or pattern that enhances or optimizes the signal-to-noise ratio and/or serves to reduce or minimize power consumption by the light sources and light detectors. These optical sensors may sample, acquire and/or detect physiological data which may then be processed or analyzed (for example, by resident processing circuitry) to obtain data that is representative of, for example, a user's heart rate, respi-

ration, heart rate variability, oxygen saturation (SpO₂), blood volume, blood glucose, skin moisture, and/or skin pigmentation level.

[0141] The light source(s) may emit light having one or more wavelengths that are specific or directed to a type of physiological data to be collected. Similarly, the optical detectors may sample, measure and/or detect one or more wavelengths that are also specific or directed to a type of physiological data to be collected and/or a physiological parameter (of the user) to be assessed or determined. For instance, in one embodiment, a light source emitting light having a wavelength in the green spectrum (for example, an LED that emits light having wavelengths corresponding to the green spectrum) and a photodiode positioned to sample, measure, and/or detect a response or reflection corresponding with such light may provide data that may be used to determine or detect heart rate. In contrast, a light source emitting light having a wavelength in the red spectrum (for example, an LED that emits light having wavelengths corresponding to the red spectrum) and a light source emitting light having a wavelength in the infrared spectrum (for example, an LED that emits light having wavelengths corresponding to the IR spectrum) and photodiode positioned to sample, measure and/or detect a response or reflection of such light may provide data used to determine or detect SpO₂.

[0142] Indeed, in some embodiments, the color or wavelength of the light emitted by the light source, e.g., an LED (or set of LEDs), may be modified, adjusted, and/or controlled in accordance with a predetermined type of physiological data being acquired or conditions of operation. Here, the wavelength of the light emitted by the light source may be adjusted and/or controlled to optimize and/or enhance the “quality” of the physiological data obtained and/or sampled by the detector. For example, the color of the light emitted by the LED may be switched from infrared to green when the user’s skin temperature or the ambient temperature is cool in order to enhance the signal corresponding to cardiac activity. (See, for example, FIG. 11D).

[0143] The biometric monitoring device, in some embodiments, may include a window (for example, a window that is, to casual inspection, opaque) in the housing to facilitate optical transmission between the optical sensors and the user. Here, the window may permit light (for example, of a selected wavelength) to be emitted by, for example, one or more LEDs, onto the skin of the user and a response or reflection of that light to pass back through the window to be sampled, measured, and/or detected by, for example, one or more photodiodes. In one embodiment, the circuitry related to emitting and receiving light may be disposed in the interior of the device housing and underneath or behind a plastic or glass layer (for example, painted with infrared ink) or an infrared lens or filter that permits infrared light to pass but not light in the human visual spectrum. In this way, the light transmissivity of the window may be invisible to the human eye.

[0144] The biometric monitoring device may employ light pipes or other light-transmissive structures to facilitate transmission of light from the light sources to the user’s body and skin. (See, for example, FIGS. 4A through 5). In this regard, in some embodiments, light may be directed from the light source to the skin of the user through such light pipes or other light-transmissive structures. Scattered light from the user’s body may be directed back to the optical circuitry in

the biometric monitoring device through the same or similar structures. Indeed, the light-transmissive structures may employ a material and/or optical design to facilitate low light loss (for example, the light-transmissive structures may include a lens to facilitate light collection, and portions of the light-transmissive structures may be coated with or adjacent to reflective materials to promote internal reflection of light within the light-transmissive structures) thereby improving the signal-to-noise-ratio of the photo detector and/or facilitating reduced power consumption of the light source(s) and/or light detectors. In some embodiments, the light pipes or other light-transmissive structures may include a material that selectively transmits light having one or more specific or predetermined wavelengths with higher efficiency than others, thereby acting as a bandpass filter. Such a bandpass filter may be tuned to improve the signal of a specific physiological data type. For example, in one embodiment, an In-Mold-Labeling or “IML” light-transmissive structure may be implemented wherein the light-transmissive structure uses a material with predetermined or desired optical characteristics to create a specific bandpass characteristic, for example, so as to pass infrared light with greater efficiency than light of other wavelengths (for example, light having a wavelength in human visible spectrum). In another embodiment, a biometric monitoring device may employ a light-transmissive structure having an optically opaque portion (including certain optical properties) and an optically-transparent portion (including optical properties different from the optically-opaque portion). Such a light-transmissive structure may be provided via a double-shot or two-step molding process wherein optically opaque material and optically transparent material are separately injected into a mold. A biometric monitoring device implementing such a light-transmissive structure may include different light transmissivity properties for different wavelengths depending on the direction of light travel through the light-transmissive structure. For example, in one embodiment, the optically-opaque material may be reflective to a specific wavelength range so as to more efficiently transport light from the user’s body back to the light detector (which may be of a different wavelength(s) relative to the wavelength(s) of the emitted light).

[0145] In another embodiment, reflective structures may be placed in the field of view of the light emitter(s) and/or light detector(s). For example, the sides of holes that channel light from light emitter(s) to a user’s skin and/or from the user’s skin to light detector(s) (or through which light-transmissive structures that perform such channeling travel) may be covered in a reflective material (e.g., chromed) to facilitate light transmission. The reflective material may increase the efficiency with which the light is transported to the skin from the light source(s) and then from the skin back into the detector(s). The reflectively-coated hole may be filled in with an optical epoxy or other transparent material to prevent liquid from entering the device body while still allowing light to be transmitted with low transmission loss.

[0146] In another embodiment that implements light-transmissive structures (for example, structures created or formed through IML), such light-transmissive structures may include a mask consisting of an opaque material that limits the aperture of one, some, or all of the light source(s) and/or detector(s). In this way, the light-transmissive structures may selectively “define” a preferential volume of the user’s body that light is emitted into and/or detected from.

Notably, other mask configurations may be employed or implemented in connection with the concepts described and/or illustrated herein; all such masking configurations to, for example, improve the photoplethysmography signal and which are implemented in connection with the concepts described and/or illustrated herein are intended to fall within the scope of the present disclosure.

[0147] In another embodiment, the light emitter(s) and/or detector(s) may be configured to transmit light through a hole or series of holes in the device exterior. This hole or series of holes may be filled in with light-transmissive epoxy (e.g. optical epoxy). The epoxy may form a light pipe that allows light to be transmitted from the light emitter(s) to the skin and from the skin back into the light detector(s). This technique also has the advantage that the epoxy may form a watertight seal, preventing water, sweat or other liquid from entering the device body through the hole(s) on the device exterior that allow the light emitter(s) and detector(s) to transmit to, and receive light from, the biometric monitoring device body exterior. An epoxy with a high thermal conductivity may be used to help prevent the light source(s) (e.g., LED's) from overheating.

[0148] In any of the light-transmissive structures described herein, the exposed surfaces of the optics (light-transmissive structures) or device body may include a hard coat paint, hard coat dip, or optical coatings (such as anti-reflection, scratch resistance, anti-fog, and/or wavelength band block (such as ultraviolet light blocking) coatings). Such characteristics or materials may improve the operation, accuracy and/or longevity of the biometric monitoring device.

[0149] FIG. 4A illustrates an example of one potential PPG light source and photodetector geometry. In this embodiment, two light sources are placed on either side of a photodetector. These three devices are located in a protrusion on the back of a wristband-type biometric monitoring device (the side which faces the skin of the user).

[0150] FIGS. 4B and 4C illustrate examples of a PPG sensor having a photodetector and two LED light sources. These components are placed in a biometric monitoring device that has a protrusion on the back side. Light pipes optically connect the LEDs and photodetector with the surface of the user's skin. Beneath the skin, the light from the light sources scatters off of blood in the body, some of which may be scattered or reflected back into the photodetector.

[0151] FIG. 5 illustrates an example of a biometric monitoring device with an optimized PPG detector that has a protrusion with curved sides so as not to discomfort the user. Additionally, the surface of light pipes that optically couple the photodetector and the LEDs to the wearer's skin are contoured to maximize light flux coupling between the LEDs and photodetectors and the light pipes. The ends of the light pipes that face the user's skin are also contoured. This contour may focus or defocus light to optimize the PPG signal. For example, the contour may focus emitted light to a certain depth and location that coincides with an area where blood flow is likely to occur. The vertex of these foci may overlap or be very close together so that the photodetector receives the maximum possible amount of scattered light.

[0152] In some embodiments, the biometric monitoring device may include a concave or convex shape, e.g., a lens, on the skin-side of the device, to focus light towards a

specific volume at a specific depth in the skin and increase the efficiency of light collected from that point into the photodetector. (See, for example, FIGS. 4A through 5). Where such a biometric monitoring device also employs light pipes to selectively and controllably route light, it may be advantageous to shape the end of the light pipe with a degree of cylindricity, e.g., the end of the light pipe may be a cylindrical surface (or portion thereof) defined by a cylinder axis that is nominally parallel to the skin-side (for example, rather than use an axially-symmetric lens). For example, in a wristband-style biometric monitoring device, such a cylindrical lens may be oriented such that the cylinder axis is nominally parallel to the wearer's forearm, which may have the effect of limiting the amount of light that enters such a lens from directions parallel to the person's forearm and increasing the amount of light that enters such a lens from directions perpendicular to the person's forearm—since ambient light is more likely to reach the sensor detection area from directions that are not occluded by the straps of the biometric monitoring device, i.e., along the user's forearm axis, than from directions that are occluded by the straps, i.e., perpendicular to the user's forearm. Such a configuration may improve the signal-to-noise-ratio by increasing the efficiency of light transferred from the emitter onto or into the skin of the user while decreasing “stray” light from being detected or collected by the photodetector. In this way, the signal sampled, measured and/or detected by the photodetector consists less of stray light and more of the user's skin/body response to such emitted light (signal or data that is representative of the response to the emitted light).

[0153] In another embodiment, light-transmissive epoxy may be molded into a concave or convex shape so as to provide beneficial optical properties to sensors as well. For example, during the application of light transmissive epoxy, the top of the light-transmissive structure that is formed by the epoxy may be shaped into a concave surface so that light couples more effectively into the light-transmissive structure.

[0154] In one embodiment, the components of the optical sensor may be positioned on the skin-side of the device and arranged or positioned to reduce or minimize the distance between (i) the light source(s) and/or the associated detector (s) and (ii) the skin of the user. See, for example, FIG. 3A, which provides a cross-sectional view of a sensor protrusion of an example portable monitoring device. In FIG. 3A, two light sources (e.g., LEDs) are placed on either side of a photodetector to enable PPG sensing. A light-blocking material is placed between the light sources and the photodetector to prevent any light from the light sources from reaching photodetector without first exiting the body of the biometric monitoring device. A flexible transparent layer may be placed on the lower surface of the sensor protrusion to form a seal. This transparent layer may serve other functions such as preventing liquid from entering the device where the light sources or photodetectors are placed. This transparent layer may be formed through in-mold labeling or “IML”. The light sources and photodetector may be placed on a flexible PCB.

[0155] Such a configuration may improve the efficiency of light flux coupling between the components of the optical sensor and the user's body. For example, in one embodiment, the light source(s) and/or associated detector(s) may be disposed on a flexible or pliable substrate that may flex,

allowing the skin-side of the biometric monitoring device, which may be made from a compliant material, to conform (for example, without additional processing) or be capable of being shaped (or compliant) to conform to the shape of the body part (for example, the user's wrist, arm, ankle, and/or leg) to which the biometric monitoring device is coupled to or attached during normal operation so that the light source(s) and/or associated detector(s) are/is close to the skin of the user (i.e., with little to no gap between the skin-side of the device and the adjacent surface of the skin of the user. See, for example, FIG. 6A. In one embodiment, the light source(s) and/or associated detector(s) may be disposed on a Flat Flex Cable or "FFC" or flexible PCB. In this embodiment, the flexible or pliable substrate (for example, an FFC or flexible PCB) may connect to a second substrate (for example, PCB) within the device having other components disposed thereon (for example, the data processing circuitry). Optical components of differing heights may be mounted to different "fingers" of flexible substrate and pressed or secured to the housing surface such that the optical components are flush to the housing surface. In one embodiment, the second substrate may be a relatively inflexible or non-pliable substrate, fixed within the device, having other circuitry and components (passive and/or active) disposed thereon.

[0156] FIG. 3B depicts a cross-sectional view of a sensor protrusion of an example portable monitoring device; this protrusion is similar to that presented in FIG. 3A with the exception that the light sources and photodetector are placed on a flat and/or rigid PCB.

[0157] FIG. 3C provides another cross-sectional view of an example PPG sensor implementation. Of note in this PPG sensor is the lack of a protrusion. Additionally, a liquid gasket and/or a pressure sensitive adhesive are used to prevent liquid from entering the biometric monitoring device body.

[0158] Some embodiments of biometric monitoring devices may be adapted to be worn or carried on the body of a user. In some embodiments including the optical heart rate monitor, the device may be a wrist-worn or arm-mounted accessory such as a watch or bracelet. (See, for example, FIGS. 2A through 7). In one embodiment, optical elements of the optical heart rate monitor may be located on the interior or skin-side of the biometric monitoring device, for example, facing the top of the wrist (i.e., the optical heart rate monitor may be adjacent to and facing the wrist) when the biometric monitoring device is worn on the wrist. (See, for example, FIGS. 2A through 3C).

[0159] In another embodiment, the optical heart rate monitor may be located on one or more external or environmental side surfaces of the biometric monitoring device. (See, for example, FIGS. 6B and 7). In such embodiments, the user may touch an optical window (behind which optical elements of the optical heart rate monitor are located) with a finger on the opposing hand to initiate a heart rate measurement (and/or other metrics related to heart rate such as heart rate variability) and/or collect data which may be used to determine the user's heart rate (and/or other metrics related to heart rate). (See, for example, FIG. 6B). In one embodiment, the biometric monitoring device may trigger or initiate the measurement(s) by detecting a (sudden) drop in incident light on the photodiode—for example, when the user's finger is placed over the optical window. In addition thereto, or in lieu thereof, a heart rate measurement (or other such

metric) may be triggered by an IR-based proximity detector and/or capacitive touch/proximity detector (which may be separate from other detectors). Such IR-based proximity detector and/or capacitive touch/proximity detector may be disposed in or on and/or functionally, electrically and/or physically coupled to the optical window to detect or determine the presence of, for example, the user's finger.

[0160] In yet another embodiment, the biometric monitoring device may include a button that, when depressed, triggers or initiates heart rate measurement (and/or other metrics related to heart rate). The button may be disposed in close proximity to the optical window to facilitate the user pressing the button while the finger is disposed on the optical window. (See, for example, FIG. 7). In one embodiment, the optical window may be embedded in a push button. Thus, when the user presses the button, it may trigger a measurement of the finger that depresses the button. Indeed, the button may be given a shape and/or resistance to pressing that enhances or optimizes a pressure profile of the button against the finger to provide a high signal-to-noise-ratio during measurement or data acquisition. In other embodiments (not illustrated), the biometric monitoring device may take the form of a clip, a smooth object, a pendant, an anklet, a belt, etc. that is adapted to be worn on the body, clipped or mounted to an article of clothing, deposited in clothing (e.g., in a pocket), or deposited in an accessory (e.g., handbag).

[0161] In one specific embodiment, the biometric monitoring device may include a protrusion on the skin- or interior side of the device. (See, FIGS. 2A through 6A). When coupled to the user, the protrusion may engage the skin with more force than the surrounding device body. In this embodiment, an optical window or light transmissive structure (both of which are discussed in detail above) may form or be incorporated in a portion of the protrusion. The light emitter(s) and/or detector(s) of the optical sensor may be disposed or arranged in the protrusion near the window or light transmissive structure. (See, for example, FIGS. 2B and 6A). As such, when attached to the user's body, the window portion of the protrusion of the biometric monitoring device may engage the user's skin with more force than the surrounding device body—thereby providing a more secure physical coupling between the user's skin and the optical window. That is, the protrusion may cause sustained contact between the biometric monitoring device and the user's skin that may reduce the amount of stray light measured by the photodetector, decrease relative motion between the biometric monitoring device and the user, and/or provide improved local pressure to the user's skin; all of which may increase the quality of the cardiac signal of interest. Notably, the protrusion may contain other sensors that benefit from close proximity and/or secure contact to the user's skin. These may be included in addition to or in lieu of a heart rate sensor and include sensors such as a skin temperature sensor (e.g., noncontact thermopile that utilizes the optical window or thermistor joined with thermal epoxy to the outer surface of the protrusion), pulse oximeter, blood pressure sensor, EMG, or galvanic skin response (GSR) sensor.

[0162] In addition thereto, or in lieu thereof, a portion of the skin-side of the biometric monitoring device may include a friction enhancing mechanism or material. For example, the skin-side of the biometric monitoring device may include a plurality of raised or depressed regions or

portions (for example, small bumps, ridges, grooves, and/or divots). Moreover, a friction enhancing material (for example, a gel-like material such as silicone or other elastomeric material) may be disposed on the skin-side. Indeed, a device back made out of gel may also provide friction while also improving user comfort and preventing stray light from entering. As noted above, a friction-enhancing mechanism or material may be used alone or in conjunction with the biometric monitoring device having a protrusion as described herein. In this regard, the biometric monitoring device may include a plurality of raised or depressed regions portions (for example, small bumps, ridges, grooves, and/or divots) in or on the protrusion portion of the device. Indeed, such raised or depressed regions portions may be incorporated/embedded into or on a window portion of the protrusion. In addition thereto, or in lieu thereof, the protrusion portion may consist of or be coated with a friction enhancing material (for example, a gel-like material such as silicone). Notably, the use of a protrusion and/or friction may improve measurement accuracy of data acquisition corresponding to certain parameters (e.g., heart rate, heart rate variability, galvanic skin response, skin temperature, skin coloration, heat flux, blood pressure, blood glucose, etc.) by reducing motion of the biometric monitoring device (and thus of the sensor) relative to the user's skin during operation, especially while the user is in motion.

[0163] Some or all of the interior or skin-side housing of the biometric monitoring device may also consist of a metal material (for example, steel, stainless steel, aluminum, magnesium, or titanium). Such a configuration may provide a structural rigidity. (See, for example, FIG. 2B). In such an embodiment, the device body may be designed to be hypoallergenic through the use of a hypoallergenic "nickel-free" stainless steel. Notably, it may be advantageous to employ (at least in certain locations) a type of metal that is at least somewhat ferrous (for example, a grade of stainless steel that is ferrous). In such embodiments, the biometric monitoring device (where it includes a rechargeable energy source (for example, rechargeable battery)) may interconnect with a charger via a connector that secures itself to the biometric monitoring device using magnets that couple to the ferrous material. In addition, biometric monitoring device may also engage a dock or dock station, using such magnetic properties, to facilitate data transfer. Moreover, such a housing may provide enhanced electromagnetic shielding that would enhance the integrity and reliability of the optical heart rate sensor and the heart rate data acquisition process/operation. Furthermore, a skin temperature sensor may be physically and thermally coupled, for example, with thermal epoxy, to the metal body to sense the temperature of the user. In embodiments including a protrusion, the sensor may be positioned near or in the protrusion to provide secure contact and localized thermal coupling to the user's skin.

[0164] In a preferred embodiment, one or more components of the optical sensor (which may, in one embodiment, be located in a protrusion, and/or in another embodiment, may be disposed or placed flush to the surface of the biometric monitoring device) are attached, fixed, included, and/or secured to the biometric monitoring device via a liquid-tight seal (i.e., a method/mechanism that prevents liquid ingress into the body of the biometric monitoring device). For example, in one embodiment, a device back made out of a metal such as, but not limited to, stainless

steel, aluminum, magnesium, or titanium, or from a rigid plastic may provide a structure that is stiff enough to maintain the structural integrity of the device while accommodating a watertight seal for the sensor package. (See, for example, FIGS. 2B through 3C).

[0165] In a preferred embodiment, a package or module of the optical sensor may be connected to the device with a pressure-sensitive adhesive and a liquid gasket. See, for example, FIG. 3C, which provides another cross-sectional view of a PPG sensor implementation. Of note in this PPG sensor is the lack of a protrusion. Additionally, a liquid gasket and/or a pressure sensitive adhesive are used to prevent liquid from entering the device body. Screws, rivets or the like may also be used, for example, if a stronger or more durable connection is required between the optical sensor package/module and the device body. Notably, the present embodiments may also use watertight glues, hydrophobic membranes such as Gore-Tex, o-rings, sealant, grease, or epoxy to secure or attach the optical sensor package/module to the biometric monitoring device body.

[0166] As discussed above, the biometric monitoring device may include a material disposed on the skin- or interior side that includes high reflectivity characteristics—for example, polished stainless steel, reflective paint, and polished plastic. In this way, light scattered off the skin-side of the device may be reflected back into the skin in order to, for example, improve the signal-to-noise-ratio of an optical heart rate sensor. Indeed, this effectively increases the input light signal as compared with a device body back that is non-reflective (or less reflective). Notably, in one embodiment, the color of the skin or interior side of the biometric monitoring device may be selected to provide certain optical characteristics (for example, reflect certain or predetermined wavelengths of light), in order to improve the signal with respect to certain physiological data types. For example, where the skin- or interior side of the biometric monitoring is green, the measurements of the heart rate may be enhanced due to the preferential emission of a wavelength of the light corresponding to the green spectrum. Where the skin- or interior side of the biometric monitoring is red, the measurements of the SpO₂ may be enhanced due to the emission preferential of a wavelength of the light corresponding to the red spectrum. In one embodiment, the color of the skin- or interior side of the biometric monitoring may be modified, adjusted and/or controlled in accordance with a predetermined type of physiological data being acquired.

[0167] FIG. 11A depicts an example schematic block diagram of an optical heart rate sensor where light is emitted from a light source toward the user's skin and the reflection of such light from the skin/internal body of the user is sensed by a light detector, the signal from which is subsequently digitized by an analog to digital converter (ADC). The intensity of the light source may be modified (e.g., through a light source intensity control module) to maintain a desirable reflected signal intensity. For example, the light source intensity may be reduced to avoid saturation of the output signal from the light detector. As another example, the light source intensity may be increased to maintain the output signal from the light detector within a desired range of output values. Notably, active control of the system may be achieved through linear or nonlinear control methods such as proportional-integral-derivative (PID) control, fixed step control, predictive control, neural networks, hysteresis, and the like, and may also employ information derived from

other sensors in the device such as motion, galvanic skin response, etc. FIG. 11A is provided for illustration and does not limit the implementation of such a system to, for instance, an ADC integrated within a MCU, or the use of a MCU for that matter. Other possible implementations include the use of one or more internal or external ADCs, FPGAs, ASICs, etc.

[0168] In another embodiment, system with an optical heart rate sensor may incorporate the use of a sample-and-hold circuit (or equivalent) to maintain the output of the light detector while the light source is turned off or attenuated to save power. In embodiments where relative changes in the light detector output are of primary importance (e.g., heart rate measurement), the sample-and-hold circuit may not have to maintain an accurate copy of the output of the light detector. In such cases, the sample-and-hold may be reduced to, for example, a diode (e.g., Schottky diode) and capacitor. The output of the sample-and-hold circuit may be presented to an analog signal conditioning circuit (e.g., a Sallen-Key bandpass filter, level shifter, and/or gain circuit) to condition and amplify the signal within frequency bands of interest (e.g., 0.1 Hz to 10 Hz for cardiac or respiratory function), which may then be digitized by the ADC. See, for example, FIG. 11B.

[0169] In operation, circuit topologies such as those already described herein (e.g. a sample-and-hold circuit) remove the DC and low frequency components of the signal and help resolve the AC component related to heart rate and/or respiration. The embodiment may also include the analog signal conditioning circuitry for variable gain settings that can be controlled to provide a suitable signal (e.g., not saturated). The performance characteristics (e.g., slew rate and/or gain bandwidth product) and power consumption of the light source, light detector, and/or sample-and-hold may be significantly higher than the analog signal conditioning circuit to enable fast duty cycling of the light source. In some embodiments, the power provided to the light source and light detector may be controlled separately from the power provided to the analog signal conditioning circuit to provide additional power savings. Alternatively or additionally, the circuitry can use functionality such as an enable, disable and/or shutdown to achieve power savings. In another embodiment, the output of the light detector and/or sample-and-hold circuit may be sampled by an ADC in addition to or in lieu of the analog signal conditioning circuit to control the light intensity of the light source or to measure the physiologic parameters of interest when, for example, the analog signal conditioning circuit is not yet stable after a change to the light intensity setting. Notably, because the physiologic signal of interest is typically small relative to the inherent resolution of the ADC, in some embodiments, the reference voltages and/or gain of the ADC may be adjusted to enhance signal quality and/or the ADC may be oversampled. In yet another embodiment, the device may digitize the output of only the sample-and-hold circuit by, for example, oversampling, adjusting the reference voltages and/or gain of the ADC, or using a high resolution ADC. See, for example, FIG. 11C.

PPG DC Offset Removal Techniques

[0170] In another embodiment, the sensor device may incorporate a differential amplifier to amplify the relative changes in the output of the light detector. See, for example, FIG. 11F. In some embodiments, a digital average or digital

low-pass filtered signal may be subtracted from the output of the light detector. This modified signal may then be amplified before it is digitized by the ADC. In another embodiment, an analog average or analog low-pass filtered signal may be subtracted from the output of the light detector through, for example, the use of a sample-and-hold circuit and analog signal conditioning circuitry. The power provided to the light source, light detector, and differential amplifier may be controlled separately from the power provided to the analog signal conditioning circuit to improve power savings.

[0171] In another embodiment, a signal (voltage or current, depending on the specific sensor implementation) may be subtracted from the raw PPG signal to remove any bias in the raw PPG signal and therefore increase the gain or amplification of the PPG signal that contains heart rate (or other circulatory parameters such as heart rate variability) information. This signal may be set to a default value in the factory, to a value based on the user's specific skin reflectivity, absorption, and/or color, and/or may change depending on feedback from an ambient light sensor, or depending on analytics of the PPG signal itself. For example, if the PPG signal is determined to have a large DC offset, a constant voltage may be subtracted from the PPG signal to remove the DC offset and enable a larger gain, therefore improving the PPG signal quality. The DC offset in this example may result from ambient light (for example from the sun or from indoor lighting) reaching the photodetector from or reflected light from the PPG light source.

[0172] In another embodiment, a differential amplifier may be used to measure the difference between current and previous samples rather than the magnitude of each signal. Since the magnitude of each sample is typically much greater than the difference between each sample, a larger gain can be applied to each measurement, therefore improving the PPG signal quality. The signal may then be integrated to obtain the original time domain signal.

[0173] In another embodiment, the light detector module may incorporate a transimpedance amplifier stage with variable gain. Such a configuration may avoid or minimize saturation from bright ambient light and/or bright emitted light from the light source. For example, the gain of the transimpedance amplifier may be automatically reduced with a variable resistor and/or multiplexed set of resistors in the negative feedback path of the transimpedance amplifier. In some embodiments, the device may incorporate little to no optical shielding from ambient light by amplitude-modulating the intensity of the light source and then demodulating the output of the light detector (e.g., synchronous detection). See, for instance, FIG. 11E. In other aspects, if the ambient light is of sufficient brightness to obtain a heart rate signal, the light source may be reduced in brightness and/or turned off completely.

[0174] In yet another embodiment, the aforementioned processing techniques may be used in combination to optically measure physiological parameters of the user. See, for example, FIG. 11G. This topology may allow the system to operate in a low power measurement state and circuit topology when applicable and adapt to a higher power measurement state and circuit topology as necessary. For instance, the system may measure the physiologic parameter (e.g., heart rate) of interest using analog signal-conditioning circuitry while the user is immobile or sedentary to reduce

power consumption, but switch to oversampled sampling of the light detector output directly while the user is active.

[0175] In embodiments where the biometric monitoring device includes a heart rate monitor, processing of the signal to obtain heart rate measurements may include filtering and/or signal conditioning such as band-pass filtering (e.g., Butterworth filter). To counteract large transients that may occur in the signal and/or to improve convergence of said filtering, nonlinear approaches may be employed such as neural networks or slew rate limiting. Data from the sensors on the device such as motion, galvanic skin response, skin temperature, etc., may be used to adjust the signal conditioning methods employed. Under certain operating conditions, the heart rate of the user may be measured by counting the number of signal peaks within a time window or by utilizing the fundamental frequency or second harmonic of the signal (e.g., through a fast Fourier transform (FFT)). In other cases, such as heart rate data acquired while the user is in motion, FFTs may be performed on the signal and spectral peaks extracted, which may then be subsequently processed by a multiple-target tracker which starts, continues, merges, and deletes tracks of the spectra. In some embodiments, a similar set of operations may be performed on the motion signal and the output may be used to do activity discrimination (e.g., sedentary, walking, running, sleeping, lying down, sitting, biking, typing, elliptical, weight training) which is used to assist the multiple-target tracker. For instance, it may be determined that the user was stationary and has begun to move. This information may be used to preferentially bias the track continuation toward increasing frequencies. Similarly, the activity discriminator may determine that the user has stopped running or is running slower and this information may be used to preferentially bias the track continuation toward decreasing frequencies. Tracking may be achieved with single-scan or multi-scan, multiple-target tracker topologies such as joint probabilistic data association trackers, multiple-hypothesis tracking, nearest neighbor, etc. Estimation and prediction in the tracker may be done through Kalman filters, spline regression, particle filters, interacting multiple model filters, etc. A track selector module may use the output tracks from the multiple-spectra tracker and estimate the user's heart rate. The estimate may be taken as the maximum likelihood track, a weight sum of the tracks against their probabilities of being the heart rate, etc. The activity discriminator may furthermore influence the selection and/or fusion to get the heart rate estimate. For instance, if the user is sleeping, sitting, lying down, or sedentary, a prior probability may be skewed toward heart rates in the 40-80 bpm range; whereas if the user is running, jogging, or doing other vigorous exercise, a prior probability may be skewed toward elevated heart rates in the 90-180 bpm range. The influence of the activity discriminator may be based on the speed of the user. The estimate may be shifted toward (or wholly obtained by) the fundamental frequency of the signal when the user is not moving. The track that corresponds to the user's heart rate may be selected based on criteria that are indicative of changes in activity; for instance, if the user begins to walk from being stationary, the track that illustrates a shift toward higher frequency may be preferentially chosen.

[0176] The acquisition of a good heart rate signal may be indicated to the user through a display on the biometric monitoring device or another device in wired or wireless communication with the biometric monitoring device (e.g.,

a Bluetooth Low Energy-equipped mobile phone). In some embodiments, the biometric monitoring device may include a signal-strength indicator that is represented by the pulsing of an LED viewable by the user. The pulsing may be timed or correlated to be coincident with the user's heartbeat. The intensity, pulsing rate and/or color of the LED may be modified or adjusted to suggest signal strength. For example, a brighter LED intensity may represent a stronger signal or in an RGB LED configuration, a green colored LED may represent a stronger signal.

[0177] In some embodiments, the strength of the heart rate signal may be determined by the energy (e.g., squared sum) of the signal in a frequency band of, for instance, 0.5 Hz to 4 Hz. In other embodiments, the biometric monitoring device may have a strain gauge, pressure sensor, force sensor, or other contact-indicating sensor that may be incorporated or constructed into the housing and/or in the band (in those embodiments where the biometric monitoring device is attached to or mounted with a band like a watch, bracelet, and/or armband—which may then be secured to the user). A signal quality metric (e.g. heart rate signal quality) may be calculated based on data from these contact sensors either alone or in combination with data from the heart rate signal.

[0178] In another embodiment, the biometric monitoring device may monitor heart rate optically through an array of photodetectors such as a grid of photodiodes or a CCD camera. Motion of the optical device with respect to the skin may be tracked through feature-tracking of the skin and/or adaptive motion correction using an accelerometer and gyroscope. The detector array may be in contact with the skin or offset at a small distance away from the skin. The detector array and its associated optics may be actively controlled (e.g., with a motor) to maintain a stabilized image of the target and acquire a heart rate signal. This optomechanical stabilization may be achieved using information from motion sensors (e.g., a gyroscope) or image features. In one embodiment, the biometric monitoring device may implement relative motion cancellation using a coherent or incoherent light source to illuminate the skin and a photodetector array with each photodetector associated with comparators for comparing the intensity between neighboring detectors—obtaining a so-called speckle pattern which may be tracked using a variety of image tracking techniques such as optical flow, template matching, edge tracking, etc. In this embodiment, the light source used for motion tracking may be different than the light source used in the optical heart rate monitor.

[0179] In another embodiment, the biometric monitoring device may consist of a plurality of photodetectors and photoemitters distributed along a surface of the device that touches the user's skin (i.e., the skin-side of the biometric monitoring device). (See, for example, FIGS. 2A through 6A). In the example of a bracelet, for instance, there may be a plurality of photodetectors and photoemitters placed at various sites along the circumference of the interior of the band. (See, for example, FIG. 6A). A heart rate signal-quality metric associated with each site may be calculated to determine the best or set of best sites for estimating the user's heart rate. Subsequently, some of the sites may be disabled or turned off to, for example, reduce power consumption. The device may periodically check the heart rate signal quality at some or all of the sites to enhance, monitor and/or optimize signal and/or power efficiency.

[0180] In another embodiment, a biometric monitoring device may include a heart rate monitoring system including a plurality of sensors such as optical, acoustic, pressure, electrical (e.g., ECG or EKG), and motion and fuse the information from two or more of these sensors to provide an estimate of heart rate and/or mitigate noise induced from motion.

[0181] In addition to heart rate monitoring (or other biometric monitoring), or in lieu thereof, the biometric monitoring device, in some embodiments, may include optical sensors to track or detect time and duration of ultraviolet light exposure, total outdoor light exposure, the type of light source and duration and intensity of that light source (fluorescent light exposure, incandescent bulb light exposure, halogen, etc.), exposure to television (based on light type and flicker rate), whether the user is indoors or outdoors, time of day and location based on light conditions. In one embodiment, the ultraviolet detection sensor may consist of a reverse biased LED emitter driven as a light detector. The photocurrent produced by this detector may be characterized by, for instance, measuring the time it takes for the LED's capacitance (or alternately a parallel capacitor) to discharge.

[0182] All of the optical sensors discussed herein may be used in conjunction with other sensors to improve detection of the data described above or be used to augment detection of other types of physiological or environmental data.

[0183] Where the biometric monitoring device includes an audio or passive acoustic sensor, the device may contain one or more passive acoustic sensors that detect sound and pressure and that can include, but are not limited to, microphones, piezo films, etc. The acoustic sensors may be disposed on one or more sides of the device, including the side that touches or faces the skin (skin-side) and the sides that face the environment (environmental sides).

[0184] Skin-side acoustic or audio sensors may detect any type of sound transmitted through the body and such sensors may be arranged in an array or pattern that optimizes both the signal-to-noise-ratio and power consumption of such sensors. These sensors may detect respiration (e.g., by listening to the lung), respiratory sounds (e.g., breathing, snoring) and problems (e.g., sleep apnea, etc.), heart rate (listening to the heart beat), user's voice (via sound transmitted from the vocal cords throughout the body).

[0185] The biometric monitoring devices of the present disclosure may also include galvanic skin-response (GSR) circuitry to measure the response of the user's skin to emotional and physical stimuli or physiological changes (e.g., the transition of sleep stage). In some embodiments, the biometric monitoring device may be a wrist- or arm-mounted device incorporating a band made of conductive rubber or fabric so that the galvanic skin response electrodes may be hidden in the band. Because the galvanic skin response circuitry may be subjected to changing temperatures and environmental conditions, it may also include circuitry to enable automatic calibration, such as two or more switchable reference resistors in parallel or in series with the human skin/electrode path that allows real-time measurement of known resistors to characterize the response of the galvanic skin response circuit. The reference resistors may be switched into and out of the measurement path such that they are measured independently and/or simultaneously with the resistance of the human skin.

[0186] Circuits for Performing PPG

[0187] PPG circuitry may be optimized to obtain the best quality signal regardless of a variety of environmental conditions including, but not limited to, motion, ambient light, and skin color. The following circuits and techniques may be used to perform such optimization (see FIGS. 16A through 16J);

[0188] a sample-and-hold circuit and differential/instrumentation amplifier which may be used in PPG sensing. The output signal is an amplified difference between current and previous sample, referenced to a given voltage.

[0189] controlled current source to offset "bias" current prior to transimpedance amplifier. This allows greater gain to be applied at transimpedance amplifier stage.

[0190] a sample-and-hold circuit for current feedback applied to photodiode (prior to transimpedance amplifier). This can be used for ambient light removal, or "bias" current removal, or as a pseudo differential amplifier (may require dual rails).

[0191] a differential/instrumentation amplifier with ambient light cancellation.

[0192] a photodiode offset current generated dynamically by a DAC.

[0193] a photodiode offset current generated dynamically by controlled voltage source.

[0194] ambient light removal using a "switched capacitor" method.

[0195] photodiode offset current generated by a constant current source (also can be done with a constant voltage source and a resistor).

[0196] ambient light removal and differencing between consecutive samples.

[0197] ambient light removal and differencing between consecutive samples.

[0198] FIG. 16A illustrates an example schematic of a sample-and-hold circuit and differential/instrumentation amplifier which may be used in PPG sensing. The output signal in such a circuit may be an amplified difference between a current sample and a previous sample, referenced to a given voltage.

[0199] FIG. 16B illustrates an example schematic of a circuit for a PPG sensor using a controlled current source to offset "bias" current prior to a transimpedance amplifier. This allows greater gain to be applied at the transimpedance amplifier stage.

[0200] FIG. 16C illustrates an example schematic of a circuit for a PPG sensor using a sample-and-hold circuit for current feedback applied to photodiode (prior to a transimpedance amplifier). This circuit may be used for ambient light removal, or "bias" current removal, or as a pseudo-differential amplifier.

[0201] FIG. 16D illustrates an example schematic of a circuit for a PPG sensor using a differential/instrumentation amplifier with ambient light cancellation functionality.

[0202] FIG. 16E illustrates an example schematic of a circuit for a PPG sensor using a photodiode offset current generated dynamically by a DAC.

[0203] FIG. 16F illustrates an example schematic of a circuit for a PPG sensor using a photodiode offset current generated dynamically by a controlled voltage source.

[0204] FIG. 16G illustrates an example schematic of a circuit for a PPG sensor including ambient light removal functionality using a "switched capacitor" method.

[0205] FIG. 16H illustrates an example schematic of a circuit for a PPG sensor that uses a photodiode offset current generated by a constant current source (this may also be done using a constant voltage source and a resistor).

[0206] FIG. 16I illustrates an example schematic of a circuit for a PPG sensor that includes ambient light removal functionality and differencing between consecutive samples.

[0207] FIG. 16J illustrates an example schematic of a circuit for ambient light removal and differencing between consecutive samples.

[0208] Various circuits and concepts related to heart rate measurement using a PPG sensor are discussed in more detail in U.S. Provisional Patent Application No. 61/946,439, filed Feb. 28, 2014, which was previously incorporated herein by reference in the “Cross-Reference to Related Applications” section and which is again hereby incorporated by reference with respect to content directed at heart rate measurements with a PPG sensor and at circuits, methods, and systems for performing such measurements, e.g., to compensate for sensor saturation, ambient light, and skin tone.

Biometric Feedback

[0209] Some embodiments of biometric monitoring devices may provide feedback to the user based on one or more biometric signals. In one embodiment, a PPG signal may be presented to the user as a real-time or near-real-time waveform on a display of the biometric monitoring device (or on a display of a secondary device in communication with the biometric monitoring device). This waveform may provide similar feedback to the waveform displayed on an ECG or EKG machine. In addition to providing the user with an indication of the PPG signal which may be used to estimate various heart metrics (e.g., heart rate), the waveform may also provide feedback that may enable the user to optimize the position and pressure with which they are wearing the biometric monitoring device. For example, the user may see that the waveform has a low amplitude. In response to this, the user may try moving the position of the biometric monitoring device to a different location which gives a higher amplitude signal. In some implementations, the biometric monitoring device may, based on such indications, provide instructions to the user to move or adjust the fit of the biometric monitoring device so as to improve the signal quality.

[0210] In another embodiment, feedback about the quality of the PPG signal may be provided to the user through a method other than displaying the waveform. The biometric monitoring device may emit an auditory alarm (e.g. a beep) if the signal quality (e.g. signal to noise ratio) exceeds a certain threshold. The biometric monitoring device may provide a visual cue (through the use of a display for example) to the user to either change the position of the sensor and/or increase the pressure with which the device is being worn (for example by tightening a wrist strap in the case that the device is worn on the wrist).

[0211] Biometric feedback may be provided for sensors other than PPG sensors. For example, if the device uses ECG, EMG, or is connected to a device which performs either of these, it may provide feedback to the user regarding the waveform from those sensors. If the signal-to-noise-ratio of these sensors is low, or the signal quality is otherwise compromised, the user may be instructed on how they can improve the signal. For example, if the heart rate cannot be

detected from the ECG sensor, the device may provide a visual message to the user instructing them to wet or moisten the ECG electrodes to improve the signal.

Environmental Sensors

[0212] Some embodiments of biometric monitoring devices of the present disclosure may use one, some or all of the following environmental sensors to, for example, acquire the environmental data, including environmental data outlined in the table below. Such biometric monitoring devices are not limited to the number or types of sensors specified below but may employ other sensors that acquire environmental data outlined in the table below. All combinations and permutations of environmental sensors and/or environmental data are intended to fall within the scope of the present disclosure. Additionally, the device may derive environmental data from the corresponding sensor output data, but is not limited to the types of environmental data that it could derive from said sensor.

[0213] Notably, embodiments of biometric monitoring devices of the present disclosure may use one or more, or all of the environmental sensors described herein and one or more, or all of the physiological sensors described herein. Indeed, biometric monitoring device of the present disclosure may acquire any or all of the environmental data and physiological data described herein using any sensor now known or later developed—all of which are intended to fall within the scope of the present disclosure.

Environmental Sensors	Environmental data acquired
Motion Detector	Location
Potential Embodiments: Inertial, Gyroscopic or Accelerometer-based Sensors	
GPS	
Pressure/Altimeter sensor	Elevation
Ambient Temp	Temperature
Light Sensor	Indoor vs outdoor
	Watching TV (spectrum/flicker rate detection)
	Optical data transfer-initiation, QR codes, etc.
	Ultraviolet light exposure
Audio	Indoor vs. Outdoor
Compass	Location and/or orientation
Potential Embodiments: -3 Axis Compass	

[0214] In one embodiment, the biometric monitoring device may include an altimeter sensor, for example, disposed or located in the interior of the device housing. (See, for example, FIGS. 12B and 12C; FIG. 12C illustrates an example of a portable biometric monitoring device having physiological sensors, environmental sensors, and location sensors connected to a processor). In such a case, the device housing may have a vent that allows the interior of the device to measure, detect, sample and/or experience any changes in exterior pressure. In one embodiment, the vent may prevent water from entering the device while facilitating measuring, detecting and/or sampling changes in pressure via the altimeter sensor. For example, an exterior surface of the biometric monitoring device may include a vent type configuration or architecture (for example, a Gore™ vent) that allows ambient air to move in and out of the housing of the device (which allows the altimeter sensor

to measure, detect and/or sample changes in pressure), but reduces, prevents, and/or minimizes water and other liquids from flowing into the housing of the device.

[0215] The altimeter sensor, in one embodiment, may be filled with gel that allows the sensor to experience pressure changes outside of the gel. The gel may act as a relatively impervious, incompressible, yet flexible, membrane that transmits external pressure variations to the altimeter while physically separating the altimeter (and other internal components) from the outside environment. The use of a gel-filled altimeter may give the device a higher level of environmental protection with or without the use of an environmentally sealed vent. The device may have a higher survivability rate with a gel-filled altimeter in locations including, but not limited to, locations that have high humidity, clothes washers, dish washers, clothes dryers, a steam room or sauna, a shower, a pool, a bath, and any location where the device may be exposed to moisture, exposed to liquid, or submerged in liquid.

Sensors integration/Signal Processing

[0216] Some embodiments of the biometric monitoring devices of the present disclosure may use data from two or more sensors to calculate the corresponding physiological or environmental data as seen in the table below (for example, data from two or more sensors may be used in combination to determine metrics such as those listed below). The biometric monitoring device may include, but is not limited to, the number, types, or combinations of sensors specified below. Additionally, such biometric monitoring devices may derive the included data from the corresponding sensor combinations, but are not limited to the number or types of data that may be calculated from the corresponding sensor combinations.

Sensor Integrations	Data derived from signal processing of multiple sensors
Skin Temp and Ambient Temp	Heat Flux
Heart Rate and Motion	Elevation gain
Motion detector and other user's motion detector (linked by wireless communication path)	Users in the proximity
Motion, any heart rate sensor, galvanic skin response	Sit/Standing detection
Any heart rate, heart rate variability sensor, respiration, motion	Sleep Phase detection Sleep Apnea detection
Any heart rate sensor and/or wetness sensor, and/or motion detector	Resting Heart rate Active Heart Rate Heart rate while asleep Heart rate while sedentary
Any heart rate detector	Early detection of heart problems: Cardiac Arrhythmia Cardiac Arrest
Multiple heart rate detectors	Pulse transit time
Audio and/or strain gauge	Typing detection
GPS and photoplethysmography (PPG)	Location-stress correlation: determination of stressful regions determination of low stress regions Activity-specific heart rate resting heart rate active heart rate Automatic activity classification and activity heart rate determination

-continued

Sensor Integrations	Data derived from signal processing of multiple sensors
Heart rate, galvanic skin response, accelerometer and respiration	User fatigue, for example while exercising

[0217] In some embodiments, the biometric monitoring device may also include a near-field communication (NFC) receiver/transmitter to detect proximity to another device, such as a mobile phone. When the biometric monitoring device is brought into close or detectable proximity to the second device, it may trigger the start of new functionality on the second device (e.g., the launching of an “app” on the mobile phone and radio syncing of physiological data from the device to the second device). (See, for example, FIG. 10). Indeed, the biometric monitoring device of the present disclosure may implement any of the circuitry and techniques described and/or illustrated in U.S. Provisional Patent Application 61/606,559, filed Mar. 5, 2012, “Near Field Communication System, and Method of Operating Same”, inventor: James Park (the contents of which are incorporated herein by reference for such purpose).

[0218] FIG. 10 illustrates an example of a portable biometric monitoring device that has a bicycle application on it that may display bicycle speed and/or pedaling cadence, among other metrics. The app may be activated whenever the biometric monitoring device comes into proximity of a passive or active NFC tag. This NFC tag may be attached to the user's handlebars.

[0219] In another embodiment, the biometric monitoring device may include a location sensor (for example, GPS circuitry) and heart rate sensor (for example, photoplethysmography circuitry) to generate GPS- or location-related data and heart rate-related data, respectively. (See, for example, FIGS. 12B and 12C). The biometric monitoring device may then fuse, process and/or combine data from these two sensors/circuitries to, for example, determine, correlate, and/or “map” geographical regions according to physiological data (for example, heart rate, stress, activity level, quantity of sleep and/or caloric intake). In this way, the biometric monitoring device may identify geographical regions that increase or decrease a measurable user metric including, but not limited to, heart rate, stress, activity, level, quantity of sleep and/or caloric intake.

[0220] In addition thereto, or in lieu thereof, some embodiments of biometric monitoring devices may employ GPS-related data and photoplethysmography-related data (notably, each of which may be considered data streams) to determine or correlate the user's heart rate according to activity levels—for example, as determined by the user's acceleration, speed, location and/or distance traveled (as measured by the GPS and/or determined from GPS-related data). (See, for example, FIGS. 12B and 12C). Here, in one embodiment, heart rate as a function of speed may be “plotted” for the user, or the data may be broken down into different levels including, but not limited to, sleeping, resting, sedentary, moderately active, active, and highly active.

[0221] Indeed, some embodiments of biometric monitoring devices may also correlate GPS-related data to a database of predetermined geographic locations that have activities associated with them for a set of predetermined conditions. For example, activity determination and corre-

sponding physiological classification (for example, heart rate classification) may include correlating a user's GPS coordinates that correspond to location(s) of exercise equipment, health club and/or gym and physiological data. Under these circumstances, a user's heart rate during, for example a gym workout, may be automatically measured and displayed. Notably, many physiological classifications may be based on GPS-related data including location, acceleration, altitude, distance and/or velocity. Such a database including geographic data and physiological data may be compiled, developed and/or stored on the biometric monitoring device and/or external computing device. Indeed, in one embodiment, the user may create their own location database or add to or modify the location database to better classify their activities.

[0222] In another embodiment, the user may simultaneously wear multiple biometric monitoring devices (having any of the features described herein). The biometric monitoring devices of this embodiment may communicate with each other or a remote device using wired or wireless circuitry to calculate, for example, biometric or physiologic qualities or quantities that, for example, may be difficult or inaccurate to calculate otherwise, such as pulse transit time. The use of multiple sensors may also improve the accuracy and/or precision of biometric measurements over the accuracy and/or precision of a single sensor. For example, having a biometric tracking device on the waist, wrist, and ankle may improve the detection of the user taking a step over that of a single device in only one of those locations. Signal processing may be performed on the biometric tracking devices in a distributed or centralized method to provide measurements improved over that of a single device. This signal processing may also be performed remotely and communicated back to the biometric tracking devices after processing.

[0223] In another embodiment, heart rate or other biometric data may be correlated to a user's food log (a log of foods ingested by a user, their nutritional content, and portions thereof). Food log entries may be entered into the food log automatically or may be entered by the user themselves through interaction with the biometric monitoring device (or a secondary or remote device, e.g., a smartphone, in communication with the biometric monitoring device or some other device, e.g., a server, in communication with the biometric monitoring device). Information may be presented to the user regarding the biometric reaction of their body to one or more food inputs. For example, if a user has coffee, their heart rate may rise as a result of the caffeine. In another example, if a user has a larger portion of food late at night, it may take longer for them to fall asleep than usual. Any combination of food input and corresponding result in biometrics may be incorporated into such a feedback system.

[0224] The fusion of food intake data and biometric data may also enable some embodiments of biometric monitoring device to make an estimation of a user's glucose level. This may be particularly useful for users who have diabetes. With an algorithm which relates the glucose level to the user's activity (e.g. walking, running, calorie burn) and nutritional intake, a biometric monitoring device may be able to advise the user when they are likely to have an abnormal blood sugar level.

Processing Task Delegation

[0225] Embodiments of biometric monitoring devices may include one or more processors. Figures. For example, an independent application processor may be used to store and execute applications that utilize sensor data acquired and processed by one or more sensor processors (processor (s) that process data from physiological, environmental, and/or activity sensors). In the case where there are multiple sensors, there may also be multiple sensor processors. An application processor may have sensors directly connected to it as well. Sensor and application processors may exist as separate discrete chips or exist within the same packaged chip (multi-core). A device may have a single application processor, or an application processor and sensor processor, or a plurality of application processors and sensor processors.

[0226] In one embodiment, the sensor processor may be placed on a daughterboard that consists of all of the analog components. This board may have some of the electronics typically found on the main PCB such as, but not limited to, transimpedance amplifiers, filtering circuits, level shifters, sample-and-hold circuits, and a microcontroller unit. Such a configuration may allow the daughterboard to be connected to the main PCB through the use of a digital connection rather than an analog connection (in addition to any necessary power or ground connections). A digital connection may have a variety of advantages over an analog daughterboard to main PCB connection, including, but not limited to, a reduction in noise and a reduction in the number of necessary cables. The daughterboard may be connected to the main board through the use of a flex cable or set of wires.

[0227] Multiple applications may be stored on an application processor. An application may consist of executable code and data for the application, but is not limited to these. Data may consist of graphics or other information required to execute the application or it may be information output generated by the application. The executable code and data for the application may both reside on the application processor (or memory incorporated therein) or the data for the application may be stored and retrieved from an external memory. External memory may include but is not limited to NAND flash, NOR flash, flash on another processor, other solid-state storage, mechanical or optical disks, RAM, etc.

[0228] The executable code for an application may also be stored in an external memory. When a request to execute an application is received by the application processor, the application processor may retrieve the executable code and/or data from the external storage and execute it. The executable code may be temporarily or permanently stored on the memory or storage of the application processor. This allows the application to be executed more quickly on the next execution request, since the step of retrieval is eliminated. When the application is requested to be executed, the application processor may retrieve all of the executable code of the application or portions of the executable code. In the latter case, only the portion of executable code required at that moment is retrieved. This allows applications that are larger than the application processor's memory or storage to be executed.

[0229] The application processor may also have memory protection features to prevent applications from overwriting, corrupting, interrupting, blocking, or otherwise interfering with other applications, the sensor system, the application processor, or other components of the system.

[0230] Applications may be loaded onto the application processor and/or any external storage via a variety of wired, wireless, optical, or capacitive mechanisms including, but not limited to, USB, Wi-Fi, Bluetooth, Bluetooth Low Energy, NFC, RFID, Zigbee.

[0231] Applications may also be cryptographically signed with an electronic signature. The application processor may restrict the execution of applications to those that have the correct signature.

Integration of Systems in a Biometric Monitoring Device

[0232] In some implementations of biometric monitoring devices, some sensors or electronic systems in the biometric monitoring device may be integrated with one another or may share components or resources. For example, a photodetector for an optically-based heart rate sensor (such as may be used in the heart-rate sensors discussed in U.S. Provisional Patent Application No. 61/946,439, filed Feb. 28, 2014, and previously incorporated by reference herein, may also serve as a photodetector for determining ambient light level, such as may be used to correct for the effects of ambient light on the heart rate sensor reading. For example, if the light source for such a heart rate detector is turned off, the light that is measured by the photodetector may be indicative of the amount of ambient light that is present.

[0233] In some implementations of a biometric monitoring device, the biometric monitoring device may be configured or communicated with using onboard optical sensors such as the components in an optical heart rate monitor. For example, the photodetectors of an optical heart-rate sensor (or, if present, an ambient light sensor) may also serve as a receiver for an optically-based transmission channel, e.g., infrared communications.

[0234] In some implementations of a biometric monitoring device, a hybrid antenna may be included that combines a radio frequency antenna, e.g., a Bluetooth antenna or GPS antenna, with an inductive loop, such as may be used in a near-field communications (NFC) tag or in an inductive charging system. In such implementations, the functionality for two different systems may be provided in one integrated system, saving packing volume. In such a hybrid antenna, an inductive loop may be placed in close proximity to the radiator of an inverted-F antenna. The inductive loop may inductively couple with the radiator, allowing the inductive loop to serve as a planar element of the antenna for radio-frequency purposes, thus forming, for example, a planar inverted-F antenna. At the same time, the inductive loop may also serve its normal function, e.g., such as providing current to an NFC chip through inductive coupling with an electromagnetic field generated by an NFC reader. Examples of such hybrid antenna systems are discussed in more detail in U.S. Provisional Patent Application No. 61/948,470, filed Mar. 5, 2014, which was previously incorporated herein by reference in the “Cross-Reference to Related Applications” section and which is again hereby incorporated by reference with respect to content directed at hybrid antenna structures. Of course, such hybrid antennas may also be used in other electronic devices other than biometric monitoring devices, and such non-biometric-monitoring-device use of hybrid antennas is contemplated as being within the scope of this disclosure.

Methods of Wearing the Device

[0235] Some embodiments of biometric monitoring devices may include a housing having a size and shape that

facilitates fixing the biometric monitoring device to the user's body during normal operation wherein the device, when coupled to the user, does not measurably or appreciably impact the user's activity. The biometric monitoring device may be worn in different ways depending on the specific sensor package that is integrated into the biometric monitoring device and the data that the user would like to acquire.

[0236] A user may wear some embodiments of the biometric monitoring devices of the present disclosure on their wrist or ankle (or arm or leg) with the use of a band that is flexible and thereby readily fitted to the user. The band may have an adjustable circumference, therefore allowing it to be fitted to the user. The band may be constructed from a material that shrinks when exposed to heat, therefore allowing the user to create a custom fit. The band may be detachable from the “electronics” portion of the biometric monitoring device and, if necessary, replaceable.

[0237] In some embodiments, the biometric monitoring device may consist of two major components—a body (containing the “electronics”) and a band (that facilitates attaching the device to the user). The body may include a housing (made, for example, of a plastic or plastic-like material) and extension tabs projecting from the body (made, for example, from a metal or metal-like material). (See, for example, FIGS. 2C through 3C). The band (made, for example, of a thermoplastic urethane) may be attachable to the body, e.g., mechanically or adhesively. The band may extend out a fraction of the circumference of the user's wrist. The distal ends of the urethane band may be connected with a Velcro or a hook-and-loop elastic fabric band that loops around a D-Ring on one side and then attaches back to itself. In this embodiment, the closure mechanism may allow the user infinite band length adjustment (unlike an indexed hole and mechanical clasp closure). The Velcro or elastic fabric may be attached to the band in a manner that allows it to be replaced (for example, if it is worn or otherwise undesirable to wear before the useful end of life of the device). In one embodiment, the Velcro or fabric may be attached with screws or rivets and/or glue, adhesives, and/or a clasp to the band.

[0238] Embodiments of the biometric monitoring devices of the present disclosure may also be integrated into and worn in a necklace, chest band, bra, adhesive patch, glasses, earring, or toe band. Such biometric monitoring devices may be built in such a way that the sensor package/portion of the biometric monitoring device is removable and may be worn in any number of ways including, but not limited to, those listed above.

[0239] In another embodiment, embodiments of biometric monitoring devices of the present disclosure may be worn clipped to an article of clothing or deposited in clothing (e.g., pocket) or an accessory (e.g., handbag, backpack, wallet). Because such biometric monitoring devices may not be near the user's skin, in embodiments that include heart rate measurements, the measurements may be obtained in a discrete, “on demand” context by the user manually placing the device into a specific mode (e.g., by depressing a button, covering a capacitive touch sensor with a fingertip, etc., possibly with the heart rate sensor embedded in the button/sensor) or automatically once the user places the device against the skin (e.g., applying the finger to an optical heart rate sensor).

User Interface with the Device

[0240] Some embodiments of a biometric monitoring device may include functionality for allowing one or more methods of interacting with the device either locally or remotely.

[0241] In some embodiments, the biometric monitoring device may convey data visually through a digital display. The physical embodiment of this display may use any one or a plurality of display technologies including, but not limited to one or more of LED, LCD, AMOLED, E-Ink, Sharp display technology, graphical displays, and other display technologies such as TN, HTN, STN, FSTN, TFT, IPS, and OLET. This display may show data acquired or stored locally on the device or may display data acquired remotely from other devices or Internet services. The biometric monitoring device may use a sensor (for example, an Ambient Light Sensor, “ALS”) to control or adjust the amount of screen backlighting, if backlighting is used. For example, in dark lighting situations, the display may be dimmed to conserve battery life, whereas in bright lighting situations, the display brightness may be increased so that it is more easily read by the user.

[0242] In another embodiment, the biometric monitoring device may use single or multicolor LEDs to indicate a state of the device. States that the biometric monitoring device may indicate using LEDs may include, but are not limited to, biometric states such as heart rate or application states such as an incoming message or that a goal has been reached. These states may be indicated through the LED’s color, the LED being on or off (or in an intermediate intensity), pulsing (and/or rate thereof) of the LEDs, and/or a pattern of light intensities from completely off to highest brightness. In one embodiment, an LED may modulate its intensity and/or color with the phase and frequency of the user’s heart rate.

[0243] In some embodiments, the use of an E-Ink display may allow the display to remain on without the battery drain of a non-reflective display. This “always-on” functionality may provide a pleasant user experience in the case of, for example, a watch application where the user may simply glance at the biometric monitoring device to see the time. The E-Ink display always displays content without comprising the battery life of the device, allowing the user to see the time as they would on a traditional watch.

[0244] Some implementations of a biometric monitoring device may use a light such as an LED to display the heart rate of the user by modulating the amplitude of the light emitted at the frequency of the user’s heart rate. The device may depict heart rate zones (e.g., aerobic, anaerobic, etc.) through the color of an LED (e.g., green, red) or a sequence of LEDs that light up in accordance with changes in heart rate (e.g., a progress bar). The biometric monitoring device may be integrated or incorporated into another device or structure, for example, glasses or goggles, or communicate with glasses or goggles to display this information to the user.

[0245] Some embodiments of a biometric monitoring device may also convey information to a user through the physical motion of the device. One such embodiment of a method to physically move the device is the use of a vibration-inducing motor. The device may use this method alone, or in combination with a plurality of other motion-inducing technologies.

[0246] In some implementations, a biometric monitoring device may convey information to a user through audio

feedback. For example, a speaker in the biometric monitoring device may convey information through the use of audio tones, voice, songs, or other sounds.

[0247] These three information communication methods—visual, motion, and auditory—may, in various embodiments of biometric monitoring devices, be used alone or in any combination with each other or another method of communication to communicate any one or plurality of the following information:

[0248] That a user needs to wake up at certain time

[0249] That a user should wake up as they are in a certain sleep phase

[0250] That a user should go to sleep as it is a certain time

[0251] That a user should wake up as they are in a certain sleep phase and in a preselected time window bounded by the earliest and latest time that the user wants to wake up.

[0252] That an email was received

[0253] That the user has been inactive for a certain period of time. Notably, this may integrate with other applications like, for instance, a meeting calendar or sleep tracking application to block out, reduce, or adjust the behavior of the inactivity alert.

[0254] That the user has been active for a certain period of time

[0255] That the user has an appointment or calendar event

[0256] That the user has reached a certain activity metric

[0257] That the user has gone a certain distance

[0258] That the user has reached a certain mile pace

[0259] That the user has reached a certain speed

[0260] That the user has accumulated a certain elevation gain

[0261] That the user has taken a certain number of steps

[0262] That the user has had a heart rate measurement recently

[0263] That the user’s heart rate has reached a certain level

[0264] That the user has a normal, active, or resting heart rate of a specific value or in a specific range

[0265] That the user’s heart rate has enter or exited a certain goal range or training zone

[0266] That the user has a new heart rate “zone” goal to reach, as in the case of heart rate zone training for running, bicycling, swimming, etc. activities

[0267] That the user has swum a lap or completed a certain number of laps in a pool

[0268] An external device has information that needs to be communicated to the user such as an incoming phone call or any one of the above alerts

[0269] That the user has reached a certain fatigue goal or limit. In one embodiment, fatigue may be determined through a combination of heart rate, galvanic skin response, motion sensor, and/or respiration data

[0270] These examples are provided for illustration and are not intended to limit the scope of information that may be communicated by such embodiments of biometric monitoring devices (for example, to the user). Note that the data used to determine whether or not an alert condition is met may be acquired from a first device and/or one or more secondary devices. The biometric monitoring device itself may determine whether the criteria or conditions for an alert

have been met. Alternatively, a computing device in communication with the biometric monitoring device (e.g., a server and/or a mobile phone) may determine when the alert should occur. In view of this disclosure, other information that the biometric monitoring device may communicate to the user may be envisioned by one of ordinary skill in the art. For example, the biometric monitoring device may communicate with the user when a goal has been met. The criteria for meeting this goal may be based on physiological, contextual, and environmental sensors on a first device, and/or other sensor data from one or more secondary devices. The goal may be set by the user or may be set by the biometric monitoring device itself and/or another computing device in communication with the biometric monitoring device (e.g. a server). In an example embodiment, the biometric monitoring device may vibrate when a biometric goal is met.

[0271] Some embodiments of biometric monitoring devices of the present disclosure may be equipped with wireless and/or wired communication circuitry to display data on a secondary device in real time. For example, such biometric monitoring devices may be able to communicate with a mobile phone via Bluetooth Low Energy in order to give real-time feedback of heart rate, heart rate variability, and/or stress to the user. Such biometric monitoring devices may coach or grant “points” for the user to breathe in specific ways that alleviate stress (e.g. by taking slow, deep breaths). Stress may be quantified or evaluated through heart rate, heart rate variability, skin temperature, changes in motion-activity data and/or galvanic skin response.

[0272] Some embodiments of biometric monitoring devices may receive input from the user through one or more local or remote input methods. One such embodiment of local user input may use a sensor or set of sensors to translate a user’s movement into a command to the device. Such motions could include but may not be limited to tapping, rolling the wrist, flexing one or more muscles, and swinging one’s arm. Another user input method may be through the use of a button such as, but not limited to, capacitive touch buttons, capacitive screen buttons, and mechanical buttons. In one embodiment, the user interface buttons may be made of metal. In embodiments where the screen uses capacitive touch detection, it may always be sampling and ready to respond to any gesture or input without an intervening event such as pushing a physical button. Such biometric monitoring devices may also take input through the use of audio commands. All of these input methods may be integrated into biometric monitoring devices locally or integrated into a remote device that can communicate with such biometric monitoring devices, either through a wired or wireless connection. In addition, the user may also be able to manipulate the biometric monitoring device through a remote device. In one embodiment, this remote device may have Internet connectivity.

Alarms

[0273] In some embodiments, the biometric monitoring device of the present disclosure may act as a wrist-mounted vibrating alarm to silently wake the user from sleep. Such biometric monitoring devices may track the user’s sleep quality, waking periods, sleep latency, sleep efficiency, sleep stages (e.g., deep sleep vs REM), and/or other sleep-related metrics through one or a combination of heart rate, heart rate variability, galvanic skin response, motion sensing (e.g., accelerometer, gyroscope, magnetometer), and skin tem-

perature. The user may specify a desired alarm time or window of time (e.g., set alarm to go off between 7 am and 8 am). Such embodiments may use one or more of the sleep metrics to determine an optimal time within the alarm window to wake the user. In one embodiment, when the vibrating alarm is active, the user may cause it to hibernate or turn off by slapping or tapping the device (which is detected, for example, via motion sensor(s), a pressure/force sensor, and/or capacitive touch sensor in the device). In one embodiment, the device may attempt to arouse the user at an optimum point in the sleep cycle by starting a small vibration at a specific user sleep stage or time prior to the alarm setting. It may progressively increase the intensity or noticeability of the vibration as the user progresses toward wakefulness or toward the alarm setting. (See, for example, FIG. 8).

[0274] FIG. 8 illustrates functionality of an example portable biometric monitoring device smart alarm feature. The biometric monitoring device may be able to detect or may be in communication with a device that can detect the sleep stage or state of a user (e.g., light or deep sleep). The user may set a window of time which they would like to be awoken (e.g., 6:15 am to 6:45 am). The smart alarm may be triggered by the user going into a light sleep state during the alarm window.

[0275] The biometric monitoring device may be configured to allow the user to select or create an alarm vibration pattern of their choice. The user may have the ability to “snooze” or postpone an alarm event. In one embodiment, the user may be able to set the amount of delay for the “snooze” feature—the delay being the amount of time before the alarm will go off again. They may also be able to set how many times the snooze feature may be activated per alarm cycle. For example, a user may choose a snooze delay of 5 minutes and a maximum sequential snooze number to be 3. Therefore, they can press snooze up to 3 times to delay the alarm by 5 minutes each time they press snooze to delay the alarm. In such embodiments, the snooze function will not turn off the alarm if the user attempts to press snooze a fourth time.

[0276] Some biometric monitoring devices may have information about the user’s calendar and/or schedule. The user’s calendar information may be entered directly into the biometric monitoring device or it may be downloaded from a different device (e.g. a smartphone). This information may be used to automatically set alarms or alarm characteristics. For example, if a user has a meeting at 9 am in the morning, the biometric monitoring device may automatically wake the user up at 7:30 am to allow the user enough time to prepare for and/or get to the meeting. The biometric monitoring device may determine the amount of time required for the user to prepare for the meeting based on the user’s current location, the location of the meeting, and the amount of time it would take to get the location of the meeting from the user’s current location. Alternatively, historical data about how long the user takes to get to the meeting location and/or prepare to leave for the meeting (e.g. how long it takes to wake up, take a shower, have breakfast, etc. in the morning) may be used to determine at what time to wake the user. A similar functionality may be used for calendar events other than meetings such as eating times, sleeping times, napping times, and exercise times.

[0277] In some embodiments, the biometric monitoring device may use information on when the user went to sleep

to determine when an alarm should go off to wake the user. This information may supplement calendar information described herein. The user may have a goal of approximately how many hours of sleep they would like to get each night or week. The biometric monitoring device may set the morning alarm at the appropriate time for the user to meet these sleep goals. In addition to amount of time that the user would like to sleep each night, other sleep goals that the user may set may include, but are not limited to, the amount of deep sleep, REM sleep, and light sleep that the user experiences while sleeping, all of which may be used by the biometric monitoring device to determine when to set an alarm in the morning. Additionally, the user may be alerted at night when they should go to bed to meet their sleep goals. Additionally, the user may be alerted during the day when they should take a nap to meet their sleep goals. The time at which to alert a user that they should take a nap may be determined by factors that optimize the user's sleep quality during the nap, subsequent naps, or night-time sleep. For example, the user is likely to have a hard time falling asleep at night if they took a nap in the early evening. The user may also be advised to eat certain foods or drinks or avoid certain foods or drinks to optimize their sleep quality. For example, a user may be discouraged from drinking alcohol close to their bed time as it is likely to decrease their sleep quality. The user may also be advised to perform certain activities or avoid certain activities to optimize their sleep quality. For example, a user may be encouraged to exercise in the early afternoon to improve their sleep quality. A user may be discouraged from exercising or watching TV close to their bedtime to improve their sleep quality.

User Interface with a Secondary Device

[0278] In some embodiments, the biometric monitoring device may transmit and receive data and/or commands to and/or from a secondary electronic device. The secondary electronic device may be in direct or indirect communication with the biometric monitoring device. Direct communication refers herein to the transmission of data between a first device and a secondary device without any intermediary devices. For example, two devices may communicate to one another over a wireless connection (e.g. Bluetooth) or a wired connection (e.g. USB). Indirect communication refers to the transmission of data between a first device and a secondary device with the aid of one or multiple intermediary third devices which relay the data. Third devices may include, but are not limited to, a wireless repeater (e.g. WiFi repeater), a computing device such as a smartphone, laptop, desktop or tablet computer, a cell phone tower, a computer server, and other networking electronics. For example, a biometric device may send data to a smartphone which forwards the data through a cellular network data connection to a server which is connected through the internet to the cellular network.

[0279] In some embodiments, the secondary device that acts as a user interface to the biometric monitoring device may consist of a smartphone. An app on the smart phone may facilitate and/or enable the smartphone to act as a user interface to the biometric monitoring device. The biometric monitoring device may send biometric and other data to the smartphone in real-time or with some delay. The smartphone may send a command or commands to the biometric monitoring device, for example, to instruct it to send biometric and other data to the smartphone in real-time or with some delay. For example, if the user enters a mode in the app for

tracking a run, the smartphone may send a command to the biometric device to instruct it to send data in real-time. Therefore, the user can track their run on their app as they go along without any delay.

[0280] Such a smartphone may have one or multiple apps to enable the user to view data from their biometric device or devices. The app may, by default, open to a "dashboard" page when the user launches or opens the app. On this page, summaries of data totals such as the total number of steps, floors climbed miles traveled, calories burned, calories consumed and water consumed may be shown. Other pertinent information such as the last time the app received data from the biometric monitoring device, metrics regarding the previous night's sleep (e.g. when the user went to sleep, woke up, and how long they slept for), and how many calories the user can eat in the day to maintain their caloric goals (e.g. a calorie deficit goal to enable weight loss) may also be shown. The user may be able to choose which of these and other metrics are shown on the dashboard screen. The user may be able to see these and other metrics on the dashboard for previous days. They may be able to access previous days by pressing a button or icon on a touchscreen. Alternatively, gestures such as swiping to the left or right may enable the user to navigate through current and previous metrics.

[0281] The smartphone app may also have another page which provides a summary of the user's activities. Activities may include, but are not limited to, walking, running, biking, cooking, sitting, working, swimming, working out, weight-lifting, commuting, and yoga. Metrics pertinent to these activities may be presented on this page. For example, a bar graph may show how the number of steps the user took for different portions of the day (e.g. how many steps every 5 minutes or 1 hour). In another example, the amount of time the user spent performing a certain activity and how many calories were burned in this period of time may be displayed. Similar to the dashboard page, the app may provide navigational functionality to allow the user to see these and other metrics for past days. Other time periods such as an hour, minute, week, month or year may also be selected by the user to enable them to view trends and metrics of their activities over shorter or larger spans of time.

[0282] The smartphone app may also have an interface to log food that has been, or will be, eaten by the user. This interface may have a keyword search feature to allow the user to quickly find the food that they would like to enter into their log. As an alternative to, or in addition to, searching for foods, users may have the ability to find a food to log by navigating through a menu or series of menus. For example, a user may choose the following series of categories—breakfast/cereal/healthy/oatmeal to arrive at the food which they would like to log (e.g., apple-flavored oatmeal). At any one of these menus, the user may be able to perform a keyword search. For example, the user may search for "oatmeal" after having selected the category "breakfast" to search for the keyword "oatmeal" within the category of breakfast foods. After having selected the food that they would like to log, the user may be able to modify or enter the serving size and nutritional content. After having logged at least one food, the app may display a summary of the foods that were logged in a certain time period (e.g. a day) and the nutritional content of the foods (individual and total calorie content, vitamin content, sugar content, etc.).

[0283] The smartphone app may also have a page that displays metrics regarding the user's body such as the user's

weight, body fat percentage, BMI, and waist size. It may display a graph or graphs showing the trend of one or multiple of these metrics over a certain period of time (e.g., two weeks). The user may be able to choose the value of this period of time and view previous time periods (e.g., last month).

[0284] The smartphone app may also have a page which allows the user to enter how much water the user has consumed. Each time the user drinks some water, they may enter that amount in the unit of their choice (e.g., ozs., cups, etc.). The app may display the total of all of the water the user has logged within a certain time period (e.g., a day). The app may allow the user to see previously-logged water entries and daily totals for previous days as well as the current day.

[0285] The smartphone app may also have a page that displays online friends of the user. This “friends” page may enable the user to add or request new friends (e.g., by searching for their name or by their email address). This page may also display a leaderboard of the user and his or her friends. The user and his or her friends may be ranked based on one or more metrics. For example, the user and his or her friends may be ranked using the total of the past seven days’ step counts.

[0286] The smartphone app may also have a page that shows metrics regarding the user’s sleep for the previous night and/or previous nights. This page may also enable the user to log when they slept in the past by specifying when they went to bed and when they woke. The user may also have the ability to enter a subjective metric about their sleep (e.g., bad night’s rest, good night’s rest, excellent night’s rest, etc.). The user may be able to view these metrics for days or time periods (e.g., two weeks) in the past. For example, the sleep page may default to showing a bar graph of the amount of time the user slept each night in the last two weeks. The user may be able to also view a bar graph of the amount of time the user slept each night in the last month.

[0287] The user may also be able to access the full capabilities of the smartphone app described herein (e.g., the ability to enter food logs, view dashboard, etc.) through an alternative or additional interface. In one embodiment, this alternative interface may consist of a webpage that is hosted by a server in indirect communication with the biometric monitoring device. The webpage may be accessed through any internet connected device using a program such as a web browser.

Wireless Connectivity and Data Transmission

[0288] Some embodiments of biometric monitoring devices of the present disclosure may include a means of wireless communication to transmit and receive information from the Internet and/or other devices. The wireless communication may consist of one or more interfaces such as Bluetooth, ANT, WLAN, power-line networking, and cell phone networks. These are provided as examples and should not be understood to exclude other existing wireless communication methods or protocols, or wireless communication techniques or protocols that are yet to be invented.

[0289] The wireless connection may be bi-directional. The biometric monitoring device may transmit, communicate and/or push its data to other devices, e.g., smart phones, computers, etc., and/or the Internet, e.g., web servers and the like. The biometric monitoring device may also receive, request and/or pull data from other devices and/or the Internet.

[0290] The biometric monitoring device may act as a relay to provide communication for other devices to each other or to the Internet. For example, the biometric monitoring device may connect to the Internet via WLAN but also be equipped with an ANT radio. An ANT device may communicate with the biometric monitoring device to transmit its data to the Internet through the biometric monitoring device’s WLAN (and vice versa). As another example, the biometric monitoring device may be equipped with Bluetooth. If a Bluetooth-enabled smart phone comes within range of the biometric monitoring device, the biometric monitoring device may transmit data to, or receive data from, the Internet through the smart phone’s cell phone network. Data from another device may also be transmitted to the biometric monitoring device and stored (or vice versa) or transmitted at a later time.

[0291] Embodiments of biometric monitoring devices of the present disclosure may also include functionality for streaming or transmitting web content for display on the biometric monitoring device. The following are typical examples of such content:

- [0292]** 1. Historical graphs of heart rate and/or other data measured by the device but stored remotely
- [0293]** 2. Historical graphs of user activity and/or foods consumed and/or sleep data that are measured by other devices and/or stored remotely (e.g., such as at a website like fitbit.com)
- [0294]** 3. Historical graphs of other user-tracked data that are stored remotely. Examples include heart rate, blood pressure, arterial stiffness, blood glucose levels, cholesterol, duration of TV watching, duration of video game play, mood, etc.
- [0295]** 4. Coaching and/or dieting data based on one or more of the user’s heart rate, current weight, weight goals, food intake, activity, sleep, and other data.
- [0296]** 5. User progress toward heart rate, weight, activity, sleep, and/or other goals.
- [0297]** 6. Summary statistics, graphics, badges, and/or metrics (e.g., “grades”) to describe the aforementioned data
- [0298]** 7. Comparisons between the aforementioned data for the user and similar data for his/her “friends” with similar devices and/or tracking methods
- [0299]** 8. Social content such as Twitter feeds, instant messaging, and/or Facebook updates
- [0300]** 9. Other online content such as newspaper articles, horoscopes, weather reports, RSS feeds, comics, crossword puzzles, classified advertisements, stock reports, and websites
- [0301]** 10. Email messages and calendar schedules

[0302] Content may be delivered to the biometric monitoring device according to different contexts. For instance, in the morning, news and weather reports may be displayed along with the user’s sleep data from the previous night. In the evening, a daily summary of the day’s activities may be displayed.

[0303] Various embodiments of biometric monitoring devices as disclosed herein may also include NFC, RFID, or other short-range wireless communication circuitry that may be used to initiate functionality in other devices. For instance, a biometric monitoring device may be equipped with an NFC antenna so that when a user puts it into close proximity with a mobile phone, an app is launched automatically on the mobile phone.

[0304] These examples are provided for illustration and are not intended to limit the scope of data that may be transmitted, received, or displayed by the device, nor any intermediate processing that may occur during such transfer and display. In view of this disclosure/application, many other examples of data that may be streamed to or via a biometric monitoring device may be envisioned by one reasonably skilled in the art.

Charging and Data Transmission

[0305] Some embodiments of biometric monitoring devices may use a wired connection to charge an internal rechargeable battery and/or transfer data to a host device such as a laptop or mobile phone. In one embodiment, similar to one discussed earlier in this disclosure, the biometric monitoring device may use magnets to help the user align the biometric monitoring device to a dock or cable. The magnetic field of magnets in the dock or cable and the magnets in the device itself may be strategically oriented so as to force the biometric monitoring device to self-align with the dock or cable (or, more specifically, a connector on the cable) and so as to provide a force that holds the biometric monitoring device in the dock or to the cable. The magnets may also be used as conductive contacts for charging or data transmission purposes. In another embodiment, a permanent magnet may only be used in the dock or cable side and not in the biometric monitoring device itself. This may improve the performance of the biometric monitoring device where the biometric monitoring device employs a magnetometer. If there is a magnet in the biometric monitoring device, the strong field of a nearby permanent magnet may make it significantly more difficult for the magnetometer to accurately measure the earth's magnetic field. In such embodiments, the biometric monitoring device may utilize a ferrous material in place of a magnet, and the magnets on the dock or cable side may attach to the ferrous material.

[0306] In another embodiment, the biometric monitoring device may contain one or more electromagnets in the biometric monitoring device body. The charger or dock for charging and data transmission may also contain an electromagnet and/or a permanent magnet. The biometric monitoring device could only turn on its electromagnet when it is close to the charger or dock. The biometric monitoring device may detect proximity to the dock or charger by looking for the magnetic field signature of a permanent magnet in the charger or dock using a magnetometer. Alternatively, the biometric monitoring device may detect proximity to the charger by measuring the Received Signal Strength Indication (RSSI) of a wireless signal from the charger or dock, or, in some embodiments, by recognizing an NFC or RFID tag associated with the charger or dock. The electromagnet could be reversed, creating a force that repels the device from the charging cable or dock either when the device doesn't need to be charged, synced, or when it has completed syncing or charging. In some embodiments, the charger or dock may include the electromagnet and may be configured (e.g., a processor in the charger or dock may be configured via program instructions) to turn the electromagnet on when a biometric monitoring device is connected for charging (the electromagnet may normally be left on such that a biometric monitoring device that is placed on the charger is drawn against the charger by the electromagnet, or the electromagnet may be left off until the charger determines that a biometric monitoring device has been placed on

the charger, e.g., through completion of a charging circuit, recognition of an NFC tag in the biometric monitoring device, etc., and then turned on to draw the biometric monitoring device against the charger. Upon completion of charging (or of data transfer, if the charger is actually a data transfer cradle or a combined charger/data transfer cradle), the electromagnet may be turned off (either temporarily or until the biometric monitoring device is again detected as being placed on the charger) and the biometric monitoring device may stop being drawn against the charger. In such embodiments, it may be desirable to orient the interface between the biometric monitoring device and the charger such that, in the absence of a magnetic force generated by the electromagnet, the biometric monitoring device would fall off of the charger or otherwise shift into a visibly different position from the charging position (to visually indicate to a user that charging or data transfer is complete).

Sensor Use in Data Transfer

[0307] In some implementations, biometric monitoring devices may include a communications interface that may switch between two or more protocols that have different data transmission rates and different power consumption rates. Such switching may be driven by data obtained from various sensors of the biometric monitoring device. For example, if Bluetooth is used, the communications interface may switch between using Bluetooth base rate/enhanced data rate (BR/EDR) and Bluetooth low energy (BLE) protocols responsive to determinations made based on data from the sensors of the biometric monitoring device. For example, the lower-power, slower BLE protocol may be used when sensor data from accelerometers in a biometric monitoring device indicates that the wearer is asleep or otherwise sedentary. By contrast, the higher-power, faster BR/EDR protocol may be used when sensor data from the accelerometers in a biometric monitoring device indicates that the wearer is walking around. Such adaptive data transmission techniques and functionality are discussed further in U.S. Provisional Patent Application No. 61/948,468, filed Mar. 5, 2014, which was previously incorporated herein by reference in the "Cross-Reference to Related Applications" section and which is again hereby incorporated by reference with respect to content directed at adaptive data transfer rates in biometric monitoring devices.

[0308] Such communication interfaces may also serve as a form of sensor for a biometric monitoring device. For example, a wireless communications interface may allow a biometric monitoring device to determine the number and type of devices that are within range of the wireless communications interface. Such data may be used to determine if the biometric monitoring device is in a particular context, e.g., indoors, in a car, etc., and to change its behavior in various ways in response to such a determination. For example, as discussed in U.S. Provisional Patent Application No. 61/948,468 (incorporated by reference above), such contexts may be used to drive the selection of a particular wireless communications protocol to use for wireless communications.

Configurable App Functionality

[0309] In some embodiments, biometric monitoring devices of the present disclosure may include a watch-like form factor and/or a bracelet, armlet, or ankle form factor

and may be programmed with “apps” that provide specific functionality and/or display specific information. Apps may be launched or closed by a variety of means including, but not limited to, pressing a button, using a capacitive touch sensor, performing a gesture that is detected by an accelerometer, moving to a specific location or area detected by a GPS or motion sensor, compressing the biometric monitoring device body (thereby creating a pressure signal inside the device that may be detected by an altimeter inside the biometric monitoring device), or placing the biometric monitoring device close to an NFC tag that is associated with an app or set of apps. Apps may also be automatically triggered to launch or close by certain environmental or physiological conditions including, but not limited to, detection of a high heart rate, detection of water using a wet sensor (to launch a swimming application, for example), a certain time of day (to launch a sleep tracking application at night, for example), a change in pressure and motion characteristic of a plane taking off or landing to launch and close an “airplane” mode app. Apps may also be launched or closed by meeting multiple conditions simultaneously. For example, if an accelerometer detects that a user is running and the user presses a button, the biometric monitoring device may launch a pedometer application, an altimeter data collection application, and/or display. In another case where the accelerometer detects swimming and the user presses the same button, it may launch a swimming lap-counting application.

[0310] In some embodiments, the biometric monitoring device may have a swim-tracking mode that may be launched by starting a swimming app. In this mode, the biometric monitoring device’s motion sensors and/or magnetometer may be used to detect swim strokes, classify swim stroke types, detect swimming laps, and other related metrics such as stroke efficiency, lap time, speed, distance, and calorie burn. Directional changes indicated by the magnetometer may be used to detect a diversity of lap turn methods. In a preferred embodiment, data from a motion sensor and/or pressure sensor may be used to detect strokes.

[0311] In another embodiment, a bicycling app may be launched by moving the biometric monitoring device within proximity of an NFC or RFID tag that is located on the bicycle, on a mount on the bicycle, or in a location associated with a bicycle including, but not limited to, a bike rack or bike storage facility. (See, for example, FIG. 10). The app launched may use a different algorithm than is normally used to determine metrics including, but not limited to, calories burned, distance traveled, and elevation gained. The app may also be launched when a wireless bike sensor is detected including, but not limited to, a wheel sensor, GPS, cadence sensor, or power meter. The biometric monitoring device may then display and/or record data from the wireless bike sensor or bike sensors.

[0312] Additional apps include, but are not limited to, a programmable or customizable watch face, stop watch, music player controller (e.g., mp3 player remote control), text message and/or email display or notifier, navigational compass, bicycle computer display (when communicating with a separate or integrated GPS device, wheel sensor, or power meter), weight-lifting tracker, sit-up reps tracker, pull up reps tracker, resistance training form/workout tracker, golf swing analyzer, tennis (or other racquet sport) swing/serve analyzer, tennis game swing detector, baseball swing analyzer, ball throw analyzer (e.g., football, baseball), orga-

nized sports activity intensity tracker (e.g., football, baseball, basketball, volleyball, soccer), disk throw analyzer, food bite detector, typing analyzer, tilt sensor, sleep quality tracker, alarm clock, stress meter, stress/relaxation biofeedback game (e.g., potentially in combination with a mobile phone that provides auditory and/or visual cues to train user breathing in relaxation exercises), teeth brushing tracker, eating rate tracker (e.g., to count or track the rate and duration by which a utensil is brought to the mouth for food intake), intoxication or suitability to drive a motor vehicle indicator (e.g., through heart rate, heart rate variability, galvanic skin response, gait analysis, puzzle solving, and the like), allergy tracker (e.g., using galvanic skin response, heart rate, skin temperature, pollen sensing and the like (possibly in combination with external seasonal allergen tracking from, for instance, the internet and possibly determining the user’s response to particular forms of allergen, e.g., tree pollen, and alerting the user to the presence of such allergens, e.g., from seasonal information, pollen tracking databases, or local environmental sensors in the biometric monitoring device or employed by the user), fever tracker (e.g., measuring the risk, onset, or progress of a fever, cold, or other illness, possibly in combination with seasonal data, disease databases, user location, and/or user provided feedback to assess the spread of a particular disease (e.g., flu) in relation to a user, and possibly prescribing or suggesting the abstinence of work or activity in response), electronic games, caffeine affect tracker (e.g., monitoring the physiologic response such as heart rate, heart rate variability, galvanic skin response, skin temperature, blood pressure, stress, sleep, and/or activity in either short term or long term response to the intake or abstinence of coffee, tea, energy drinks and/or other caffeinated beverages), drug affect tracker (e.g., similar to the previously mentioned caffeine tracker but in relation to other interventions, whether they be medical or lifestyle drugs such as alcohol, tobacco, etc.), endurance sport coach (e.g., recommending or prescribing the intensity, duration, or profile of a running/bicycling/swimming workout, or suggesting the abstinence or delay of a workout, in accordance with a user specified goal such as a marathon, triathlon, or custom goal utilizing data from, for instance, historical exercise activity (e.g., distance run, pace), heart rate, heart rate variability, health/sickness/stress/fever state), weight and/or body composition, blood pressure, blood glucose, food intake or caloric balance tracker (e.g., notifying the user how many calories he may consume to maintain or achieve a weight), pedometer, and nail biting detector. In some cases, the apps may rely solely on the processing power and sensors of the present disclosure. In other cases, the apps may fuse or merely display information from an external device or set of external devices including, but not limited to, a heart rate strap, GPS distance tracker, body composition scale, blood pressure monitor, blood glucose monitor, watch, smart watch, mobile communication device such as a smart phone or tablet, or server.

[0313] In one embodiment, the biometric monitoring device may control a music player on a secondary device. Aspects of the music player that may be controlled include, but are not limited to, the volume, selection of tracks and/or playlists, skipping forward or backward, fast forwarding or rewinding of tracks, the tempo of the track, and the music player equalizer. Control of the music player may be via user input or automatic based on physiological, environmental, or contextual data. For example, a user may be able to select

and play a track on their smart phone by selecting the track through a user interface on the biometric monitoring device. In another example, the biometric monitoring device may automatically choose an appropriate track based on the activity level of the user (the activity level being calculated from biometric monitoring device sensor data). This may be used to help motivate a user to maintain a certain activity level. For example, if a user goes on a run and wants to keep their heart rate in a certain range, the biometric monitoring device may play an upbeat or higher tempo track if their heart rate is below the range which they are aiming for.

Automated Functions Triggered by User's Activity

Sleep Stage Triggered Functionality

[0314] Sleep stages can be monitored through various biometric signals and methods disclosed herein, such as heart rate, heart rate variability, body temperature, body motions, ambient light intensity, ambient noise level, etc. Such biometrics may be measured using optical sensors, motion sensors (accelerometers, gyroscopic sensors, etc.), microphones, and thermometers, for example, as well as other sensors discussed herein.

[0315] The biometric monitoring device may have a communication module as well, including, but not limited to, Wi-Fi (802.xx), Bluetooth (Classic, low power), or NFC. Once the sleep stages are estimated, the sleep stages may be transmitted to a cloud-based system, home server, or main control unit that is connected to communication-enabled appliances (with Wi-Fi, Bluetooth, or NFC) wirelessly. Alternatively, the biometric monitoring device may communicate directly with the communication-enabled appliances. Such communication-enabled appliances may include, for example, kitchen appliances such as microwaves, ovens, coffee grinders/makers, toasters, etc.

[0316] Once the sleep stages indicate that it is close the time for the user to wake up, the biometric monitoring device may send out a trigger to the appliances that the user has indicated should be operated automatically. For example, the coffee grinder and maker may be caused to start making coffee, and the toaster may be caused to start warming up bread. The microwave oven may be caused to start cooking oatmeal or eggs as well, and electric kettle to start boiling water. So long as the ingredients are appropriately prepared, this automated signal may trigger breakfast-cooking.

Alertness Detection

[0317] Alertness, e.g., a low alertness may correlate with a person being drowsy, may also be detected from the biometrics listed above, and may be used to trigger an appliance such as a coffee maker to start brewing coffee automatically.

Hydration

[0318] The portable biometric monitoring device in combination with an activity level tracker may submit the user's activity level to a cloud-based system, home server, main control unit, or appliances directly. This may trigger some actions of the appliances, especially related to hydration, such as starting the ice cube maker of a refrigerator, or lowering operating temperature of a water purifier.

Power Saving

[0319] Many appliances typically operate in a low-power idle state that consumes power. Using aggregated information of the user's biometric signals, communication-enabled appliances may be caused to go into a super-low power mode. For example, a water dispenser at home may shut itself down into a super-low-power mode when the user is asleep or out for work, and may start cooling/heating water once the user's activity at home is expected.

Restaurant Recommendation System Based on Location and Activity

[0320] Aggregation of real-time biometric signals and location information may be used to create an educated-guess on one or multiple users' needs for a given time, e.g., ionized drink. Combining this guessed need with historical user data on the user's activity levels, activity types, activity time, and activity durations, as well as food intake data logged by the users, an app on a smart phone and/or smart watch may recommend a restaurant that would meet the user's life-style and current need.

[0321] For example, a user who just finished a six mile circuit may launch this app. The app may know that this person maintained a high activity level for the past hour, and thus determine that the person may be dehydrated. From the historical user data, the app may also know, for example, that the user's diet is heavy on vegetables but low in sugar. With an optimization algorithm that considers the user's current location, price ranges, and other factors mentioned above, the app may recommend a restaurant that offers smoothies, for example.

Swim Tracking

[0322] In some embodiments of a biometric tracking device, the biometric tracking may include a swimming algorithm that may utilize data from one or more motion sensors, altitude sensors (e.g., such as a barometric pressure sensor), orientation sensors (e.g., magnetometer), location service sensor (e.g., GPS, wireless triangulation), and/or temperature sensors. The sensors may be embedded in a single device mounted to, for instance, the wrist. In other embodiments, extra sensor devices may be attached to the swimmer's forehead, back of the head, goggles, back, hip, shoulder, thighs, legs, and/or feet.

[0323] Three potential functional components of swimming exercise analysis are as follows:

[0324] Stroke count detection—provides stroke counts per lap, where a lap is defined to be a one-way traverse from one end of the pool to the opposite end.

[0325] Stroke type classification—describes the swimming stroke type of the user (e.g., crawl stroke, breast stroke, back stroke, butterfly stroke, side stroke, kicking without strokes, body streamline, etc.) and can be any or a combination of:

[0326] a. Classification of each stroke that a user takes

[0327] b. Classification of the predominant stroke type used per complete lap.

[0328] c. Classification of stroke type used per fractional lap (e.g. half a lap of freestyle, half a lap of breast stroke)

[0329] Lap count—counts the laps traversed by the user. One method of determining a lap is by detecting when the user turns in a pool.

[0330] Turning is defined to be a 180 degree change in heading direction. As a turn is detected, start and end of a lap may be inferred. Taking a break (no motion for a certain period of time) at a point in the pool (typically at one end or the other) before starting to swim again is also considered a turn as long as the following heading direction is opposite the heading prior to the break.

[0331] In some embodiments, these functional components may be combined in a multitude of ways.

Algorithm Structure

[0332] The three functional components of the swimming exercise analysis may be performed sequentially, in parallel, or in hybrid order (a combination of some sequential blocks and some parallel blocks).

Sequential Approach (See FIG. 15A)

[0333] In one embodiment, raw and/or pre-processed sensor signals may first be analyzed by a stroke detector algorithm. The stroke detector algorithm may use temporal peaks (local maxima and/or local minima) in a motion sensor (e.g., accelerometer, gyroscope) as an indication that a stroke has been taken. Then one or more heuristic rules may also be applied to remove peaks that do not represent strokes. For example, the magnitudes of the peaks, temporal distance of two adjacent peaks, peak-to-peak amplitude, and/or morphological characteristics of the peaks (e.g., sharpness) may indicate that certain peaks do not represent strokes. When sensors provide more than one dimensional data, e.g., such as 3-axis accelerometers, or 3 axis motion sensors+altimeter (totaling 4-axis data), timings and relevant sizes of peaks in all axes may be taken into account to determine whether or not the peaks in one or more of the axes are generated by a stroke or not.

[0334] If a single peak representing a stroke or group of peaks from multiple data axes representing strokes are observed, features may be extracted from a segment of data that are obtained from the time between when the previous peak is detected and when the current peak is detected. Features include, but are not limited to, maximum and minimum values, number of ripples in the segment, powers measured in various metrics, e.g., L1 power and L2 power, standard deviation, mean, etc. The extracted features may then be put through a machine learning system where the system coefficients are computed off-line (supervised learning) or are adapted as the user uses the biometric monitoring device (unsupervised learning). The machine learning system may then return a stroke classification for each detected stroke.

[0335] The turn-detector algorithm may search for sudden changes in motion by calculating derivatives, moving average, and/or using high-pass filtering on the signals of the sensors (the sensors including, but not limited to, those listed in this disclosure). Principal Component Analysis (PCA) can also and/or alternatively be performed on the signal(s). If one principle component is different from the sub-sequential one, then it may be determined that a turn occurred. Whole or partial coefficients of a transform, such as the Fast Fourier Transform (FFT) may be used as features as well. Parametric models such as Autoregressive (AR) models may also be used. Time-varying model parameters may then be estimated using Linear Prediction Analysis (LPA), Least Mean Squares filtering (LMS), Recursive Least Squares filtering

(RLS), and/or Kalman filtering. Estimated model parameters are then compared to determine if there is an abrupt change in their values.

[0336] In one embodiment, the skill level and/or swimming styles (e.g., speed) of the swimmer may be inferred from sensor data, and then used in turn detection. For example, advanced swimmers typically have more powerful strokes (i.e., large accelerometer peak magnitudes) and take fewer strokes to complete a lap. Therefore, metrics that estimate the swimmer's skill level or characteristics may be used in a turn detection algorithm. These metrics may include, but are not limited to averaged motion signals, or integrated motion signals in particular arm movements, estimated heading speed, and detected patterns of an advanced swimmer in motion signals. The swimmer's skill level or other characteristics may also be determined through user input. For example, the user may input that they are an advanced, intermediate, or beginner swimmer.

[0337] One or many (combined) features from these analyses may be used to detect if a given data sample, and/or neighboring data samples, have characteristics of a turn. To obtain the optimal combination of the features and decision boundary, one can utilize machine learning techniques such as logistic regression, decision tree, neural nets, etc.

[0338] In some embodiments, if a turn is detected, the swimming data accrued since the previous turn may be summarized, such as the number of strokes, stroke type for each stroke and for the lap, split time, etc. If no turn is detected, the stroke counter and type may be updated. Unless the user quits swimming, the algorithm may go back to stroke count detection.

Parallel Approach (See FIG. 15B)

[0339] In the parallel approach, some or all of the three functional components may be executed in parallel. For example, stroke-type detection and turn detection may be performed jointly, while stroke count detection is run independently.

[0340] In such embodiments, two functional components, stroke-type and turn detection, may be implemented in a single algorithm that simultaneously detects stroke-types and turns. For example, a classifier of swimming stroke types, e.g., movement analysis that detects free style strokes, breast stroke strokes, back strokes, butterfly strokes, and of turn types (e.g. tumble turn, flip turn, two hand touch) may return a detected type of stroke or a type of detected turn. During the detection, temporal as well as spectral features may be extracted. A moving window may first be applied to multiple axes of data. Statistics of this windowed segment may then be computed, namely, maximum and minimum value, number of ripples in the segment, powers measured in various metrics (e.g., L1 power and L2 power, standard deviation, mean). Independent component analysis (ICA) and/or principal component analysis (PCA) can be applied as well to find any hidden signals that better represent turn-type and stroke-type characteristics. Temporal features may then be computed from this (potentially improved) signal representation. For temporal features, various non-parametric filtering schemes, low-pass filtering, band-pass filtering, high-pass filtering, may be applied to enhance desired signal characteristics.

[0341] Spectral analysis such as FFT, wavelet transform, Hilbert transform, etc., may be applied to this windowed segment as well. Whole or partial transform coefficients may

be chosen as features. Parametric models such as AR, moving average (MA), or ARMA (autoregressive and moving average) models may be used, and the parameters of such a model may be found via autocorrelation and/or partial autocorrelation, or LPA, LMS, RLS, or Kalman filter. The entire or part of estimated coefficients may be used as features.

[0342] Different lengths of moving average windows may be run in parallel, and provide features listed above, and the whole or part of the features may be utilized as features as well.

[0343] Machine-learned coefficients (supervised learning) may then be applied to these extracted features. One or more machine learning techniques, namely multiple layers of binomial linear discriminant analysis (e.g., logistic regression), multinomial logistic regression, neural net, decision tree/forest, or support vector machine, can be trained, and then used.

[0344] As the window of interest moves, the features may be extracted and these newly-extracted features will return either a stroke type or detected turn via a machine learning system.

[0345] The stroke detector algorithm may run in parallel independent of stroke type and turn detection. Temporal peaks of raw or pre-filtered sensor signals may be detected and chosen by heuristic rules.

[0346] At the summarizing stage (the stage where metrics regarding the swim may be determined, displayed, and/or stored) of the algorithm, post-processing may be applied to the sequence of stroke type and turn detections. If a turn is confirmed with certain confidence, the swimming metric data from the previous turn may be summarized along with stroke counts detected. If no turn is confirmed, the moving average window may proceed. Until the user stops swimming, the algorithm may continue to update swimming metrics regarding the exercise of the user, including, but not limited to, a total number of turns, total number of laps, total number of strokes, average strokes per lap, number of strokes in the last lap, the change in number of strokes per lap, etc.

Hybrid Approach (See FIGS. 15C and 15D)

[0347] In a hybrid approach, the stroke type and stroke count detection may be run in parallel, followed by turn detection.

[0348] Stroke-type detection may return a stroke type via machine learned coefficients. A first moving window may take segments of sensor signals. Then features, either entire features or a subset of the moving window features listed in herein, may be extracted. The machine learning coefficients, trained off-line, may then be applied to the features to determine which stroke-type generated the given segments of sensor signals.

[0349] Along with stroke type detection, stroke count detection may be run simultaneously.

[0350] Once the stroke type and counts are detected, turn detection may be performed with either the entire feature or a subset of the features listed.

[0351] If a turn is detected, completion of a lap may be recorded in the swimming summary metrics of the user. A post process may be applied to detected stroke types to determine the most prominent stroke type for the completed lap. Then the algorithm may move to the stroke-type and count detection stages unless the user stops swimming. If no

turn is detected, the algorithm may continue updating stroke types and counts of the current lap until a turn is detected.

Blood Glucose Level and Heart Rate

[0352] Biometric monitoring devices that continuously measure biometric signals may provide meaningful information on preconditions of, progress towards, and recoveries from diseases. Such biometric monitoring devices may have sensors and run algorithms accordingly to measure and calculate biometric signals such as heart rate, heart rate variability, steps taken, calories burned, distance traveled, weight and body fat, activity intensity, activity duration and frequency, etc. In addition to the measured biometric signals, food intake logs provided by users may be used.

[0353] In one embodiment, a biometric monitoring device may observe heart rate and its changes over time, especially before and after a food intake event or events. It is known that heart rate is affected by blood sugar level, whereas it is well known that high blood sugar level is a pre-diabetic condition. Thus, mathematical models that describe the relation between time elapsed (after food intake) and blood sugar level may be found via statistical regression, where data are collected from normal, pre-diabetic, and diabetic individuals to provide respective mathematical models. With the mathematical models, one may predict whether an individual with specific heart rate patterns is healthy, pre-diabetic, or diabetic.

[0354] Knowing that many heart failures are associated with pre-diabetic or diabetic conditions, it is possible to further inform users of biometric monitoring devices with possible heart failures, e.g., coronary heart disease, cerebrovascular disease and peripheral vascular disease etc., of such risks based on their biometric data.

[0355] Users' activity intensity, type, duration, and frequency may also be taken into account, when developing the mathematical models, as an argument that controls "probability" of the disease onset, using recommended exercise guidelines such as guidelines provided by American Heart Association (<http://www.heart.org/>). Many guidelines on nutrition and weight management are also available in academia and to the general public to prevent cardiovascular and diabetic disease. Such guidelines may be incorporated into the mathematical models with the user data accumulated over time, such as ingredients of the food that the users consumed, and weight and body fat trends.

[0356] If users have set their family members as their friends on a social network site, which stores and displays biometric data, the likelihood of the family members getting a disease may also be analyzed and the users informed of the results.

[0357] In addition to informing users regarding a potential development of disease, recommended life-style including exercise regime and recipes with healthier ingredients and methods of preparation may be provided to the users.

Unification of Grocery Shopping, Cooking, and Food Logging

Grocery Organizing and Recipe Recognition System

[0358] Receipts from grocery shopping may contain copious information, especially regarding an individual's eating habits. A novel system that combines information from grocery store receipts with an individual's biometric data, as

collected by a biometric monitoring device, for example, is presented here. The system may collect and analyze data (information) regarding an individual, and may then recommend options that may change the individual's life-style so as to improve their health. The implementation of this system may involve cloud computing, hardware platform development for sensing and interface, and mobile/website site development.

[0359] In one embodiment, when a user checks out at a grocery store, the list of groceries (as obtained from the receipt or, for example, from an email receipt or invoice) may be transmitted automatically to a remote database (e.g., a cloud server), that may also store the user's biometric data. When the user gets home and organizes items in their refrigerator and/or pantry, an app on their smart phone/watch may recommend which items in the pantry or refrigerator to throw away based on historical data on food items (e.g., if food items are expired or likely to have gone bad). Alerts indicating when food has expired or that it should be consumed in the near future to avoid spoilage may be automatically sent to the user independently of such activity. For example, these alerts may be sent out to the user whenever a certain threshold has been met (e.g., in two days the milk will expire). The alerts may also be sent to the user through means other than through a smart phone/watch. For example, the alerts may be presented to the user through a web interface, through email, through an alert on a laptop computer, on a tablet computer, desktop computer, or any other electronic device which is in direct or indirect communication with the computer which maintains and/or analyzes the database of food

[0360] Using the updated list of food items, and based on the user's historical food consumption data, the app may recommend recipes to the user. In one embodiment, preference may be given to recipes that use the items what should be eaten first (e.g., before they expire, go bad, or become less fresh faster than other ingredients). To recommend the optimal recipe that is nutritionally balanced, correctly portioned, and tailored to the user's activity, the app may also analyze the user's activity data as well. For example, if the user lifted weights in the morning, high-protein meals may be recommended. In another example, if the user was not very active, the size of the recipe may be decreased to lower the number of calories that the final meal contains.

[0361] Note that these strategies may be applied to multiple users that either share the same food and/or meals. For example, a combined food database may be created for a household so that if one member of the house got eggs and another member of the house got milk from the grocery store that both eggs and milk would be represented in the food database. Similarly, the nutritional preferences (e.g., vegetarian, allergic to certain foods, etc.), activity, basal metabolic rate, and total calorie burn may be used to form a recommendation on what food/recipe to prepare and/or purchase.

[0362] Biometric signals including, but not limited to, heart rate and heart rate variability may provide indications of pre-conditions of diseases. This information may be used to recommend that the user purchase, consume, and/or prepare particular foods so as to reduce their risk of the disease(s) for which they have the pre-conditions. For example, if a user has a precondition for cardiac problems, it may be recommended that they purchase more vegetables,

consume less fatty foods, and prepare food in methods which require less oil (e.g., not deep frying).

Control "Smart Appliance"

[0363] In another embodiment, various appliances may all be Wi-Fi enabled, and may communicate with servers. Since the app (which may be connected to the appliances via, for example, the cloud or the Internet) may know which food items the refrigerator contains, the app may communicate with the refrigerator to lower or raise the temperature of the refrigerator depending on the food items. For example, if many of the food items are more sensitive to cold, such as vegetables, the refrigerator may be instructed to raise the temperature. The app may also directly communicate with the refrigerator as well via Bluetooth, BTLE, or NFC.

Food Logging

[0364] The app may also provide items to log in as the user's food based on a grocery shopping list (which may, for example, be a list maintained within the app) and food recipes that the app recommended. In case of precooked meals (e.g., frozen dinner) or produce that does not require any further processing before being eaten, the user may simply input their serving size (or in the case that the user eats the whole meal, the user may not need to enter a serving size), and then the food logging will be completed. Since the grocery list or receipt provides the exact brand and maker of certain foods, more accurate nutritional information may be logged into the user's account.

[0365] When a user logs a food item that is cooked by following a recipe suggested by the app, the app may calculate nutritional information from the ingredients and cooking procedure. This may provide more accurate estimate of calorie intake than a simple categorization of the end product/meal, since many recipes exist to prepare a particular type of food, e.g., meatballs for pasta may be made with beef, turkey, pork, etc., and may include varying degrees of carbohydrates.

Sport Metric Acquisition Using a Sensor Device

[0366] In some embodiments, a sensor may be mounted on a racket, e.g., tennis racket, to help to measure the different strokes of the player. This may be applicable to most, if not all, racket sports including, but not limited to, tennis, racquetball, squash, table tennis, badminton, lacrosse, etc., as well as sports played with a bat like baseball, softball, cricket, etc. Similar techniques may also be used to measure different aspects of golf. Such a device can be mounted on the base of the racket, on the handle or on the shock absorber typically mounted on the strings. This device may have various sensors like an accelerometer, gyroscope, magnetometer, strain sensor, and/or microphone. The data from these sensors may either be stored locally or transmitted wirelessly to a host system on a smartphone or other wireless receiver.

[0367] In some embodiments of a biometric monitoring device, a wrist mounted biometric monitoring device including an accelerometer, gyroscope, magnetometer, microphone, etc. may perform similar analysis of the user's game or motions. This biometric monitoring device may take the form of a watch or other band worn on the user's wrist. Racket- or bat-mounted sensors that measure or detect the moment of impact between the bat or racket and the ball and

wirelessly transmit such data to the wrist-mounted biometric monitoring device may be used to improve accuracy of such algorithms by accurately measuring the time of impact with the ball.

[0368] Both wrist and racket-/bat-mounted devices may help measure different aspects of the user's game including, but not limited to, stroke-type (forehand, backhand, serve, slice, etc.), number of forehands, number of backhands, ball spin direction, topspin, service percentage, angular velocity of racket head, backswing, shot power, shot consistency, etc. The microphone or the strain sensor may be used in addition to the accelerometer to identify the moment at which the ball impacts the racket/bat. In cricket and baseball, such a device may measure the backswing, the angular velocity of the bat at the time of impact, the number of shots on the off-side vs. leg-side (cricket). It may also measure the number of swings and misses and the number of defensive vs. offensive strokes. Such a device may also have a wireless transmitter to transmit such statistics in real time to a scoreboard or to individual devices held by spectators.

[0369] The wrist- or racket-mounted device may have a small number of buttons (e.g., two) that may be used by the player to indicate when a volley is won or when an unforced error occurs. This will allow the algorithm to calculate the fraction of winners and unforced errors that are forehands vs. backhands. The algorithm may also keep track of the number of aces vs. double-faults in tennis. If both players use such a system, the system may also automatically keep track of the score.

Bicycle Handlebar Based ECG

[0370] In some embodiments of biometric monitoring devices, a user's heart rate may be monitored using an electrode in contact with the left hand and an electrode in contact with the right hand (an ECG heart rate measurement). As riding a bicycle requires the user to make hand contact with either side of the handlebars, this particular activity is well suited to tracking user heart rate using ECG techniques. By embedding electrodes in the handlebars or handlebar grips or tape, the user's heart rate may be measured whenever the user is holding the handlebars. For bicycles that have grips (as opposed to using handlebar tape), electrodes may be incorporated into a special grip that may be used to replace the existing grips, e.g., the factory-installed grips, which are typically non-conductive. The left and right grips may be electrically connected to electronics that measure the ECG signal, using a wire, for example. In the case that the handlebars themselves are conductive, the handlebars may be used to electrically connect one of the grips to the electronics that measure the ECG signal. The electronics that measure the ECG signal may be incorporated into one or both of the grips. Alternatively, the electronics that measure the ECG signal may be located in a separate housing. In one embodiment, this separate housing may be mounted on the bicycle handlebar or stem. It may have functions and sensors that typical bicycle computers have (e.g., speed sensor, cadence sensor, GPS sensor). It may also have atypical sensors such as a wind speed sensor, GSR sensor(s), and accelerometer sensor (potentially also incorporated into the handlebars). This embodiment may use techniques described in this disclosure to calculate activity metrics including, but not limited to, calorie burn, and transmit these metrics to secondary and tertiary device(s) (e.g. smartphones and servers).

[0371] Electrodes for the ECG may be incorporated into parts of the bike or accessories other than into grip tape and handlebar grips such as into gloves, brake hoods, brake levers, or the handlebars themselves. These electrodes or additional electrodes may be used to measure GSR, body fat and hydration in addition to, or in alternative to, heart rate. In one example, the user's heart rate may be measured using conductive threads (used as ECG electrodes) sewn into grip tape installed on the handlebar. The grip tape electrodes may be connected to a central bike computer unit that contains electronics to measure GSR, hydration, and/or heart rate. The biometric monitoring device may display this information on a display. If the user's hydration or heart rate exceeds a certain threshold, the user may be alerted to drink more, drink less, increase intensity or decrease intensity. In the case that the bike computer measures only one or two of GSR, hydration or heart rate, algorithms may be used to estimate metrics which that cannot be measured directly. For example, if the biometric monitoring device can only measure heart rate and duration of exercise, a combination of heart rate and duration of exercise may be used to estimate hydration and alert the user when they should drink. Similarly, heart rate and exercise duration may be used to alert the user when they should eat or drink something other than water (e.g., a sports drink).

Indirect Metric Estimation

[0372] Bicycle computers typically measure a variety of metrics including, but not limited to, speed, cadence, power, and wind speed. In the case that the portable monitoring device does not measure these metrics or is not in communication with devices which may be able to supply these metrics, these and other metrics may be inferred using the sensors that the portable biometric monitoring device does have. In one embodiment, the portable biometric monitoring device may measure heart rate. It may use this measurement to infer/estimate the amount of power that the user is outputting. Other metrics such as the user's age, height, and weight may help inform the power measurement. Additional sensor data such as GPS-measured speed, altitude gain/descent, bicycle attitude (so as the measure the incline or decline of a slope), and accelerometer signals may be used to further inform the power estimate. In one embodiment, an approximately linear relationship between heart rate and power output may be used to calculate the user's power output.

[0373] In one embodiment, a calibration phase may occur where the user takes data from the portable biometric monitoring device and a secondary device that may be used during calibration as a baseline but not be used at a later time (e.g., a power meter). This may allow a relationship between sensor data measured by the portable monitoring device and sensor data measured by the secondary device data to be determined. This relationship may then be used when the secondary device is not present to calculate estimated values of data that is explicitly provided by the secondary device but not by the biometric monitoring device.

Activity Based Automatic Scheduling

[0374] In one embodiment, the day's travel requirements (to work, from work, between meetings) may be scheduled for the user based on the information in their calendar (or emails or text messages etc.), with the aim of meeting daily

activity goal(s) or long term activity goal(s). The user's historical data may be used to help plan both meeting the goal(s) and also the transit time required. This feature may be combined with friends or colleagues. The scheduling may be done such that a user may meet a friend along the way as they walk to work, or meet a colleague on the way to a meeting (the user might need to set a rendezvous point, though). If there is real-time communication between biometric monitoring devices of the user and the user's friend, the user may be directed to walk a longer route if data from the friend's biometric monitoring device indicates that their friend is running late.

[0375] In another embodiment, walking/running/fitness routes may be suggested to the user based (in whole or in part) on their proximity to the user. The data for such recommendations could also or additionally be based on GPS info from other users. If there is real-time communication, the user may be directed to a busy route or a quiet route as preferred. Knowing heart rate and basic fitness information about other users may allow the system to suggest a route to match a user's fitness level and the desired exercise/exertion level. Again this information may be used for planning/guiding a user to longer term activity/fitness goals.

Location/Context Sensing and Applications

[0376] Through one or more methods, embodiments of the biometric monitoring devices disclosed herein may have sensors that can determine or estimate the location and or context (e.g. in a bus, at home, in a car) of the biometric monitoring device. Purpose-built location sensors such as GPS, GLONASS, or other GNSS (Global Navigation Satellite System) sensors may be used. Alternatively, location may be inferred, estimated or guessed using less precise sensors. In some embodiments in which it is difficult to know the user's location, user input may aid in the determination of their location and or context. For example, if sensor data makes it difficult to determine if a user was in a car or a bus, the biometric monitoring device or a portable communication device in communication with the biometric monitoring device or a cloud server which is in communication with the biometric monitoring device may present a query to the user asking them if they took the bus today or took a car. Similar queries may occur for locations other than vehicular contexts. For example, if sensor data indicate that the user completed a vigorous workout, but there is no location data that indicates that the user went to a gym, the user may be asked if they went to the gym today.

Vehicular Transportation Detection

[0377] In some embodiments, sensors of the biometric monitoring device and/or a portable electronic device in communication with the biometric monitoring device and/or a server which communicates with the biometric monitoring device may be used to determine what type of vehicle (if any) the user is, or was, in. Note that in the embodiments below, a sensor in one or more biometric monitoring devices and/or portable electronic devices may be used to sense the relevant signal. Also note that while specific network protocols such as WiFi or Bluetooth may be used in the following descriptions, one or more alternative protocols such as RFID, NFC, or cellular telephony may also be used.

[0378] In one embodiment, the detection of a Bluetooth device associated with a vehicle may be used to infer that the user is in a vehicle. For example, a user may have a car that has a Bluetooth multimedia system. When the user gets close enough to their car for a long enough period of time, the sensor device may recognize the Bluetooth identification of the multimedia system and assume that the user is in the car. Data from other sensors may be used to corroborate the assumption that the user is in the vehicle. Examples of data or signals from other sensors that may be used to confirm that the user is in a car include a GPS speed measurement that is higher than 30 mph and accelerometer signals that are characteristic of being in a car. Information intrinsic to the Bluetooth ID may be used to determine that it is a Wi-Fi router of a vehicle or type of vehicle. For example, the Bluetooth ID of a router in a car may be "Audi In-Car Multimedia." The keyword "Audi" or "Car" may be used to guess that the router is associated with a vehicle type of "car." Alternatively, a database of Bluetooth ID's and their associated vehicles may be used.

[0379] In one embodiment, a database of Bluetooth ID's and their associated vehicles may be created or updated by the user of a biometric monitoring device or through portable communication device data. This may be done with and/or without the aid of user input. In one embodiment if a biometric monitoring device can determine whether or not it is in a vehicle, vehicle type, or specific vehicle without the use of Bluetooth ID, and it encounters a Bluetooth ID that moves with the vehicle, it may send the Bluetooth ID and information regarding the vehicle to a central database to be catalogued as a Bluetooth ID that corresponds with a vehicle. Alternatively, if a user inputs information about the vehicle they are in or were in at a previous point in time and there is a Bluetooth ID that was encountered during or close to the time that the user indicated they were in the vehicle, the Bluetooth ID and vehicle information may be sent to a central database and associated with one another.

[0380] In another embodiment, the detection of a Wi-Fi device associated with a vehicle may be used to infer that the user is in that vehicle or type of vehicle. Some trains, buses, airplanes, cars, and other vehicles have Wi-Fi routers in them. The SSID of the router may be detected and used to infer or aid an inference that a user is in a specific vehicle or type of vehicle.

[0381] In one embodiment, a database of SSID's and their associated vehicles may be created or updated with the user of a biometric monitoring device or through portable communication device data. This may be done with and/or without the aid of user input. In one embodiment, if a biometric monitoring device can determine whether or not it is in a vehicle, vehicle type, or specific vehicle without the use of an SSID, and it encounters an SSID that moves with the vehicle, the biometric monitoring device may send the SSID and information regarding the vehicle to a central database to be catalogued as an SSID that corresponds with a vehicle. Alternatively, if a user inputs information about the vehicle they are in or were in at a previous point in time and there is an SSID that was encountered during or close to the time that the user indicated they were in the vehicle, the SSID and vehicle information may be sent to a central database and associated with one another.

[0382] In another embodiment of a biometric monitoring device, location sensors may be used to determine the track of a user. This track may then be compared to a database of

routes for different modes of transit. Modes of transit may include, but are not limited to walking, running, biking, driving, taking a bus, taking a train, taking a tram, taking the subway, and/or motorcycling. If the user's track corresponds well with a route of a specific mode of transit, it may be assumed that the user used that mode of transit for the period of time that it took them to traverse the route. Note that the speed with which the route or sections of the route were completed may improve the guess of the mode of transit. For example, a bus and a car may both be able to take the same route, but the additional stopping of the bus at bus stops may allow the device to determine that the user was taking a bus rather than a car. Similarly, the discrimination between biking and driving a route may be aided by the typical difference of speed between the two. This difference in speed may also depend on the time of day. For example, some routes may be slower by car during rush hour.

[0383] In another embodiment, a biometric monitoring device may be able to detect that the user is in or near a vehicle based on measurements of the magnetic field of vehicle. In some embodiments, the magnetic field signature of a location typically associated with the vehicle (e.g., train station, subway station, bus stop, car garage) may also be used to infer that the user is currently in, will be, or has been in a vehicle. The magnetic field signature may be time invariant or time varying.

[0384] If it is determined that the user was indeed in a vehicle for a period of time, other metrics about the user may be modified to reflect such a status. In the case that the biometric monitoring device and/or portable electronic device can measure activity metrics such as steps taken, distance walked or run, altitude climbed, and/or calories burned, these metrics may be modified based on information about vehicular travel. If any steps taken or altitude climbed were incorrectly logged during the time that the user is in a vehicle, they may be removed from the log of metrics about the user. Metrics derived from the incorrectly logged steps taken or altitude climbed such as distance traveled and calories burned may also be removed from the log of metrics about the user. In the case that it can be determined in real-time or near real-time whether or not the user is in a vehicle, the sensors detecting metrics which should not be measured while in a vehicle (e.g. steps taken, stairs climbed) may be turned off or algorithms which are used to measure these metrics may be turned off to prevent incorrectly logged metrics (as well to save power). Note that metrics regarding vehicle use such as type of vehicle taken, when it was taken, which route was taken, and how long the trip took may be recorded and used later to present the user with this data and/or to correct other activity and physiological metrics about the user.

Location Sensing Using Bluetooth

[0385] Methods similar to those described above may also be used by a biometric monitoring device to determine when the user comes into proximity of static locations. In one embodiment, Bluetooth ID's from computers (e.g., tablet computers) at restaurants or stores may be used to determine the user's location. In another embodiment, semi-fixed Bluetooth ID's from portable communication devices (e.g., smartphones) may be used to determine a user's location. In the case of semi-fixed Bluetooth ID sources, multiple Bluetooth ID's may be needed to reach an acceptable level of confidence of the location of the user. For example, a

database of Bluetooth ID's of the coworkers of a user may be created. If the user is within range of several of these Bluetooth ID's during typical working hours, it may be assumed that the user is at work. The detection of other Bluetooth ID's may also be used to record when two users meet up. For example, it may be determined that a user went for a run with another user by analyzing pedometer data and Bluetooth ID's. Similar such concepts are discussed in further detail in U.S. Provisional Patent Application No. 61/948,468, filed Mar. 5, 2014, and previously incorporated by reference with regard to such concepts.

Uncertainty Metric for GPS Based on Location

[0386] When fusing sensor signals with GPS signal to estimate informative biometrics, such as steps, live pace, speed, or trajectory of trips, quality of the GPS signal is often very informative. However, GPS signal quality is known to be time-varying, and one of the factors that affects the signal quality is environmental surroundings.

[0387] Location information may be used to estimate GPS signal quality. A server may store a map of area types, where the area types are pre-determined by number and kind of objects that deteriorate GPS signals. The types may, for example, be: large building area, small building area, open area, side-by-water area, and forested area. These area types are then queried when GPS sensor gets turned on with its very first few location estimates, which are expected to be rough and inaccurate. With the rough GPS estimates of the location, possible types of areas may be returned, and these area types may then be taken into account in the calculation of the GPS signal quality and reliability.

[0388] For example, if a user is in or near an urban canyon (an area surround by tall buildings) such as downtown San Francisco, a low certainty may be associated with any GNSS location measurements. This certainty may be used later by algorithms that attempt to determine the user's track, speed, and/or elevation based on, at least in part, GPS data.

[0389] In one embodiment, a database of location and GPS signal quality may be created automatically using data from one or more GNSS sensors. This may be automatically performed by comparing the GNSS tracks with a map of streets and seeing when the GNSS sensors show characteristics of a user travelling along a street (e.g., having a speed of 10 mph or higher), but their track is not located on a road. The database of GPS certainty based on approximate location may also be inferred from maps showing where there are tall buildings, canyons, or dense forests.

Location Sensing Using Vehicular GNSS and/or Dead Reckoning

[0390] Many vehicles have integrated GNSS navigation systems. Users of vehicles that don't have integrated GNSS navigation systems often buy a GNSS navigation system for their car that is typically mounted non-permanently in the driver's field of view. In one embodiment, a portable biometric monitoring device may be able to communicate with the vehicle's GNSS system. In the case where the portable biometric monitoring device is also used to track location, it may receive location information from the vehicle GNSS. This may enable the biometric monitoring device to turn off its own GNSS sensor (in the case that it has one), therefore reducing its power consumption.

[0391] In addition to GNSS location detection, a vehicle may be able to transmit data about its steering wheel orientation and/or its orientation with respect to the earth's

magnetic field in addition to its speed as measured using the tire size and tire rotational velocity. This information may be used to perform dead-reckoning to determine a track and/or location in the case that the vehicle does not have a GNSS system or the vehicle's GNSS system cannot get a reliable location measurement. Dead-reckoning location information may supplement GNSS sensor data from the biometric monitoring device. For example, the biometric monitoring device may reduce the frequency with which it samples GNSS data and fill in the gap between GNSS location data with locations determined through dead reckoning.

Step Counter Data Fusion with Satellite-Based Location Determination

[0392] In some implementations of a biometric monitoring device, data from various different sensors may be fused together to provide new insights as to activities of the wearer of the biometric monitoring device. For example, data from an altimeter in the biometric monitoring device may be combined with step count data obtained by performing peak detection analysis on accelerometer data from an accelerometer of the biometric monitoring device to determine when the wearer of the biometric monitoring device is, for example, climbing stairs or walking uphill (as opposed to riding an elevator or an escalator or walking across flat ground).

[0393] In another example of sensor data fusion, data from a step counter such as that discussed above may be combined with distance measurements derived from GPS data to provide a refined estimate of total distance traveled within a given window. For example, GPS-based distance or speed data may be combined with step-counter-based distance or speed (using steps taken multiplied by stride length, for example) using a Kalman filter in order to obtain a refined distance estimate that may be more accurate than either the GPS-based distance or speed measurement or the step-counter-based distance or speed measurement alone. In another implementation, a GPS-based distance measurement may be filtered using a smoothing constant that is a function of the step rate as measured by, for example, an accelerometer. Such implementations are discussed further in U.S. Provisional Patent Application No. 61/973,614, filed Apr. 1, 2014, which was previously incorporated herein by reference in the "Cross-Reference to Related Applications" section and which is again hereby incorporated by reference with respect to content directed at distance or speed estimation refinement using data from satellite-based location systems and step count sensors.

Biometric and Environmental/Exercise Performance Correlation

[0394] Some embodiments of portable monitoring devices described herein may detect a variety of data including biometric data, environmental data, and activity data. All of this data may be analyzed or presented to a user to facilitate analysis of or correlation between two or more types of data. In one embodiment, a user's heart rate may be correlated to car speed, biking speed, running speed, swimming speed or walking speed. For example, the user may be presented with a graph that plots biking speed on the X axis and heart rate on the Y axis. In another example, a user's heart rate may be correlated to music that they were listening to. The biometric monitoring device may receive data regarding what music the user was listening to through a wireless connection (e.g., Bluetooth) to a car radio. In another embodiment, the

biometric monitoring device may also function as a music player itself, and therefore can record which song was played when.

Weight Lifting Aid

[0395] Without the aid of a personal trainer or partner, it may be difficult to do a weight-lifting routine properly. A portable biometric monitoring device may aid a user in completing a weight lifting routine by communicating to the user how long they should hold up each weight, how quickly they should lift it, how quickly they should lower it, and how many repetitions of each lift to perform. The biometric monitoring device may measure the user's muscle contractions using one or more EMG sensors or strain sensors. The user's muscle contractions may also be inferred by measuring vibrations of one or more body parts (for example using an accelerometer), sweat (e.g., using a GSR sensor), rotation of one or multiple body parts (e.g., using a gyroscope), and/or a temperature sensor on one or more body parts. Alternatively, a sensor may be placed on the weight lifting apparatus itself to determine when the user is lifting, with how much speed they are lifting or lowering, how long they are lifting for, and how many repetitions of lifts they have performed.

[0396] In one embodiment, if the biometric monitoring device or weight lifting apparatus detects that the user is approaching their failure limit (when the user can no longer support the weight), the weight lifting apparatus may automatically lift the weight or prevent the weight from being lowered. In another embodiment, a robot in communication with the biometric monitoring device or weight lifting apparatus may automatically lift the weight or prevent the weight from being lowered. This may allow the user to push themselves to their limit without needing a partner/spotter (to lift the weight in case of failure) and without risking injury from dropping the weight.

Glucose Level Monitoring Aid

[0397] In some embodiments, a portable biometric monitoring device may be configured to aid users who need to monitor their glucose levels (e.g., diabetics). In one embodiment, the portable biometric monitoring device may indirectly infer a user's glucose level or a metric related to the user's glucose level. Sensors other than those typically used in monitoring glucose monitoring (using continuous or discrete finger-prick types of sensors) may be used in addition to, as an alternative to, or as an aid to the typical glucose monitoring methods. For example, an biometric monitoring device may alert the user that they should check their blood glucose level based on data measured from sensors on the biometric monitoring device. If the user has performed a certain type of activity for a certain amount of time, their blood glucose level is likely to have decreased, and therefore, the biometric monitoring device may display an alert, create an auditory alert, or vibrate to alert the user that their blood glucose may be low and that they should check it using a typical glucose measurement device (e.g., a finger-prick type glucose monitor). The biometric monitoring device may allow the user to input the glucose level that is measured from the glucose meter. Alternatively, the glucose measurement may be automatically transmitted to the biometric monitoring device and/or a third device in direct or indirect communication with the biometric monitoring device.

toring device (e.g., a smart phone or server). This glucose measurement may be used to inform the algorithm used by the biometric monitoring device to determine when the next glucose level alert should be delivered to the user. The user may also be able to enter what food they ate, are eating, or are planning to eat into the biometric monitoring device or a device in direct or indirect communication with the biometric monitoring device. This information may also be used to determine when the user should be alerted to check their blood glucose level. Other metrics and sensor data described herein (e.g., heart rate data) may also be used alone or in combination to determine when the user should be alerted to check their blood glucose.

[0398] In addition to being alerted when glucose levels should be checked, a biometric monitoring device may also display an estimate of the current glucose level. In another embodiment, data from the biometric monitoring device may be used by a secondary device (e.g., a smart phone or server) to estimate the user's glucose level and/or present this data to the user (e.g., by displaying it on a smartphone, on a webpage, and/or by communicating the data through audio).

[0399] A biometric monitoring device may also be used to correlate exercise, diet, and other factors to blood glucose level. This may aid users in seeing the positive or negative effects of these factors on their blood glucose levels. The blood glucose levels with which the activity is correlated to may be measured by the user using a different device (e.g., a finger-prick monitor or continuous blood glucose monitor), by the biometric monitoring device itself, and/or by inferring the blood glucose level or a metric related to the glucose level using other sensors. In some embodiments of biometric monitoring devices, a user may wear a continuous glucose monitoring device and a biometric monitoring device. These two devices may automatically upload data regarding activities and glucose levels to a third computing device (e.g., a server). The server may then analyze the data and/or present the data to the user so that they become more aware of the relationship between their activities and glucose levels. The server may also receive input on the user's diet (e.g., the user may enter what foods they eat) and correlate the diet with glucose levels. By helping the user understand how diet, exercise, and other factors (e.g., stress) affects their blood glucose levels, biometric monitoring devices may aid users who have diabetes.

UV Exposure Detection

[0400] In one embodiment, the biometric monitoring device may have the ability to monitor an individual's exposure to UV radiation. UVA and UVB may be measured with one or multiple sensors. For example, a photodiode having a bandpass filter which passes only UVA may detect UVA exposure and a photodiode having a bandpass filter which passes only UVB may detect UVB exposure. The user's skin pigmentation may also be measured using a camera or reflectometer (light emitter and light detector which determines the efficiency with which light is reflected off the skin). Using UVA, UVB, and skin pigmentation data, the biometric monitoring device may provide a user with information regarding the amount of UV exposure they have been subjected to. The biometric monitoring device may also provide estimates or alarms regarding over exposure to UV, potential for sunburn, and potential for increasing their risk of skin cancer.

Screen Power Saving Using User Presence Sensors

[0401] The portable biometric monitoring device may have one or more displays to present information to the user. In one embodiment sensors on the biometric monitoring device may determine the user is using the biometric monitoring device and/or wearing the biometric monitoring device to determine the state of the display. For example, a biometric monitoring device having a PPG sensor may use the PPG sensor as a proximity sensor to determine when the user is wearing the biometric monitoring device. If the user is wearing the biometric monitoring device, the state of the screen (e.g. a color LCD screen) may be changed to "on" or "standby" from its typical state of being off.

Power Conservation with Respect to Satellite-Based Location Determination Systems

[0402] In some implementations, certain systems included in a biometric monitoring device may consume relatively large amounts of power compared to other systems in the biometric monitoring device. Due to the small space constraints of many biometric monitoring devices, this may seriously affect overall battery charge life for the biometric monitoring device. For example, in some biometric monitoring devices, a satellite-based location determination system may be included. Each time the satellite-based location determination system is used to obtain a position fix using data from the GPS satellite constellation, it uses power drawn from the biometric monitoring device battery. The biometric monitoring device may be configured to alter the frequency with which the satellite-based location determination system obtains a location fix based on data from one or more sensors of the biometric monitoring device. This adaptive location fix frequency functionality may help conserve power while still allowing the satellite-based location determination system to provide location fixes at useful intervals (when appropriate).

[0403] For example, if a biometric monitoring device has an ambient light sensor, data from the ambient light sensor may be used to determine whether the lighting conditions indicate that the biometric monitoring device is likely indoors as opposed to outdoors. If indoors, the biometric monitoring device may cause the location fix frequency to be set to a level that is lower than the location fix frequency that may be used when the lighting conditions appear to indicate that the biometric monitoring device is outdoors. This has the effect of decreasing the number of location fixes that are attempted when the biometric monitoring device is indoors and thus less likely to obtain a good location fix using a satellite-based location determination system.

[0404] In another example, if motion sensors of the biometric monitoring device indicate that the wearer of the biometric monitoring device is substantially stationary, e.g., sleeping or generally not moving more than a few feet every minute, the location fix frequency of the satellite-based location determination system may be set to a lower level than if the motion sensors indicate that the wearer of the biometric monitoring device is in motion, e.g., walking or running from one location to another, e.g., moving more than a few feet.

[0405] In yet another example, the biometric monitoring device may be configured to determine if the biometric monitoring device is actually being worn by a person—if not, the biometric monitoring device may set the location fix frequency to a lower level than if the biometric monitoring device is actually being worn. Such determinations regard-

ing whether or not the biometric monitoring device is being worn may be made, for example, when motion data collected from motion sensors of the biometric monitoring device indicate that the biometric monitoring device is substantially immobile, e.g., not even demonstrating small movements experienced by biometric monitoring devices when the wearer is sleeping or sedentary, or when data, for example, from a heart rate sensor indicates that no heart rate is detected. For optical heart rate sensors, if there is little or no change in the amount of light detected by the light detection sensor when the light source is turned on and off, this may be indicative of the fact that the heart rate sensor is not pressed against a person's skin and that, by inference, the biometric monitoring device is not being worn. Such adaptive satellite-based location determination system fix frequency concepts are discussed in more detail in U.S. Provisional Patent Application No. 61/955,045, filed Mar. 18, 2014, which was previously incorporated herein by reference in the "Cross-Reference to Related Applications" section and which is again hereby incorporated by reference with respect to content directed at power conservation in the context of satellite-based location determination systems.

[0406] It is to be understood that biometric monitoring devices, in addition to including the features discussed below in more detail, may also include one or more features or functionalities discussed above or discussed in the various applications incorporated by reference in the above discussion. Such implementations are to be understood as being within the scope of this disclosure.

[0407] While the above discussion has focused on a variety of different systems and functionality that may be included in a biometric monitoring device, the discussion that follows below focuses on some particular embodiments (some of which may also be discussed above) in further detail.

[0408] As noted above, personal health or biometric monitoring devices may include a wireless communications capability allowing them to communicate with nearby electronic devices such as smartphones, tablets, computers, and other, similarly-equipped biometric monitoring devices. Such wireless communications functionality may be used to allow the biometric monitoring device to send or receive data between the biometric monitoring device and a remote device, e.g., a server, a laptop, a smartphone, etc. This may allow the data collected by the biometric monitoring device to be archived for long-term storage, post-processed, or viewed via an interface other than the interface of the biometric monitoring device (in some cases, the biometric monitoring device may not have a visual interface that is capable of displaying meaningful data, and the data collected by the biometric monitoring device must be sent to an external device in order to view it). The wireless communications functionality may also be used to allow data, software updates, etc. to be transmitted from a remote device to the biometric monitoring device.

[0409] One wireless communications technology that may be used to provide wireless communications capability in biometric monitoring devices is Bluetooth. For example, the Fitbit One, Flex, Zip, and Force all include Bluetooth low-energy communications capability.

[0410] The Bluetooth wireless communications protocol has undergone several revisions during its lifetime. The most recent version is titled Bluetooth Smart (or version 4.0). The Bluetooth 4.0 standard includes both "Classic Bluetooth"

and "Bluetooth Low Energy" (BLE) protocols. The Classic Bluetooth protocol, which is also referred to herein as "base rate/enhanced data rate" or "BR/EDR," is capable of higher data throughput, e.g., 1 to 3 Mbps symbol rate and 0.7 to 2.1 Mbps application throughput, than BLE, which supports up to 1 Mbps symbol rate and 305 kbps application throughput. BLE, however, allows for power consumption levels that are between 1% and 50% of that required for Classic Bluetooth. BLE is intended to support very low power applications which are powered, for example, off of a coin or button cell.

[0411] BLE is typically implemented in two modes: single-mode and dual-mode. In single mode, only the BLE protocol stack is implemented, e.g., such as in the Nordic Semiconductor nRF8001 integrated circuit. The single-mode implementation is typically used in devices in which power conservation is a major design driver, e.g., remote sensors, proximity tags, and fitness monitoring products. In dual-mode implementations, the BLE protocol stack is integrated into an existing Classic Bluetooth controller, allowing the controller to support either Classic Bluetooth or BLE connections. The dual-mode implementation is typically used in devices in which power conservation, at least with respect to the amount of power drawn by the Bluetooth chipset, is not an overriding design driver and where the device that has the Bluetooth chipset may need to communicate both with devices that utilize Classic Bluetooth and with devices that utilize BLE. For example, a cell phone may need to communicate with a wireless headset using Classic Bluetooth and with a fitness monitoring device using BLE. By using a dual-mode implementation of BLE, communication with both types of devices via Bluetooth may be supported by a single chipset.

[0412] Conventional dual-mode implementations attempt to connect with a device using the highest data rate that is supported. Thus, if two dual-mode devices establish a Bluetooth connection, the Bluetooth connection will be a Classic Bluetooth connection. By contrast, if a dual-mode device and a single-mode device establish a Bluetooth connection, the connection will only be via BLE.

[0413] New implementations of utilizing BR/EDR and BLE Bluetooth connections are described below; these alternative implementations are not believed to be previously contemplated or implemented within the industry. These new implementations involve a device that has both Classic (BR/EDR) and BLE functionality. Such dual-mode functionality may be provided by either a dual-mode implementation as discussed above, e.g., a single chipset providing both BR/EDR and BLE protocol stacks, or by a more discrete implementation, e.g., a BR/EDR chipset and a separate BLE chipset.

[0414] According to various implementations described herein, a device having dual-mode functionality may utilize such dual-mode Bluetooth functionality in a more intelligent fashion than devices utilizing conventional dual-mode Bluetooth implementations. As used herein with respect to Bluetooth protocol selection, the apparatus in question may also be referred to as a "common device" (because it has both Bluetooth BR/EDR functionality and Bluetooth BLE functionality in a common structure); many of the examples herein are described in the context of an apparatus or common device that is a biometric monitoring device, although implementations of the Bluetooth protocol management concepts discussed herein may also be provided on other types of devices.

[0415] FIG. 17 depicts a simplified block schematic of a device with both Bluetooth base rate/enhanced data rate and Bluetooth low-energy capability. A device such as device 1700 may include a controller 1702 that includes at least one processor 1704 and a memory 1706. The at least one processor 1704 and the memory 1706 may be communicatively connected. The controller 1702 (or the at least one processor 1704) may be communicatively connected with a BR/EDR controller 1708 and a BLE controller 1710. While shown as separate blocks in FIG. 17, the BR/EDR controller 1708 and BLE controller 1710 may be provided, at least in part, using common hardware, e.g., the same Bluetooth controller may be used to provide both BR/EDR and BLE functionality. The controller 1702 (or the at least one processor 1704) may also be communicatively connected with one or more sensors, e.g., biometric sensors 1712. It is to be understood that other arrangements of the components represented in FIG. 17 may also be used to provide BR/EDR and BLE functionality in a common device, and that the techniques and systems for utilizing BR/EDR and BLE functionality discussed herein may also be implemented using such alternate architectures.

[0416] FIG. 18 depicts a flow diagram of one example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device. Technique 1800 begins in block 1802, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. An apparatus having both BR/EDR and BLE functionality may, in the context of the portions of this disclosure discussing Bluetooth communications, also be referred to as a “common device.” In block 1804, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 1802 and 1804 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0417] In some implementations, the BR/EDR connection and the BLE connection may utilize a common set of credentials for authentication purposes (this is true of the following implementations as well).

[0418] At some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. Prior to transmitting the data, a decision may be made in block 1806 as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. If the BR/EDR protocol is selected in block 1806, then the technique may proceed to block 1808 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 1806, then the technique may proceed to block 1810 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 1806 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 1806 may be repeated for the additional data. A variety of factors may influence the determination of whether to use the BR/EDR protocol or the

BLE protocol to transmit the data. These factors are explored in more detail further below.

[0419] FIG. 19 depicts a flow diagram of another example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device. Technique 1900 begins in block 1902, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 1904, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 1902 and 1904 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0420] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. Prior to transmitting the data, a decision may be made in block 1906 as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. If the BR/EDR protocol is selected in block 1906, then the technique may proceed to block 1908 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 1906, then the technique may proceed to block 1910 and the BR/EDR connection may be terminated or suspended by the apparatus such that the remote device may only communicate with the apparatus via the BLE protocol. Following block 1910, block 1912 may be performed, in which the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 1906 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 1906 may be repeated for the additional data. The BR/EDR protocol connection may be re-activated or re-established if a subsequent iteration of block 1906 determines that the BR/EDR protocol is to be used to transmit additional data. Alternatively, the BR/EDR protocol connection may be re-established after the data is transmitted via the BLE protocol in block 1912, regardless of whether or not a further decision has been made to actually transmit data via the BR/EDR protocol again.

[0421] The technique 1900 may be useful for allowing an apparatus to control which Bluetooth protocol is used to transmit data when such data transmission occurs between the apparatus and a remote device that may operate according to conventional norms, e.g., a remote device that always utilizes the BR/EDR protocol if available when communicating with another apparatus. By turning off the BR/EDR protocol connection, the apparatus may “force” the remote device to use the BLE protocol connection when it otherwise would not use the BLE protocol connection. It is to be understood that the reverse of this technique may also be utilized, if necessary, i.e., the BLE protocol connection may be disabled/suspended/turned off to force a remote device to utilize the BR/EDR protocol connection in place of the BLE protocol connection. However, since devices having both BR/EDR and BLE capabilities do not conventionally select BLE over BR/EDR when both are available, such imple-

mentations may be of little utility in the context of the current state of the art. Such implementations may, however, have future utility if combined BLE and BR/EDR capabilities evolve in such a direction.

[0422] It is to be understood that this technique of “forcing” the use of one Bluetooth protocol or the other may be used with any of the techniques discussed herein.

[0423] FIG. 20 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the data to be transmitted is application data. Technique 2000 begins in block 2002, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2004, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2002 and 2004 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0424] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2005, the data to be transmitted may be identified, e.g., the data may be identified as belonging to a particular class of data, such as data that is an application (executable files, program libraries, or other data that may be used to install an application, or update application code, on the apparatus). Prior to transmitting the data, a decision may be made in block 2006 as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2006 may be made based on whether the data is identified as an application or part of an application. If the data is identified as an application or as part of an application, then the BR/EDR protocol may be selected in block 2006. If the data is not identified as an application or part of an application, then the BLE protocol may be selected in block 2006 instead. It is to be understood that identification of the data as not being an application or part of an application does not necessarily mean that the BLE protocol will be selected in block 2006 in all implementations—other types of data may also cause the BR/EDR protocol to be selected over the BLE protocol. For example, if the data is identified as being streaming media, such as streaming video or audio, the BR/EDR protocol may be selected in block 2006 instead of the BLE protocol. This may ensure that there is no lag or stuttering in the media stream since the higher-throughput BR/EDR protocol may be used. The decision to use the BR/EDR protocol over the BLE protocol also may be triggered by the identification of data types other than those discussed above.

[0425] If the BR/EDR protocol is selected in block 2006, then the technique may proceed to block 2008 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2006, then the technique may proceed to block 2010 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2006 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether

to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2006 may be repeated for the additional data.

[0426] FIG. 21 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the data to be transmitted is data collected from one or more sensors of the common device.

[0427] Technique 2100 begins in block 2102, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2104, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2102 and 2104 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0428] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2105, the data to be transmitted may be identified. In this implementation, the data may be identified as being sensor data collected from one or more sensors of the apparatus. Prior to transmitting the data, a decision may be made in block 2106 as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2106 may be made based on whether the data is identified as being data collected from one or more sensors of the apparatus. If the data is identified as being data from the one or more sensors of the apparatus (or data based on such sensor data), then the BLE protocol may be selected in block 2106. If the data is not identified data from the one or more sensors of the apparatus, then the BR/EDR protocol may be selected in block 2106 instead. It is to be understood that identification of the data as not being data from the one or more sensors of the apparatus does not necessarily mean that the BR/EDR protocol will be selected in block 2106 in all implementations—other types of data may also cause the BLE protocol to be selected over the BR/EDR protocol. For example, if the data is identified as being a small data packet such as a text message or other non-streaming, small-size data chunk, the BLE protocol may be selected in block 2106 instead of the BR/EDR protocol. The decision to use the BLE protocol over the BR/EDR protocol also may be triggered by the identification of data types other than those discussed above.

[0429] If the BR/EDR protocol is selected in block 2106, then the technique may proceed to block 2108 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2106, then the technique may proceed to block 2110 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2106 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2106 may be repeated for the additional data.

[0430] FIG. 22 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate

or Bluetooth low-energy capability in a common device based on the battery charge level of the common device. Technique 2200 begins in block 2202, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2204, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2202 and 2204 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0431] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2206, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2206 may be made based on a battery charge level of the apparatus. For example, if the battery charge level is less than 20%, then the decision may be made in block 2206 to use the BLE protocol. If the battery charge level is greater than or equal to 20%, then the decision may be made in block 2206 to use the BR/EDR protocol. The battery charge level threshold that triggers this decision may be expressed in a number of different ways, e.g., in terms of raw power remaining, battery voltage levels, etc., and may alternatively be a “less than or equal to X” threshold for BLE protocol use. The level of X may generally be selected to be a value or values that correspond with a battery charge level that has been deemed sufficiently low that more aggressive power-saving techniques are warranted. Such battery charge levels may be as low as 10% or 5% of the overall capacity of the battery.

[0432] If the BR/EDR protocol is selected in block 2206, then the technique may proceed to block 2208 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2206, then the technique may proceed to block 2210 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2206 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2206 may be repeated for the additional data.

[0433] In some implementations, the determination in block 2206 may also determine if the apparatus is currently being charged and may, if so, cause the BR/EDR protocol to be used even if the battery charge level is less than the threshold that would normally cause the BLE protocol to be used.

[0434] FIG. 23 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether the device is stationary or in motion. Technique 2300 begins in block 2302, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2304, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the

BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2302 and 2304 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0435] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2306, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2306 may be made based on whether the apparatus is in a particular motion state (or lack thereof). For example, the apparatus may have one or more motion sensors that may indicate when the apparatus is experiencing accelerations consistent with motion. Alternatively or additionally, the apparatus may have a global positioning system receiver, a magnetometer, a gyroscope, or other type of sensor or sensors that may detect when the apparatus is in motion. If the apparatus appears, from the motion data provided by such sensors, to be substantially stationary with respect to a global frame of reference, then a decision may be made in block 2306 to use the BLE protocol to transmit the data. If the apparatus appears, from the motion data provided by such sensors, to be in motion, however, the BR/EDR protocol may be used to transmit the data.

[0436] The determination as to the motion state of the apparatus may be strict, e.g., any motion detected may be sufficient to cause the processor of the apparatus to determine that the apparatus is “in motion” for the purposes of Bluetooth protocol selection, or may be somewhat relaxed, e.g., to prevent sensor “noise” or incidental, localized movement from causing the processor of the apparatus to determine that the device is in motion. For example, a wristband-implemented biometric monitoring device may almost always technically be “in motion” due to minor movements of the arm on which it is worn—even when the wearer is sitting at a desk and typing on a computer keyboard. The apparatus processor(s) may determine that such minor movement does not constitute sufficient movement to warrant a determination that the apparatus is “in motion” for the purposes of Bluetooth protocol selection.

[0437] If the BR/EDR protocol is selected in block 2306, then the technique may proceed to block 2308 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2306, then the technique may proceed to block 2310 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2306 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2306 may be repeated for the additional data.

[0438] The motion state of the apparatus may provide a useful indicator of the environment within which the data transmission between the apparatus and the remote device is to occur. For example, if Bluetooth connections are established and the apparatus appears to be largely stationary, it may be reasonable to assume that the apparatus will remain stationary for some time and is thus less likely to be at a high risk of losing a Bluetooth connection (if the apparatus is in

motion, there may be a higher risk that the Bluetooth connection may be lost or interrupted, which may require that the data be re-transmitted and which may result in more power drain than is desirable).

[0439] FIG. 24 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether a user of the device appears to be asleep. Technique 2400 begins in block 2402, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2404, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2402 and 2404 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0440] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2406, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2406 may be made based on whether the apparatus indicates that a wearer of the apparatus is asleep. For example, the apparatus may have one or more motion sensors that may indicate when the apparatus is experiencing accelerations consistent with the person wearing the device being sleep. For example, accelerometers on an apparatus that is a wristband-type biometric monitoring device may indicate that the wristband biometric monitoring device is experiencing low levels of acceleration (such as accelerations consistent with occasional arm movements made during sleep) coupled with an overall apparatus orientation (as indicated with respect to the Earth's gravitational field) consistent with the arm on which the apparatus is worn being horizontal.

[0441] In some implementations, a user may indicate to the apparatus that they are going to sleep, e.g., by interacting with the apparatus (or by interacting with a remote device, e.g., a smartphone, to set a “sleep monitoring” mode. For example, in the Fitbit Ultra and One, the user may indicate that they are going to sleep by pressing the single user-interface button on such devices for approximately 2 seconds (the same action may be used after the user has woken up to indicate that the user is no longer asleep). In some such implementations, the same actions used to indicate that the user is going to sleep, e.g., pressing a user interface button, may also be used to indicate that the user is performing a particular activity, e.g., going for a run or bicycle ride, i.e., not sleeping. In such cases where a deliberate user interaction with the apparatus may be indicative of either “sleep” or “activity,” the apparatus may differentiate between “sleep” and “activity” by relying on secondary indicia, such as acceleration data. For example, if a user interacts with the apparatus to indicate either “sleep” or “activity” and the apparatus then detects accelerations consistent with walking, running, or other “active” movements, then the apparatus may determine that the wearer is not sleeping. By contrast, if the user interacts with the apparatus to indicate either “sleep” or “activity” and the apparatus then detects accel-

erations consistent with a sedentary position, then the apparatus may determine that the wearer is asleep.

[0442] In some implementations, the determination as to whether or not the wearer is sleeping may be based, or partially based, on the time of day. For example, during normal “sleep” hours, e.g., 9:00 PM to 6:00 PM, the apparatus may determine that the wearer is asleep. This determination may be additionally guided by other data, e.g., accelerations measured by the apparatus sensors may, as discussed above, be consistent with the wearer of the apparatus being asleep. In some such implementations, a deliberate user interaction of the wearer with the apparatus, e.g., pressing a user interface button as described above, may be interpreted as indicating “sleep” if it occurs during normal “sleep” hours and as “activity” if it occurs during normal “waking” hours. The ranges of time that correlate with normal “sleep” hours and normal “waking” hours may be set to a default standard, e.g., 9:00 PM to 6:00 AM local time, or may be adjusted based on the patterns of the wearer. For example, the wearer may be able to specify the hours that they are normally asleep (a person working the night shift may, for example, indicate to the apparatus that they normally sleep from 8:00 AM to 4:00 PM), or the apparatus may, over time, determine the wearer's normal sleep patterns from historical data (such determinations may also be made remotely, e.g., by a server that receives data from the apparatus, and then provided to the apparatus). Some or all of the above techniques for determining whether a wearer of an apparatus that functions as a biometric monitoring device is asleep or not may be used together in order to provide additional accuracy.

[0443] If the BR/EDR protocol is selected in block 2406, then the technique may proceed to block 2408 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2406, then the technique may proceed to block 2410 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2406 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2406 may be repeated for the additional data.

[0444] The sleep state of the wearer of the apparatus may provide a useful indicator of the environment within which the data transmission between the apparatus and the remote device is to occur. For example, if the wearer of the apparatus is asleep, it is reasonable to assume that the apparatus will remain stationary for some time and is thus less likely to be at a high risk of losing a Bluetooth connection and the slower and less power-intensive BLE protocol may be used (if the wearer is awake, there is a higher chance that the apparatus will be in motion and thus a higher risk that the Bluetooth connection may be lost or interrupted, which may require that the data be re-transmitted and which may result in more power drain than is desirable—the higher-bandwidth, higher-power BR/EDR protocol may be used in such cases).

[0445] FIG. 25 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether data is being sent from the common device to a remote device.

[0446] Technique 2500 begins in block 2502, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2504, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2502 and 2504 may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0447] As in the technique 1800, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block 2506, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block 2506 may be made based on whether the data is to be transmitted from the apparatus to the remote device (as opposed to from the remote device to the apparatus). If the data is being sent from the apparatus to the remote device, a decision may be made in block 2506 to use the BLE protocol. If the data is being sent from the remote device to the apparatus, then a decision may be made in block 2506 to use the BR/EDR protocol.

[0448] If the BR/EDR protocol is selected in block 2506, then the technique may proceed to block 2508 and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block 2506, then the technique may proceed to block 2510 and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in 2506 may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block 2506 may be repeated for the additional data.

[0449] The directionality of data transmission may be a useful indicator of the type of data being transmitted. For example, if the apparatus is a biometric monitoring device, then the vast bulk of the data transmitted from the apparatus to a remote device will likely be data collected from the sensors of the apparatus. Such sensor data may be not be time-critical, and thus may be a candidate for lower-bandwidth transmission. Such sensor data may also be continuous in nature, e.g., generated at small, regular intervals throughout the day, and the remote device that receives such data may still be able to provide substantial functionality even if the remote device does not the most up-to-date data, which may also suggest that such sensor data may be a candidate for lower-bandwidth transmission. By contrast, data sent from the remote device to the apparatus may, in some implementations, be application data or real-time notification data, and a higher bandwidth transmission of the data may thus be desirable.

[0450] For example, some apparatuses that are biometric monitoring devices may take the form of a smartwatch with integrated biometric monitoring sensors. Such an apparatus may have the ability to receive “apps” from a remote device. The “apps” may be programs that are not initially stored on the apparatus, but that are received from the remote device via the Bluetooth connection. Since programs typically do not function reliably until all of the program files are

accessible to the executing processor(s) from local memory, an app that is downloaded to the apparatus may be useless to the user of the apparatus until it is fully downloaded. It may thus be desirable to transmit such data from the remote device to the apparatus using a higher bandwidth connection since the wearer of the apparatus may typically wish to use the app as soon as possible after requesting that it be installed. In some cases, a remote device may transmit notifications to the apparatus, e.g., text messages, emails, pictures, etc., and the wearer of the apparatus may wish to see such notifications as soon as possible since they may be part of a real-time (or near-real-time) conversation with another person.

[0451] Another aspect of transmitting an app is that such transmission is typically part of a single transaction, e.g., “installing” the app. Once the app is installed, there may be periodic and infrequent updates of the app that need to be transmitted and installed, but, by and large, the app does not need to be re-transmitted. Due to the size of apps, transmitting an app over the Bluetooth connection may take some time, introducing a higher risk of the Bluetooth connection being interrupted (and increasing the possibility that the app data will need to be re-transmitted, which consumes further power) as compared with the transmission of data generated by sensors on the apparatus, which may generally take the form of an ongoing stream of small transactions that produce a constant, but low-level, stream of data that may be transmitted in small, discrete packets in a relatively continuous manner. If such a small transaction is interrupted due to Bluetooth connection loss, the power that is wasted due to the interrupted transmission is relatively small compared to that which may be wasted for larger transmissions such as apps.

App Data	Sensor Data
Sporadic transmission, typically in response to user request	Largely continuous transmission, typically independent of user interaction
Typically requires complete transmission of app before app can be executed on apparatus	Partial data or reduced resolution data transmission may still be useable by remote device.
Data size for single transaction is typically large.	Data size for single transaction is typically small.

[0452] The differences between app data and sensor data discussed above may also be relevant in the context of FIGS. 20 and 21, e.g., when the data itself is evaluated to determine if BR/EDR or BLE is to be used to transmit it.

[0453] FIG. 26 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on what type of remote device is in communication with the common device.

[0454] Technique 2600 begins in block 2602, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block 2604, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks 2602 and 2604 may

be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0455] As in the technique **1800**, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block **2606**, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block **2606** may be made based on whether the remote device is a cell phone, smartphone, or tablet (or, in some implementations, some other form of personal portable communications device). If the remote device is a cell phone, smartphone, or tablet, a decision may be made in block **2606** to use the BLE protocol. If the remote device is not a cell phone, smartphone, or tablet, then a decision may be made in block **2606** to use the BR/EDR protocol.

[0456] If the BR/EDR protocol is selected in block **2606**, then the technique may proceed to block **2608** and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block **2606**, then the technique may proceed to block **2610** and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in **2606** may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block **2606** may be repeated for the additional data.

[0457] Cell phones, smartphones, and tablets are all highly portable devices and thus have a high likelihood of being carried with a person, even if the person is moving (this is especially true of cell phones and smartphones). Moreover, if a biometric monitoring device has a Bluetooth connection to such remote devices, it is highly likely that the remote device belongs to the same person as does the biometric monitoring device. In such cases, there is a higher probability that both the biometric monitoring device and the remote device may travel together with the owner—a Bluetooth connection between the biometric monitoring device and the remote device in these cases is unlikely to be interrupted due to the continued close proximity of the remote device to the apparatus, and BLE may be used with a reasonable expectation that the Bluetooth connection will remain intact.

[0458] FIG. 27 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on whether a vehicle-mounted Bluetooth device is in range.

[0459] Technique **2700** begins in block **2702**, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block **2704**, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks **2702** and **2704** may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0460] As in the technique **1800**, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to

the remote device, from the remote device to the apparatus, or both. In block **2706**, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block **2706** may be made based on the apparatus is within range of a vehicle-mounted Bluetooth device. For example, many newer vehicles include built-in speakerphone systems that can communicate with a person's cell phone. If the apparatus detects that such a vehicle-mounted Bluetooth device is within range (or, in some implementations, is within range and has a sufficiently high signal strength, e.g., a signal strength commensurate with the signal strength typically experienced when the apparatus is within the interior of the vehicle), then a determination may be made to use the BLE protocol. If no vehicle-mounted Bluetooth device is detected by the apparatus, then the apparatus may use the BR/EDR protocol. It is to be noted that the vehicle-mounted Bluetooth device may be different from the remote device.

[0461] If the BR/EDR protocol is selected in block **2706**, then the technique may proceed to block **2708** and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block **2706**, then the technique may proceed to block **2710** and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in **2706** may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block **2706** may be repeated for the additional data.

[0462] If a biometric monitoring device (or apparatus) is within range (or within range and detecting a signal strength above a certain threshold) of a vehicle-mounted Bluetooth device, there may be a high chance that the wearer of the biometric monitoring device is within the vehicle in question. If the wearer is within such a vehicle and there is a Bluetooth connection established between the biometric monitoring device and a remote device, there is an increased likelihood that the remote device is also in the vehicle and thus a decreased likelihood that the remote device will travel out of range of the biometric monitoring device. In some implementations, the biometric monitoring device may also determine how fast the biometric monitoring device is going, or whether the motions experienced by the biometric monitoring device are consistent with vehicular travel. For example, if a vehicle-mounted Bluetooth device is detected and the biometric monitoring device detects that it is traveling at 50 mph, then the biometric monitoring device may determine that the biometric monitoring device is in a vehicle traveling on a highway. Due to Bluetooth's limited range, it is unlikely that an existing Bluetooth connection would exist unless it was to a remote device that was also within the vehicle. Thus, it is safe to assume that the connection is unlikely to be interrupted (except, perhaps, once the vehicle slows to a stop, at which point the wearer may exit the vehicle while leaving the remote device within).

[0463] FIG. 28 depicts a flow diagram of an example technique of utilizing Bluetooth base rate/enhanced data rate or Bluetooth low-energy capability in a common device based on the length of time since one or more of the Bluetooth connections was most recently lost.

[0464] Technique **2800** begins in block **2802**, in which an apparatus having both BR/EDR and BLE functionality may establish a BR/EDR connection between itself and another, remote device. In block **2804**, the apparatus may establish a BLE connection between itself and the remote device—thus, the apparatus may have the option of utilizing either the BR/EDR connection or the BLE connection as potential data transmission paths between the apparatus and the remote device. It is to be understood that blocks **2802** and **2804** may be performed in the order shown, in reverse order, or wholly or partially simultaneously as well.

[0465] As in the technique **1800**, at some point, it may be desirable to transmit data, e.g., first data, between the apparatus and the remote device, e.g., from the apparatus to the remote device, from the remote device to the apparatus, or both. In block **1805**, the apparatus may receive information (for example, from a historical log maintained in a memory of the apparatus) regarding the length of time since a Bluetooth connection was most recently lost (BLE, BR/EDR, or both).

[0466] In block **2806**, a decision may be made as to whether to utilize the BR/EDR protocol or the BLE protocol to transmit the data. The decision in block **2806** may be made based on the length of time since the Bluetooth connection was most recently lost. For example, if a Bluetooth connection was last lost more than 1 hour ago, then it may be assumed that the Bluetooth connection is relatively stable and BLE may be selected (with the expectation that the slower data transmission speed as compared with BR/EDR does not give rise to an increased chance of data transmission interruption. In other implementations, a decision to use BLE may be made when the Bluetooth connection has most recently remained established for at least 5 minutes, 10 minutes, 15 minutes, 30 minutes, 60 minutes, 3 hours, 6 hours, 12 hours, 24 hours, or other periods.

[0467] If the BR/EDR protocol is selected in block **2806**, then the technique may proceed to block **2808** and the data may be transmitted using the BR/EDR protocol. If the BLE protocol is selected in block **2806**, then the technique may proceed to block **2810** and the BLE protocol may be used to transmit the data between the apparatus and the remote device. After data transmission occurs, the Bluetooth communications protocol selected in **2806** may be re-used for additional data, e.g., second data, third data, etc. Alternatively, a separate determination may be made as to whether to use the BR/EDR protocol or the BLE protocol to transmit the additional data, i.e., block **2806** may be repeated for the additional data.

[0468] It is to be understood that while each of the above examples has largely focused on basing the determination of whether to use the BR/EDR protocol or the BLE protocol on a single factor, such determinations may be based on combinations of such factors, or on a multi-level evaluation of such factors. For example, an apparatus may first determine that data is to be transmitted via the BR/EDR protocol based on the data being application data. However, the apparatus may then perform a second determination based on battery charge level—if the battery charge level is very low, then the second determination may, notwithstanding the first determination that BR/EDR should be used to transmit the data, cause the apparatus to utilize the BLE protocol to transmit the data. Such determinations may also be made simultaneously instead of sequentially. In some implementations, determinations to use the BR/EDR or BLE protocols based

on some factors may outweigh determinations to use the BR/EDR or BLE protocols based on other factors. For example, a low battery charge level may trump other factors and cause the BLE protocol to be used regardless of which protocol other factors may indicate should be used. In such implementations, the determination may be structured such that the determination is partially open-ended. For example, if battery charge level is low, this may mandate that the BLE protocol be used, regardless of what other factors may indicate. However, if battery charge level is high, use of the BR/EDR protocol may not be mandatory, i.e., other factors may modify the determination as to whether or not to use the BR/EDR protocol or the BLE protocol.

[0469] FIG. **29** depicts a flow diagram of an example technique involving using several criteria to determine whether Bluetooth base rate/enhanced data rate capability or Bluetooth low-energy capability in a common device should be used to transmit data. Technique **2900** starts in block **2902** (BLE and BR/EDR connections may have already been established earlier, as discussed with respect to the preceding figures, and first data may be ready to be transmitted between the apparatus having the BLE and BR/EDR capabilities and a remote device). In block **2902**, a decision may be made as to whether to utilize the BLE protocol based on whether the battery charge level is below a specified threshold. If so, then the technique may proceed to block **2912** (optionally) and then to block **2914**. In block **2912**, an existing BR/EDR connection may be suspended or turned off to force communications with a remote device to occur via the BLE protocol (if needed). In block **2914**, the BLE protocol may be used to transmit the first data between the apparatus and the remote device.

[0470] If it is determined in block **2902** that the battery charge level is greater than or equal to the specified threshold, then the technique may proceed to block **2904**, in which the first data may be evaluated to determine if it is an application or part of an application. If it is an application or part of an application, then the technique may proceed to block **2916**, in which the BR/EDR protocol may be used to transmit the first data. If the first data is not determined to be an application or part of an application, then the technique may proceed to block **2906**. In block **2906**, a determination may be made as to whether the user or wearer of the apparatus appears to be asleep. If the user or wearer appears to be asleep, then the technique may proceed to block **2912** or directly to block **2914** if block **2912** is omitted.

[0471] If the user or wearer is not determined in block **2906** to be asleep, the technique **2900** may proceed to block **2908**, where a determination may be made as to the amount of time that has passed since the most recent loss of either of the Bluetooth connections (it is to be understood that “loss,” in the context of this discussion and earlier discussions regarding Bluetooth protocol selection, refers to undeliberate loss—if the BR/EDR connection is intentionally turned off to force BLE use, this does not equate to a Bluetooth connection “loss” event). In block **2910**, the amount of time that has passed since the most recent Bluetooth connection loss may be compared against a second threshold; if the amount of time exceeds the second threshold, then the technique may proceed to block **2912** (or to block **2914** directly if block **2912** is omitted) and BLE may be used. If the amount of time does not exceed the second threshold, then the technique may proceed to block **2916** and BR/EDR may be used.

[0472] The above example is simply one example of using a multi-tiered approach to determine which Bluetooth protocol to use based on various criteria or factors. Other implementations may use a different combination or arrangement of operations consistent with the scope of this disclosure.

[0473] It is also to be understood that the techniques outlined above may be used with wireless communications protocols other than Bluetooth, and that implementations using such other wireless communications protocols are also within the scope of this disclosure. Generally speaking, such alternative wireless communications protocols may feature at least two protocols—one that is higher-bandwidth but that draws more power (in the Bluetooth context, this is the BR/EDR mode), and one that is lower-bandwidth and draws less power (in the Bluetooth context, this is the BLE mode). Although it is not strictly necessary, both protocols may utilize common hardware, e.g., antennas, receivers, etc., to conserve space, as is possible with Bluetooth implementations.

[0474] The concepts and examples discussed above with respect to Bluetooth protocol selection (or other similar wireless communications protocol selection) may be implemented using computer-executable instructions that are stored in a computer-readable memory. The instructions may be executed by a processor that is communicatively connected with the memory and that is configured to control which Bluetooth protocol (or other communications protocol) is used. Such instructions may be provided using any of a variety of programming languages, including, but not limited to, C++, Java, iOS, Android, etc. In some implementations, some or all of the instructions may be hard-coded into an application-specific integrated circuit (ASIC).

[0475] There are many concepts and embodiments described and illustrated herein. While certain embodiments, features, attributes, and advantages have been described and illustrated herein, it should be understood that many others, as well as different and/or similar embodiments, features, attributes and advantages are apparent from the description and illustrations. As such, the above embodiments are merely provided by way of example. They are not intended to be exhaustive or to limit this disclosure to the precise forms, techniques, materials and/or configurations disclosed. Many modifications and variations are possible in light of this disclosure. It is to be understood that other embodiments may be utilized and operational changes may be made without departing from the scope of the present disclosure. As such, the scope of the disclosure is not limited solely to the description above because the descriptions of the above embodiments have been presented for the purposes of illustration and description.

[0476] Importantly, the present disclosure is neither limited to any single aspect nor embodiment, nor to any combinations and/or permutations of such aspects and/or embodiments. Moreover, each of the aspects of the present disclosure, and/or embodiments thereof, may be employed alone or in combination with one or more of the other aspects and/or embodiments thereof. For the sake of brevity, many of those permutations and combinations will not be discussed and/or illustrated separately herein.

1. An apparatus comprising:

a first Bluetooth communications interface configured to provide communications via the Bluetooth Base Rate/Enhanced Data Rate (BR/EDR) protocol;

a second Bluetooth communications interface configured to provide Bluetooth communications via the Bluetooth Low-Energy (BLE) protocol;

two or more sensors, the two or more sensors including a motion sensor; and

a controller including at least one processor and a memory, wherein:

the at least one processor, the memory, the two or more sensors, the first Bluetooth communications interface, and the second Bluetooth communications interface are communicatively connected, and

the memory stores instructions for controlling the at least one processor to:

a) establish a first Bluetooth communications connection with a remote device external to the apparatus via the first Bluetooth communications interface,

b) establish a second Bluetooth communications connection with the remote device via the second Bluetooth communications interface,

c) select the second Bluetooth communications connection to transmit first data between the apparatus and the remote device according, at least in part, to a determination, based at least in part on data generated by the two or more sensors, that a wearer of the apparatus is asleep, and

d) utilize the second Bluetooth communications connection as selected in (c) to transmit the first data between the apparatus and the remote device.

2. The apparatus of claim 1, wherein:

the two or more sensors further include a heart rate sensor configured to generate heart rate data, and

the data generated by the two or more sensors includes heart rate data and motion data.

3. The apparatus of claim 2, wherein the heart rate data further includes heart rate variability data.

4. The apparatus of claim 1, wherein:

the two or more sensors further include an audio sensor configured to detect respiratory sounds of the wearer of the apparatus, and

the data generated by the two or more sensors includes audio data and motion data.

5. The apparatus of claim 4, wherein the audio data includes one or more of: data indicating breathing of the wearer of the apparatus and data indicating a breathing rate of the wearer of the apparatus.

6. The apparatus of claim 1, wherein:

the two or more sensors further include an optical reflectometer configured to detect respiration of the wearer of the apparatus, and

the data generated by the two or more sensors includes motion data and data generated by the optical reflectometer.

7. The apparatus of claim 1, wherein:

the two or more sensors further include a galvanic skin response sensor configured to detect the galvanic skin response of the wearer of the apparatus, and

the data generated by the two or more sensors includes galvanic skin response data and motion data.

8. The apparatus of claim 1, wherein:

the two or more sensors further include a first sensor configured to detect a skin temperature of the wearer of the apparatus, and

the data generated by the two or more sensors includes skin temperature data and motion data.

9. The apparatus of claim 8, wherein the first sensor is one of: a noncontact thermopile, a skin temperature sensor, and an optical sensor.

10. The apparatus of claim 1, wherein:

the two or more sensors further include an optical sensor configured to detect ambient light, and

the data generated by the two or more sensors includes ambient light data and motion data.

11. The apparatus of claim 1, wherein the motion sensor is one or more of: an accelerometer, a gyroscope, and a magnetometer.

12. The apparatus of claim 1, wherein the selection in (c) is further made according, at least in part, to information associated with data generated by the two or more sensors that indicates the apparatus is monitoring a sleep state of the wearer of the apparatus.

13. The apparatus of claim 1, wherein the selection in (c) is further made according, at least in part, to information indicating that the first data is data generated by the two one or more sensors.

14. The apparatus of claim 1, wherein the memory stores further instructions for controlling the at least one processor to deactivate the first Bluetooth communications connection when the first Bluetooth communications connection is not used to transmit data between the apparatus and the remote device and while the second Bluetooth communications connection is still established between the apparatus and the remote device.

15. The apparatus of claim 1, wherein:

the two or more sensors are configured to generate data regarding heart rate, heart rate variability, respiration rate, galvanic skin response, motion, skin temperature, and body temperature of the wearer of the apparatus, and

the data generated by the two or more sensors includes heart rate data, heart rate variability data, respiration rate data, galvanic skin response data, motion data, skin temperature data, and body temperature data.

16. A method comprising:

a) establishing a first Bluetooth communications connection between an apparatus and a remote device external to the apparatus via the first Bluetooth communications interface;

b) establishing a second Bluetooth communications connection between the apparatus and the remote device external to the apparatus via the second Bluetooth communications interface;

c) selecting the second Bluetooth communications connection to transmit first data between the apparatus and the remote device according, at least in part, to a determination, based at least in part on data generated by two or more sensors of the apparatus, that a wearer of the apparatus is asleep, wherein the two or more sensors include a motion sensor; and

d) utilizing the second Bluetooth communications connection as selected in (c) to transmit the first data between the apparatus and the remote device.

17. The method of claim 16, wherein:

the two or more sensors further include a heart rate sensor configured to generate heart rate data, and

the determination of (c) is further based, at least in part, on data generated by the two or more sensors that includes heart rate data and motion data.

18. The method of claim 16, wherein:

the two or more sensors further include an audio sensor configured to detect respiratory sounds of the wearer of the apparatus, and

the determination of (c) is further based, at least in part, on data generated by the two or more sensors that includes audio data and motion data.

19. The method of claim 16, wherein:

the two or more sensors further include an optical reflectometer configured to detect respiration of the wearer of the apparatus, and

the determination of (c) is further based, at least in part, on data generated by the two or more sensors that includes motion data and data generated by the optical reflectometer.

20. The method of claim 16, wherein:

the two or more sensors further include a galvanic skin response sensor configured to detect the galvanic skin response of the wearer of the apparatus, and

the determination of (c) is further based, at least in part, on data generated by the two or more sensors that includes skin temperature data and motion data.

* * * * *

专利名称(译)	使用蓝牙进行自适应数据传输		
公开(公告)号	US20190229802A1	公开(公告)日	2019-07-25
申请号	US16/258452	申请日	2019-01-25
[标]申请(专利权)人(译)	飞比特公司		
申请(专利权)人(译)	FITBIT INC.		
当前申请(专利权)人(译)	FITBIT INC.		
[标]发明人	PANTHER HEIKO GERNOT ALBERT PARK JAMES		
发明人	PANTHER, HEIKO GERNOT ALBERT PARK, JAMES		
IPC分类号	H04B7/26 A61B5/024 H04W4/02 A61B5/00 H04B5/00 H04B5/02 A61B5/11		
CPC分类号	H04B7/26 A61B5/02416 A61B5/02427 A61B5/02433 A61B5/02438 H04W4/027 A61B5/4812 A61B5/0002 H04B5/0031 H04B5/02 A61B5/1123 H04L67/12 H04B5/0075 H04M1/7253 H04M2250/02 H04W76/16 H04W76/14 H04W4/80		
优先权	61/948468 2014-03-05 US 61/752826 2013-01-15 US 61/662961 2012-06-22 US 61/830600 2013-06-03 US		
其他公开文献	US10700774		
外部链接	Espacenet USPTO		

摘要(译)

本文讨论了生物识别监测设备，包括可以在这种设备中实现的各种技术。另外，本文讨论了用于利用两个不同的蓝牙通信接口的技术，系统和装置，一个提供蓝牙经典（基本速率/增强数据速率）通信功能，一个提供蓝牙低能量通信功能，在公共设备中。技术，系统和装置可以基于各种标准选择使用特定的蓝牙接口。

